



RFQ # 67-0170
UC Hastings Classroom K Refresh
Questions + Answers
2/10/2017

Q1. Please provide CAD Drawings of the room, RCP and Rack Elevation.

A1. CAD drawings will be made available to the awarded vendor.

Q2. On Drawing page AV-600: clarify Wireless Video Receiver (mentioned in document "RFQ-67-0170-Attachment-5-Specifications" on Page 2, Section B.14)

A2. Owner provided and currently installed in the existing rack. AKG two channel

Q3. On Drawing page AV-600: What is Wireless Collaboration Vs. Video Receiver (mentioned in document "RFQ-67-0170-Attachment-5-Specifications" on Page 8, Section 2.3.B)

A3. Item 2.3B in the spec.

Q4. In document RFQ-67-0170-Attachment-5-Specifications" Page 2, Section B.11: please check and confirm that instead of "monitor Flat panel in instructor's desk" that "witness stand display" is the correct one.

A4. There are three flat panels in the presenter's desk. The Witness stand is separate and does have a separate monitor.

Q5. Sharp Display is discontinued, please check and provide a replacement. (mentioned in document "RFQ-67-0170-Attachment-5-Specifications" on Page 7, Section 2.2.B)

A5. Sharp changes their model numbers at the first of the year. Use the current model in the same size and series.

Q6. Please provide Rack model / part number.

A6. Rack is OFE and was onsite during the walk through.

Q7. Video DA, is not specified in list. Please check and advise. Is it OFE?

A7. Item E under 2.3.

Q8. Please confirm TX/RX for OFE Camera(s), are present and functioning properly?

A8. Yes



Q9. What is requested job delivery timing?

A9. Job start date in mid-May (pending room availability); must be completed by end of FY17, no later than June 30th.

Q10. What are custom back boxes, special plates needs?

A10. Most backboxes are installed and exiting. The custom mounts will be the flat panels in the custom furniture. That will be an onsite measure and configure.

Q11. Please check and advise: where does input 2 come from, in functional drawing (AV-600)? As well as output route.

A11. This is in the instructor presentation console and the route is through a floor box to the rack recessed into the front of the room.

Q12. Regarding ADA hearing assistance: one transmitter has been asked, with 2 antennas. Where is the second antenna going?

A12. Room coverage should be good from a rack face mount.

Q13. There are 6 receivers but only 2 ear pieces. Are there spare ear pieces in your existing stock? Please check and advise.

A13. Replace with the kit: **MV-ALS-SYS4 / MV-ALS-SYS4-D 4-user Stationary Assistive Listening System / Dante-enabled** Includes stationary transmitter, antenna, receivers, batteries, charger, microphone, neckloop, earphones, and ADA sign kit

Q14. Kramer SID-X2N is discontinued, please check and advise on new model number.

A14. That product set is still available, but it's prudent to not install and end of life product set. The new Product set would be the Transmitter (with three inputs): DIP20.... and the receiver with scaling is the VP427.

Q15. Please clarify any need for Wood Work? Any new Casework, Millwork or Furniture?

A15. The monitors in the casework may require some adjustment to the casework for a fit. There was some talk of changing the instructor's podium, so it will be good to inquire about that.

Q16. Will parking be provided; how many spots? Loading dock?



A16. We have a loading dock located at 200 McAllister. Street parking (meter) is available and also at the paid parking garage located at 376 Larkin, between McAllister and Golden Gate.

Q17. Will Builders Risk Insurance be required for the AV Contractor per sample agreement?

A17. Yes

Q18. Is Non-union site work OK? Is prevailing wage and/or certified payroll a requirement?

A18. No. Per the mandatory requirements, current and active CSLB license (appropriate classification for the work) for bidder and all subcontractors are required. Current and active DIR registration for bidder and all subcontractors are mandatory. The contract, once signed, will be registered with the PWC within 5 business days. Certified payroll compliance is between the vendor and State of California.

Q19. Please check and provide list of OFCI (owner furnished contract installed) items.

A19. Reused devices in the functional diagram are marked with an (E). Some significant reused devices like the video projector and also listed in the spec like 2.2 A "Reconnect Exiting". Refer to 2.5 for reused cameras. Anything not listed or shown as existing or reuse should be assumed to be provided. Any item that is in doubt should be listed as provided and installed with a note to indicate its being added to the list of device to provide a "complete and working system".

Substitutions should also be noted as substitutions.