

SIGN AND RETURN INSIDE YOUR SEALED BID

September 26, 2017

ADDENDUM #3

200 McAllister Street Infrastructure Improvement Project

ITB 78-0160

ITB 78-0160 is hereby amended as follows:

DUE DATE EXTENSION

Original due date: Wednesday, September 13, 2017, by 4:00 p.m.

1st Amendment due date: Wednesday, September 20, 2017, by 4:00 p.m.

2nd Amendment due date: Wednesday, September 27, 2017, by 4:00 p.m.

NEW DUE DATE: Wednesday, October 4, 2017, by 4:00 p.m.

ANSWERS TO REQUEST FOR INFORMATION

- "NO ELECTRICAL SPECS ON BID PACKAGE."
 A: See updated and additional electrical specifications dated 9.26.17 (zip file 8 attachments)
- "PER DRAWING E0.3 & E3.1, SHOWS A NEW FIRE ALARM PANEL BEING INSTALL, IS THIS PART OF THIS CONTRACT OR BEING DONE BY OTHERS? IF THIS IS PART OF THIS CONTRACT NEED SPECS AND DRAWINGS FOR FIRE ALARM SYSTEM."
 - A: The fire alarm panel is existing to remain. Scope of work is to connect the power supply to the generator distribution.
- "PER DRAWING E0.3. SHOWS A GENERATOR DISTRIBUITION PANEL BEING INSTALL, BUT THERES
 NO PANEL SCHEDULE ON DRAWING E.02. THIS PANEL IS NOT PART OF THE GENERATOR
 EQUIPMENT."
 - A: See revised drawing for added distribution panelboard schedule.
- "PER DRAWING E0.3. FEEDER SCHEDULE NOT SPECIFY FOR CONDUIT RUN FROM GENERATOR TO GENERATOR DISTRIBUITION PANEL"
 - A: Feeder should be F500 per table on the plan.

ITB 78-0160, Addendum #3 Issued September 26, 2017

ofte A:	ne living wall; detail 11 & 12/S1.1 show 4 connections vertically to the structure but how en do the connections from the living wall to the building occur along the wall?" The areas of structural connections for the proposed living wall are noted on Sheet S2.0 tails are shown on Sheet S1.1.
	nowledgement RETURN INSIDE YOUR SEALED BID
 Date	
Sincerely,	
•	ius – Purchasing & Procurement s College of the Law