



**UC HASTINGS**  
COLLEGE OF THE LAW  
EST. 1878

**Date: 10.27.20**  
**Addendum No. 2**  
**RFP #00-0013 Inspector of Record**  
**Revisions, Questions and Answers**

Revisions

---

Request for Proposal Document:

- Scope of Work, A. Background, Bullet Point 7 deleted in its entirety:
  - ~~High level review of permitted construction drawings and specifications for adequacy and completeness prior to start of construction.~~
- Scope of Work, A. Background, Bullet Point 16 is revised and amended to read as:

“Prepare a daily report recording to include the Inspector's time and activities on the project, Weather conditions, Nature and location of construction work being performed, and any tests and inspections that were performed, and by whom. This report shall be prepared for each normal workday or for each day on which the contractor or inspector performs work, and a copy shall be promptly sent to the CM and UCH.”

Redlined Prior Version:

- Prepare a daily report recording to include the Inspector's time and activities on the project, Weather conditions, Nature and location of construction work being performed, and any tests and inspections that were performed, and by whom, ~~approximate number of workers by trade, oral instructions and interpretations given by the Design Professionals, specific observations on results of oral instructions and interpretations, any occurrence of work which might result in a claim for a change in the contract sum or contract time, the names of visitors with their titles and the time and purpose of their visit (where you are aware of the presence of visitors).~~ This report shall be prepared for each normal workday or for each day on which the contractor or inspector performs work, and a copy shall be promptly sent to the CM and UCH.
- Scope of Work, A. Background, Bullet Point 25 is revised and amended to read as:

“Within 30 days after receiving a Notice To Proceed, provide a submittal of required inspections from all entities associated with the project, with the associated construction work being tested/inspected, and the number of expected occurrences/cycles/pours/etc., and list the company/agency performing the test/inspection, and work with GC to put in a grid/spread sheet for sequence, scheduling, and tracking. List testing/inspection dates that are in alignment with the GC schedule. Dates for the upcoming 3 weeks testing/inspections shall be monitored and updated daily. Dates for all future tests & inspections shall be updated monthly. Stay in daily communication with the GC to coordinate testing times, days, and schedule changes.”

Redlined Prior Version:

- Within 30 days after receiving a Notice To Proceed, provide a submittal of required inspections from all entities associated with the project, with the associated construction work being tested/inspected, and the number of expected occurrences/cycles/pours/etc., and list the company/agency performing the test/inspection, and work with GC to put in a grid/spread sheet for sequence, scheduling, and tracking. List testing/inspection dates that are in alignment with the GC schedule. Dates for the upcoming 3 weeks testing/inspections shall be monitored and updated daily. Dates for all future tests & inspections shall be updated monthly. Stay in daily communication with the GC to coordinate testing times, days, and schedule changes.

---

## Questions and Answers

---

Q1: What is the largest we can send or do you have a 'DropBox' type file storage which can store larger files?

A1: Main Proposal Document - The main proposal document must be emailed to Hastings in the manner described in the RFP document. Proposal Attachments - Proposers may include web links to cloud document storage sites such as DropBox, Box, OneDrive within the body of their proposals for large documents, exhibits and attachments. Hastings will use these web links to download the large documents for your bid file and for review. If you use a cloud document storage site to transmit your proposal's large documents please make sure that the documents, web link and storage site remain active for at least 30 days from the date that proposals are due. Alternatively, proposers may place their large documents, exhibits and attachments onto a thumb and/or flash drive and mail it to Hastings at Purchasing, 200 McAllister Street, San Francisco, CA 94102.

Q2: Who is the Director of Construction?

A2: This person will be an employee of UC Hastings, and a separate hiring search is currently underway.

Q3. What type of inspector licensing is required for this project? Is ICC commercial acceptable?

A3. The IOR(s) credentials for the project shall at a minimum be either:

- 1) OSHPD (Office of Statewide Health Planning and Development) Class A or B, or
- 2) DSA (Division of the State Architect) Class I or II.

Other certifications that may be considered, include:

- 1) City or County trained and certified or equivalent certifications such as ICC (International Code Council) Commercial Combination Inspector or demonstrated equal, or
- 2) be a licensed architect or registered engineer (both in California).

The certifications and credentials of IOR inspector(s) used on the project shall be provided in the bid proposal along with a copy to be maintained on site.

Q4. When do you expect that full-time IOR services will be needed?

A4. First mat pour (roughly June of 2021) is likely when full time on site IOR services will be needed. However intermittent inspections and other work listed in the IOR scope of work will be required to start much earlier than that. For example, some on site inspections will begin in January 2021 for temp shoring systems, and there will be IOR submittal preparation and document review taking place in December 2020.

Q5. What is the anticipated total construction cost for this project?

A5. \$226,000,000.00

Q6. Is there a page limit for proposals?

A6. No.

Q7. Is there a specific layout you would like featuring tab numbers?

A7. No specific layout featuring tab numbers is needed. However, provide your information in a clear and easy to navigate/understand way.

Q8. Exhibit D does not feature a monthly basis billing table or weekend and holiday sections. Would you like for us to create a new table?

A8. If your labor rates are different for work on weekends and holidays, please provide that rate information as well. You may use an additional Exhibit D Pricing Table marked as weekend and holiday rates.

Q9. Are you anticipating one IOR full-time or multiple IORs?

A9. Contractors/IOR firm is to recommend in their proposal the amount of labor necessary to complete the work. - UC Hastings plans to contract directly to 1 IOR firm (or IOR). This 1 IOR will be required to provide their services in a timely fashion as necessary to support the scope of work and construction schedule, including (but not limited to) expanding or reducing their staff as needed, without any delays to construction due to lack of IOR personnel.

Q10. Are there specific certifications you would prefer the IOR to have?

A10. See A3. Response above.

Q11. Under RFP Section Guidelines for Submission, Expertise, Bullet 4, can you please explain the request for limited representation of illustrative materials such as graphics and page setups?

A11. Proposers may provide as much documentation as they feel is sufficient to make a good "representation of illustrative materials such as graphics and page setups."

Q12. Is one Exhibit A reference check form required to be signed by another firm or previous client?

A12. Proposers are required to complete and return all of page one (1) (Part A & B) for each of their four (4) work/client references (Reference Check Form). The second page of the reference check form may be left incomplete as the form will be completed or confirmed by the prior client during the reference check phase should the proposer move to that phase.

Attachments

---

Attachment 1 - UC Hastings Construction Schedule dated 10/22/2020  
Attachment 2 – 3<sup>rd</sup> Party Testing and Inspection Draft Scope (Redacted)

X \_\_\_\_\_  
Bidder acknowledgement of  
SIGN AND RETURN WITH YOUR RFP RESPONSE

\_\_\_\_\_  
Name of authorized signer

\_\_\_\_\_  
Date

Sincerely,

Purchasing Department  
UC Hastings Law  
[purchasing@uchastings.edu](mailto:purchasing@uchastings.edu)

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1	1	Fri 4/24/20	7%	UC HASTINGS LAW 198 MCALLISTER CAMPUS HOUSING SF	730 days	Fri 4/24/20	Tue 3/7/23	
2	8071	Mon 9/14/20	100%	NOTICE TO PROCEED	1 day	Mon 9/14/20	Mon 9/14/20	
3	8072	Fri 4/24/20	47%	EXECUTIVE SUMMARY	737.88 days	Fri 4/24/20	Tue 3/7/23	
4	3	Wed 4/29/20	100%	PRECONSTRUCTION MILESTONES (BID & AWARD)	83 days	Wed 4/29/20	Thu 8/27/20	
5	4	Wed 4/29/20	100%	ISSUE 95% P+W CD BID PACKAGE	0 days	Wed 4/29/20	Wed 4/29/20	
6	5	Mon 5/4/20	100%	ISSUE BID FORMS & MEP 95% DOCUMENTS - BID AMENDMENT	0 days	Mon 5/4/20	Mon 5/4/20	5FS+24 hrs
7	6	Mon 6/1/20	100%	ISSUE BASE SHORING SCOPE DOCUMENTS - BID AMENDMENT	0 days	Mon 6/1/20	Mon 6/1/20	6FS+152 hrs
8	7	Mon 6/1/20	100%	DIVISION 1 COMMENTS DUE FROM GCS	0 days	Mon 6/1/20	Mon 6/1/20	7FF
9	8	Mon 6/8/20	100%	ISSUE CONTRACT VALUES & TERMS OF SUBCONTRACTS TO BE ASSIGNED TO GCS	0 days	Mon 6/8/20	Mon 6/8/20	8FS+40 hrs
10	9	Mon 6/8/20	100%	COMPLETE CONTRACT NEGOTIATIONS WITH ALL GCS	0 days	Mon 6/8/20	Mon 6/8/20	9FF
11	10	Fri 6/26/20	100%	GMP PROPOSALS DUE TO GREYSTAR & UC HASTINGS	0 days	Fri 6/26/20	Fri 6/26/20	10FS+112 hrs
12	11	Tue 6/30/20	100%	GC INTERVIEWS WITH GREYSTAR & UC HASTINGS	0 days	Tue 6/30/20	Tue 6/30/20	11FS+16 hrs
13	12	Thu 7/2/20	100%	GC SELECTION	0 days	Thu 7/2/20	Thu 7/2/20	12FS+16 hrs
14	13	Mon 7/6/20	100%	GMP REVIEW WITH GREYSTAR	0 days	Mon 7/6/20	Mon 7/6/20	13FS+8 hrs
15	14	Thu 8/27/20	100%	EXECUTE GMP PRIME CONTRACT	0 days	Thu 8/27/20	Thu 8/27/20	14FS+32 hrs
16	15	Wed 7/29/20	100%	FINANCIAL CLOSEOUT OF BOND SALE	0 days	Wed 7/29/20	Wed 7/29/20	15FS+104 hrs
17	16	Thu 7/30/20	100%	PLANNED ISSUANCE OF NOTICE TO PROCEED	0 days	Thu 7/30/20	Thu 7/30/20	16FS+8 hrs
18	19	Fri 5/15/20	100%	PRECONSTRUCTION MILESTONES (OTHER)	86 days	Fri 5/15/20	Fri 9/18/20	
19	20	Fri 5/15/20	100%	GC FEEDBACK REGARDING STEEL VS. PT GIRDERS	0 days	Fri 5/15/20	Fri 5/15/20	6FS+72 hrs
20	21	Wed 5/20/20	100%	PG&E POWER DISCONNECT ENGINEERING COMPLETE	0 days	Wed 5/20/20	Wed 5/20/20	19FS+24 hrs
21	22	Wed 5/20/20	100%	PG&E TEMP POWER DESIGN ENGINEERING COMPLETE	0 days	Wed 5/20/20	Wed 5/20/20	20FF
22	23	Fri 5/22/20	100%	TOWER CRANE PLACEMENT - PROPOSED LOCATIONS DUE TO GREYSTAR	0 days	Fri 5/22/20	Fri 5/22/20	21FS+16 hrs
23	24	Fri 5/22/20	100%	OFF HOURS WORK PLAN DUE TO GREYSTAR	0 days	Fri 5/22/20	Fri 5/22/20	22FF
24	25	Fri 5/22/20	100%	GCS TO CONFIRM PROPOSED 2500 AMP TEMP SERVICE	0 days	Fri 5/22/20	Fri 5/22/20	23FF
25	26	Fri 7/31/20	100%	UNIVERSITY TO CEASE USE OF 198 MCALLISTER	0 days	Fri 7/31/20	Fri 7/31/20	24,17FS+8 hrs
26	27	Fri 7/31/20	100%	UNIVERSITY TO COMPLETE REMOVAL OF NON-FIXED ITEMS FROM 198 MCALLISTER	0 days	Fri 7/31/20	Fri 7/31/20	25FF
27	28	Fri 9/18/20	100%	DISCONNECT EXISTING STEAM SYSTEM	0 days	Fri 9/18/20	Fri 9/18/20	26FS+8 hrs
28	29	Fri 9/18/20	100%	ADDITIONAL SOIL TESTING (IF REQUIRED)	0 days	Fri 9/18/20	Fri 9/18/20	27FF
29	30	Fri 9/18/20	100%	START POTHOLING IN EXISTING BASEMENT	0 days	Fri 9/18/20	Fri 9/18/20	28FF
30	18	Mon 9/14/20	100%	START OF FIBER BRIDGE WORK TO CONNECT 100 AND 200 MCALLISTER	0 days	Mon 9/14/20	Mon 9/14/20	29FF
31	31	Tue 9/8/20	11%	CONSTRUCTION MILESTONES	636 days	Tue 9/8/20	Tue 3/7/23	
32	32	Mon 9/14/20	100%	MOBILIZE PROJECT	0 days	Mon 9/14/20	Mon 9/14/20	2SS
33	2311	Mon 9/14/20	100%	START CORING INVESTIGATION	0 days	Mon 9/14/20	Mon 9/14/20	32SS,2
34	9919	NA	0%	ADDITIONAL SOIL TESTING RAMBOLL 4 BORINGS AT € PLAZA	0 days	Mon 10/26/20	Mon 10/26/20	
35	2312	Sat 10/17/20	100%	START NEIGHBORING PROTECTION	0 days	Sat 10/17/20	Sat 10/17/20	160SS
36	2414	NA	0%	INSTALL SITE FENCING IN LIVE LANE	0 days	Thu 10/29/20	Thu 10/29/20	41SF-1 day
37	9686	NA	0%	REMOVE LIVE LANE FENCING/RESTRIPE LANES	0 days	Fri 9/30/22	Fri 9/30/22	3560,3561
38	2413	NA	0%	ARBORIST/TREE SERVICE COMPANY PLUMB CUT TREE BRANCHES ALONG ST SIDE	0 days	Thu 10/29/20	Thu 10/29/20	41SF-1 day
39	8395	Tue 9/29/20	100%	BEACH TREES CUT DOWN/REMOVAL	0 days	Tue 9/29/20	Tue 9/29/20	
40	8394	NA	0%	CEREMONIAL GROUND BREAKING (LARGE EQUIPMENT REQUIRED)	0 days	Fri 10/30/20	Fri 10/30/20	
41	2400	NA	0%	START HARD DEMO	0 days	Fri 10/30/20	Fri 10/30/20	392SS
42	8393	NA	0%	DISCONNECT (2) EXISTING ELECTRICAL SERVICES (DATE PROVIDED BY PG&E)	0 days	Tue 12/15/20	Tue 12/15/20	41
43	33	NA	0%	START SHORING	0 days	Thu 1/21/21	Thu 1/21/21	407SS
44	2309	NA	0%	START CSM	0 days	Mon 3/8/21	Mon 3/8/21	424SS
45	2310	NA	0%	START TIEBACKS	0 days	Mon 3/15/21	Mon 3/15/21	438SS
46	2389	NA	0%	FIBER OPTIC CABLE INSTALLATION STARTS	0 days	Wed 10/21/20	Wed 10/21/20	190SS
47	2390	NA	0%	FIBER OPTIC CABLE INSTALLATION/TERMINATION/COMMISSIONING COMPLETE	0 days	Mon 11/9/20	Mon 11/9/20	230FF

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
48	2159	NA	0%	TEMPORARY POWER SERVICE ON	0 days	Thu 1/14/21	Thu 1/14/21	239FF
49	35	NA	0%	BUILDING MASS EX PAD COMPLETE	0 days	Tue 5/18/21	Tue 5/18/21	441FF
50	41	NA	0%	TOP OUT CONCRETE STRUCTURE	0 days	Thu 5/12/22	Thu 5/12/22	471FF
51	2161	NA	0%	ROOFING COMPLETE	0 days	Thu 8/4/22	Thu 8/4/22	3631,3580
52	7644	NA	0%	TCO - ACADEMIC	0 days	Thu 2/23/23	Thu 2/23/23	3899FF
53	7645	NA	0%	TCO - RESIDENTIAL	0 days	Tue 2/28/23	Tue 2/28/23	3900FF
54	10516	NA	0%	SUBSTANTIAL COMPLETION-ACADEMIC (GREYSTAR START FF&E)	0 days	Thu 3/2/23	Thu 3/2/23	52FS+5 days,1886
55	10515	NA	0%	SUBSTANTIAL COMPLETION-RESIDENTIAL (GREYSTAR START FF&E)	0 days	Tue 3/7/23	Tue 3/7/23	53FS+5 days,3133
56	51	Mon 9/14/20	100%	START ABATEMENT	0 days	Mon 9/14/20	Mon 9/14/20	3875S
57	53	NA	0%	FIRST TOWER CRANE IN USE HYDE ST	0 days	Mon 5/10/21	Mon 5/10/21	2515S
58	10480	NA	0%	FIRST TOWER CRANE REMOVED HYDE ST	0 days	Fri 10/7/22	Fri 10/7/22	255
59	10477	NA	0%	2ND TOWER CRANE IN USE MCALLISTER ST	0 days	Mon 7/12/21	Mon 7/12/21	258
60	10479	NA	0%	2ND TOWER CRANE REMOVED MCALLISTER ST	0 days	Fri 9/30/22	Fri 9/30/22	262
61	77	NA	0%	MAN/MATERIAL HOIST IN USE HYDE	0 days	Mon 11/29/21	Mon 11/29/21	293
62	10476	NA	0%	MAN/MATERIAL HOIST IN USE MCALLISTER	0 days	Fri 12/10/21	Fri 12/10/21	271
63	49	NA	0%	FINAL POUR LEVEL 3 DECK	0 days	Fri 11/26/21	Fri 11/26/21	469FF
64	61	NA	0%	START INSTALLATION OF EXTERIOR WALL PANELS	0 days	Tue 1/18/22	Tue 1/18/22	3469SS
65	59	NA	0%	START DRYWALL - ACADEMIC FLOORS	0 days	Tue 12/21/21	Tue 12/21/21	1773SS
66	37	NA	0%	START DRYWALL - RESIDENTIAL FLOORS	0 days	Wed 4/27/22	Wed 4/27/22	2189SS
67	39	NA	0%	START ELEVATOR INSTALLATION	0 days	Thu 3/17/22	Thu 3/17/22	3673SS
68	2162	NA	0%	CURTAINWALL COMPLETE	0 days	Thu 8/18/22	Thu 8/18/22	3425FF
69	2163	NA	0%	PG&E GREEN TAG-TOWER	0 days	Fri 9/23/22	Fri 9/23/22	1754
70	10481	NA	0%	MOCK UP UNIT COMPLETE	0 days	Tue 5/24/22	Tue 5/24/22	1899
71	65	NA	0%	MOBILIZE RESIDENTIAL PUNCH BY GREYSTAR	0 days	Tue 8/30/22	Tue 8/30/22	2215SS
72	10471	NA	0%	MOBILIZE ACADEMIC PUNCH BY GREYSTAR	0 days	Tue 3/1/22	Tue 3/1/22	1838SS
73	43	NA	0%	OBTAIN TEMP USE OF ELEVATORS	0 days	Thu 9/1/22	Thu 9/1/22	3690
74	45	NA	0%	MAJOR STARTUP, TESTING & INSPECTION	0 days	Mon 10/24/22	Mon 10/24/22	3850SS
75	10485	Tue 9/8/20	11%	PERMITS REQUIRED PRIOR TO MIESTONES	194 days	Tue 9/8/20	Fri 5/28/21	
76	10487	NA	0%	SHORING	0 days	Thu 1/21/21	Thu 1/21/21	4075S
77	10488	NA	0%	TIEBACKS	0 days	Mon 3/15/21	Mon 3/15/21	4385S
78	10489	NA	0%	STRUCTURE	0 days	Fri 5/28/21	Fri 5/28/21	4685S
79	10491	Thu 10/1/20	12%	TOWER CRANES	87 days	Thu 10/1/20	Thu 1/21/21	
80	10492	Thu 10/1/20	11%	TOWER CRANE # 1	75.88 days	Thu 10/1/20	Thu 1/21/21	
81	10493	Thu 10/1/20	100%	BG SEND TC LOGISTICS TO MORO	1 day	Thu 10/1/20	Thu 10/1/20	
82	10494	Tue 10/13/20	100%	BG SEND ALL MORO SPECS TO MALCOLM	1 day	Tue 10/13/20	Wed 10/14/20	83SF-1 day
83	10495	Thu 10/15/20	75%	MALCOLM ENGINEERES FOOTING FOR TOWER CRANE # 1 HYDE ST	10 days	Thu 10/15/20	Fri 10/30/20	84SF-1 day
84	10496	NA	0%	BG SUBMITS PACKAGE TO CAL OSHA & SFBDI	1 day	Mon 11/2/20	Tue 11/3/20	85SF-1 day
85	10497	NA	0%	CAL OSHA REVIEW/APPROVE	30 days	Wed 11/4/20	Fri 12/18/20	87SF-10 days
86	10498	NA	0%	SFBDI REVIEW/APPROVE	30 days	Wed 11/4/20	Fri 12/18/20	85SS
87	10499	NA	0%	MALCOLM PROCUREMENT CASINGS/PILES/STEEL	10 days	Tue 1/5/21	Wed 1/20/21	88SF-1 day
88	10500	NA	0%	MALCOLM MOBILIZE	0 days	Thu 1/21/21	Thu 1/21/21	407
89	10501	Tue 10/13/20	12%	TOWER CRANE # 2	46 days	Tue 10/13/20	Fri 12/18/20	
90	10502	Tue 10/13/20	100%	BG SEND ALL MORO SPECS TO EOR	1 day	Tue 10/13/20	Wed 10/14/20	82SS
91	10503	Thu 10/15/20	75%	EOB ENGINEERES FOOTING FOR TOWER CRANE # 2 MCALLISTER	10 days	Thu 10/15/20	Thu 10/29/20	90FS+1 day
92	10504	NA	0%	BG SUBMITS PACKAGE TO CAL OSHA	1 day	Mon 11/2/20	Tue 11/3/20	91FS+2 days
93	10505	NA	0%	CAL OSHA REVIEW/APPROVE	30 days	Wed 11/4/20	Fri 12/18/20	92FS+1 day
94	10506	NA	0%	SFBDI REVIEW/APPROVE	30 days	Wed 11/4/20	Fri 12/18/20	92FS+1 day

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
95	10507	Tue 9/8/20	0%	REQUIRED PRIOR TO STARTING HARD DEMO	47.88 days	Tue 9/8/20	Thu 11/12/20	
96	10508	NA	0%	HYDE ST BULBOUTS DEMO & REBUILT	10 days	Wed 10/28/20	Mon 11/9/20	97SF-1 day
97	10509	NA	0%	SFMTA RESTRIPE HYDE ST AND OR TEMPORAY TAPE STRIPING	2 days	Tue 11/10/20	Thu 11/12/20	392
98	10510	Tue 9/8/20	0%	SFMTA MEETING 9/8/20 @ 2:00PM DISCUSS LOGISTICS	0 days	Tue 9/8/20	Tue 9/8/20	
99	10511	Tue 9/8/20	0%	SFMTA REQUESTS	0 days	Tue 9/8/20	Tue 9/8/20	
100	10512	Tue 9/8/20	100%	HYDE ST & MCALLISTER INSTALL A NO LEFT TURN SIGNAL	0 days	Tue 9/8/20	Tue 9/8/20	
101	10513	Tue 9/8/20	10%	SFMTA WILL PROVIDE ENGINEERED RESTRIPING PLAN (DTBD)	0 days	Tue 9/8/20	Tue 9/8/20	
102	10514	Thu 9/10/20	100%	STP GRANTED FROM CITY FOR START OF FIBER OPTIC START	0 days	Thu 9/10/20	Thu 9/10/20	
103	79	Fri 4/24/20	84%	<b>CRITICAL PROCUREMENT</b>	131 days	Fri 4/24/20	Mon 10/26/20	
104	80	Fri 4/24/20	100%	<b>BID PACKAGE 1</b>	30 days	Fri 4/24/20	Fri 6/5/20	
105	81	Fri 4/24/20	100%	ISSUE BID PACKAGE 1	0 days	Fri 4/24/20	Fri 4/24/20	5
106	82	Fri 4/24/20	100%	SUBCONTRACTORS PREPARE, SUBMIT PROPOSALS	10 days	Fri 4/24/20	Thu 5/7/20	105
107	83	Fri 5/8/20	100%	ANALYZE PROPOSALS, REVIEW SHORTLIST	15 days	Fri 5/8/20	Fri 5/29/20	106
108	84	Mon 6/1/20	100%	PREPARE, SUBMIT OWNER AUTHORIZATION PACKAGE	5 days	Mon 6/1/20	Fri 6/5/20	107
109	85	Fri 6/5/20	100%	OWNER ISSUES AUTHORIZATIONS	0 days	Fri 6/5/20	Fri 6/5/20	108
110	88	Mon 6/8/20	100%	<b>SUBCONTRACTORS</b>	45 days	Mon 6/8/20	Mon 8/10/20	
111	89	Mon 6/8/20	100%	<b>DEMOLITION</b>	5 days	Mon 6/8/20	Fri 6/12/20	
112	90	Mon 6/8/20	100%	PREPARE, ISSUE LOI TO DEMOLITION SUBCONTRACTOR	5 days	Mon 6/8/20	Fri 6/12/20	109
113	91	Mon 6/8/20	100%	DEVELOP AND SUBMIT ENGINEERED DEMO PLAN	5 days	Mon 6/8/20	Fri 6/12/20	112SF+40 hrs
114	92	Mon 6/8/20	100%	<b>SHORING</b>	45 days	Mon 6/8/20	Mon 8/10/20	
115	93	Mon 6/8/20	100%	PREPARE, ISSUE LOI TO SHORING CONTRACTOR	5 days	Mon 6/8/20	Fri 6/12/20	109
116	94	Mon 6/15/20	100%	COMPLETE, SUBMIT SHORING DESIGN	20 days	Mon 6/15/20	Mon 7/13/20	115
117	95	Tue 7/14/20	100%	PROCURE, PREPARE, DELIVER SHORING STEEL	20 days	Tue 7/14/20	Mon 8/10/20	116
118	96	Mon 6/8/20	100%	<b>DEEP FOUNDATION</b>	40 days	Mon 6/8/20	Mon 8/3/20	
119	97	Mon 6/8/20	100%	OWNER RELEASES PILES ENGINEERING & DESIGN	5 days	Mon 6/8/20	Fri 6/12/20	109
120	98	Mon 6/15/20	100%	COMPLETE, SUBMIT PILE ENGINEERING	30 days	Mon 6/15/20	Mon 7/27/20	119
121	99	Tue 7/28/20	100%	PILE SUBMITTAL REVIEW & APPROVAL	5 days	Tue 7/28/20	Mon 8/3/20	120
122	100	Wed 7/1/20	100%	<b>TOWER CRANE</b>	5 days	Wed 7/1/20	Wed 7/8/20	
123	101	Wed 7/1/20	100%	OWNER SIGNS CRANE RENTAL START AGREEMENT	5 days	Wed 7/1/20	Wed 7/8/20	12
124	102	Mon 7/13/20	16%	<b>PERMITS</b>	73.88 days	Mon 7/13/20	Mon 10/26/20	
125	105	Thu 9/17/20	100%	SUBMIT SHORING DESIGN	1 day	Thu 9/17/20	Thu 9/17/20	116
126	104	Fri 9/18/20	13%	CITY REVIEW & COMMENT SHORING SUBMITTAL (DURATION ADEED TILL CITY #29 days	29 days	Fri 9/18/20	Mon 10/26/20	125
127	103	NA	0%	SHORING PERMIT	0 days	Mon 10/26/20	Mon 10/26/20	126,141SS
128	106	Mon 7/13/20	100%	ISSUE DEMOLITON PERMIT	0 days	Mon 7/13/20	Mon 7/13/20	113
129	10432	Wed 9/16/20	53%	<b>CDR</b>	27 days	Wed 9/16/20	Thu 10/22/20	
130	10436	Wed 9/16/20	100%	<b>CDR # 001</b>	1 day	Wed 9/16/20	Wed 9/16/20	
131	10433	Wed 9/16/20	100%	EXISTING FIBER LINE RELOCATION-SUBGRADE CONCRETE UNFORSEEN CONDITIO	1 day	Wed 9/16/20	Wed 9/16/20	
132	10434	Mon 9/21/20	25%	<b>CDR # 002</b>	0.88 days	Mon 9/21/20	Mon 9/21/20	
133	10435	Mon 9/21/20	25%	REVISED METAL FRAMED SKYLIGHT AND GLAZING SPECIFICATIONS	1 day	Mon 9/21/20	Mon 9/21/20	
134	10430	Mon 9/28/20	25%	<b>CDR # 002 R1</b>	0.88 days	Mon 9/28/20	Mon 9/28/20	
135	10431	Mon 9/28/20	25%	REVISED METAL FRAMED SKYLIGHT AND GLAZING SPECIFICATIONS		Mon 9/28/20		
136	10429	Mon 9/21/20	100%	<b>CDR # 003</b>	0.88 days	Mon 9/21/20	Mon 9/21/20	
137	10428	Mon 9/21/20	100%	FIBER LINE ON MCALLISTER-UNFORSEEN UTILITY OBSTRUCTIONS	1 day	Mon 9/21/20	Mon 9/21/20	
138	10439	Mon 10/12/...	100%	<b>CDR # 004</b>	0.88 days	Mon 10/12/20	Mon 10/12/20	
139	10438	Mon 10/12/...	100%	RFI # 143 SITE UTILITIES-FIBER OPTIC ROUTING CONFLICT WITH EXISTING BRICK	1 day	Mon 10/12/20	Mon 10/12/20	
140	10440	Mon 10/12/...	25%	<b>CDR # 005</b>	0.88 days	Mon 10/12/20	Mon 10/12/20	
141	10437	Mon 10/12/...	25%	RFI # 142 SITE UTILITIES-EXISTING PG&E NETWORK VAULT AND #7 VAULT ON H	1 day	Mon 10/12/20	Mon 10/12/20	

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
142	10528	Thu 10/22/20	25%	<b>CDR # 006</b>	1 day	Thu 10/22/20	Thu 10/22/20	
143	10529	Thu 10/22/20	25%	SCAFFOLD TRUSS INSTALL OVER HYDE ST PG&E VAULT	1 day	Thu 10/22/20	Thu 10/22/20	
144	10526	Thu 10/22/20	25%	<b>CDR # 007</b>	1 day	Thu 10/22/20	Thu 10/22/20	
145	10527	Thu 10/22/20	25%	ABATEMENT OF UNFORESEEN ASBESTOS CONTAINING FIREPROOFING ON 50 MCALLISTER BASEMENT BEAM	1 day	Thu 10/22/20	Thu 10/22/20	
146	107	Mon 9/14/20	6%	<b>CONSTRUCTION</b>	627 days	Mon 9/14/20	Tue 2/28/23	
147	108	Mon 9/14/20	28%	<b>GENERAL REQUIREMENTS</b>	588 days	Mon 9/14/20	Wed 1/4/23	
148	109	Mon 9/14/20	99%	<b>MOBILIZATION</b>	596.88 days	Mon 9/14/20	Wed 1/4/23	
149	110	NA	0%	DEMOBILIZE SITE	0 days	Wed 1/4/23	Wed 1/4/23	156,157,235,158,159
150	116	Mon 9/14/20	100%	MOBILIZE SITE	0 days	Mon 9/14/20	Mon 9/14/20	2
151	117	Mon 9/14/20	100%	COORDINATE TREE REMOVAL	5 days	Mon 9/14/20	Fri 9/18/20	154SS,156SS
152	119	Mon 9/21/20	100%	PROTECT CONCRETE, APPURTENANCES TO REMAIN	10 days	Mon 9/21/20	Fri 10/2/20	156SS+40 hrs,154
153	120	Mon 9/21/20	100%	COORDINATE, EXECUTE SALVAGE	10 days	Mon 9/21/20	Fri 10/2/20	154,152SS
154	118	Mon 9/14/20	100%	EXISTING CONDITIONS SURVEY	5 days	Mon 9/14/20	Fri 9/18/20	150SS,2SS
155	121	Mon 9/14/20	24%	<b>SITE STAGING</b>	596.88 days	Mon 9/14/20	Wed 1/4/23	
156	111	Mon 9/14/20	24%	INITIATE, MAINTAIN BUILD PUBLIC PROTECTION PLAN	588 days	Mon 9/14/20	Wed 1/4/23	150SS,2SS
157	112	Mon 9/14/20	24%	INITIATE, MAINTAIN BUILD SITE SAFETY PROGRAM	588 days	Mon 9/14/20	Wed 1/4/23	159SS
158	114	Mon 9/14/20	24%	INITIATE, MAINTAIN BUILD SITE TRAFFIC CONTROL PLAN	588 days	Mon 9/14/20	Wed 1/4/23	156SS
159	115	Mon 9/14/20	24%	INITIATE, MAINTAIN BUILD WASTE MANAGEMENT PROGRAM	588 days	Mon 9/14/20	Wed 1/4/23	158SS
160	2340	NA	0%	<b>NEIGHBOR INTERFACE &amp; PROTECTION (PROVIDED BY ALEX MEYER EMAIL 6/2/20)</b>	493.88 days	Sat 10/17/20	Fri 9/16/22	
161	2341	NA	0%	<b>AT BACK SIDE OF 277 GOLDEN GATE ADJACENT TO CONTINUUM ALLEY</b>	119.88 days	Fri 10/23/20	Fri 4/16/21	
162	2342	NA	0%	RE-ROUTING € CONDUITS FOR SECURITY CAMERA MOUNTED TO 277 GG	15 days	Fri 10/23/20	Thu 10/29/20	391SF-1 day
163	2343	NA	0%	MOVEMENT PLANTERS AWAY FROM WALLS	2 days	Tue 10/27/20	Thu 10/29/20	391SF-1 day
164	2344	NA	0%	PLYWOOD OR OTHER MEANS OF PROTECTION AT GRADE	5 days	Fri 10/23/20	Thu 10/29/20	391SF-1 day
165	2345	NA	0%	FULL TIME SPOTTER ON NEIGHBORING PROPERTY DURING DEMO OF PERIMETER	60 days	Fri 1/22/21	Fri 4/16/21	402SS
166	2346	NA	0%	OVERHEAD PROTECTION AT EGREES DOOR/TEMP FENCE & SCREENING AS	5 days	Fri 10/23/20	Thu 10/29/20	391SF-1 day
167	2347	NA	0%	POST DEMO INSTALL PLYWOOD BARRIER AT GRADE AT PERIMETER	5 days	Thu 1/14/21	Thu 1/21/21	402SF-1 day
168	2348	NA	0%	<b>AT ROOF OF 277 GOLDEN GATE</b>	8 days	Fri 1/8/21	Thu 1/21/21	
169	2349	NA	0%	INSTALL PLYWOOD BARRIER AT ROOF LEVEL PERIMETER OF 277 GG	5 days	Thu 1/14/21	Thu 1/21/21	402SF-1 day
170	2350	NA	0%	PLYWOOD BARRIER WILL LIKELY BE MOUNTED TO 198 MCALLISTER PROJECT SIDE OF 277 GG CONCRETE WALL AND CANTILIVERED UP	10 days	Fri 1/8/21	Thu 1/21/21	402SF-1 day
171	2351	NA	0%	PLYWOOD BARRIER DO NOT DAMAGE OR ANCHOR TO PARAPET CAP	0 days	Fri 1/8/21	Fri 1/8/21	170SS
172	2352	NA	0%	MISTERS MAY BE REQUIRED OFF PLYWOOD BARRIER € HOSE BIBS AT 277 GG TO BE USED RAINBIRD OR SIMILAR CONTROLLER FOR MISTERS TO BE	3 days	Sat 1/16/21	Thu 1/21/21	170FF
173	2353	NA	0%	<b>INSIDE GARAGE OF 277 GOLDEN GATE</b>	493.88 days	Sat 10/17/20	Fri 9/16/22	
174	2354	NA	0%	277 GG WOULD LIKE TWO EXHAUST FANS ADDED IN GARAGE INTO DUCT	10 days	Sat 10/17/20	Thu 10/29/20	391SF-1 day
175	2355	NA	0%	AFTER DEMO & STRUCTURE/SKIN IS COMPLETE PATCH AND PAINT SIDE OF	20 days	Fri 8/19/22	Fri 9/16/22	50,342S
176	2356	NA	0%	<b>AT 146 MCALLISTER</b>	60.88 days	Sat 10/17/20	Fri 1/15/21	
177	2357	NA	0%	INSTALL PLYWOOD BARRIER AT GRADE AT PERIMETER TO REMAIN DURING	10 days	Sat 10/17/20	Thu 10/29/20	391SF-1 day
178	2358	NA	0%	FULL TIME SPOTTER ON NEIGHBORING PROPERTY DURING DEMO OF PERIMETER	60 days	Fri 10/30/20	Fri 1/15/21	391SS
179	2339	Mon 9/14/20	58%	<b>OPTICAL FIBER CABLE INSTALL DAYS 1 - 10</b>	40.88 days	Mon 9/14/20	Mon 11/9/20	
180	4500	Mon 9/14/20	100%	MCALLISTER ST SAW CUT/TRENCH/INSTALL CONDUIT/INSPECTIONS & BACKFILL	15 days	Mon 9/14/20	Fri 10/2/20	102
181	2395	Mon 9/14/20	100%	HYDE ST SAW CUT/TRENCH/INSTALL CONDUIT/INSPECTIONS & BACKFILL	15 days	Mon 9/14/20	Fri 10/2/20	180FF,131SS,137SS,139SS
182	9666	Mon 10/5/20	100%	HYDE ST VENDER CHECKING FOR PROPER VAULT SIZE THEN RESUBMIT SMALL	2 days	Mon 10/5/20	Tue 10/6/20	181
183	9668	Wed 10/7/20	100%	INSTALL HYDE ST VAULT/CONDUIT CONNECTION TO VAULT	3 days	Wed 10/7/20	Fri 10/9/20	182
184	9667	Fri 10/2/20	100%	BG SENDS CUPERTINO'S ANCHORAGE DETAILS TO CLIENT FOR VERTICAL CONDUIT	1 day	Fri 10/2/20	Fri 10/2/20	
185	9669	Fri 10/2/20	100%	CLIENT NEEDS NEIGHBOR APPROVAL TO START WITH VERTICAL CONDUIT INSTALL	5 days	Fri 10/2/20	Fri 10/9/20	184



University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
186	9962	Mon 10/12/20	100%	CUPERTINO NEEDS TO PROVIDE DETAIL ANCHORAGE SUBMITTAL FOR CLIENT	2 days	Mon 10/12/20	Wed 10/14/20	185FS+1 day
187	9966	Wed 10/14/20	100%	CLIENT APPROVE CUPERTINO'S ANCHORAGE DETAILS	2 days	Wed 10/14/20	Thu 10/15/20	186FS-1 day
188	4501	Mon 10/19/20	15%	CUPERTINO START INSTALL VERTICAL BUILDING CONDUIT/PULL BOX AT ADJACENT	5 days	Mon 10/19/20	Fri 10/23/20	180,182,185FS+1 day,186,187
189	<b>2362</b>	<b>Wed 10/21/20</b>	<b>15%</b>	<b>PRE INSTALLATION DAY 1-2 (HYDE ST)</b>	<b>0.88 days</b>	<b>Wed 10/21/20</b>	<b>Wed 10/21/20</b>	
190	2361	Wed 10/21/20	15%	PRE-INSPECTION OF FIBER OPTIC CABLE FOR CONTINUITY & BE RECORDED	1 day	Wed 10/21/20	Wed 10/21/20	181,183FS+1 day,187,188SS+2
191	2360	Wed 10/21/20	15%	PULL MULE TAPE IN CONDUITS FOR INITIAL MEASUREMENT ADD EXTRA LE	1 day	Wed 10/21/20	Wed 10/21/20	190SS,181
192	<b>2365</b>	<b>NA</b>	<b>0%</b>	<b>INSTALLATION DAY 3-4-5</b>	<b>11.88 days</b>	<b>Fri 10/23/20</b>	<b>Mon 11/9/20</b>	
193	<b>2369</b>	<b>NA</b>	<b>0%</b>	<b>DAY 3 (HYDE ST)</b>	<b>0.88 days</b>	<b>Fri 10/23/20</b>	<b>Fri 10/23/20</b>	
194	2366	NA	0%	FIBER OPTIC REEL PLACED AT MCALLISTER SIDEWALK AT VAULT #1	1 day	Fri 10/23/20	Fri 10/23/20	190,191FS+1 day
195	2367	NA	0%	PULL CABLE FROM MCALLISTER VAULT #1 TO HYDE VAULT #2	1 day	Fri 10/23/20	Fri 10/23/20	194SS
196	2368	NA	0%	END OF DAY 3 CABLE WILL BE STORED/SECURED IN VAULTS #1 & #2	1 day	Fri 10/23/20	Fri 10/23/20	195SS
197	<b>2364</b>	<b>NA</b>	<b>0%</b>	<b>DAY 4 (MCALLISTER ST)</b>	<b>0.88 days</b>	<b>Mon 10/26/20</b>	<b>Mon 10/26/20</b>	
198	2363	NA	0%	CABLE LAYED ON SIDEWALK IN FIGURE EIGHTS REPEATEDLY BETWEEN V	1 day	Mon 10/26/20	Mon 10/26/20	196FS+1 day,180
199	2359	NA	0%	END OF DAY 4 CABLE WILL BE STORED/SECURED IN VAULTS #2 & #3	1 day	Mon 10/26/20	Mon 10/26/20	198SS
200	<b>2373</b>	<b>NA</b>	<b>0%</b>	<b>DAY 5</b>	<b>0.88 days</b>	<b>Tue 10/27/20</b>	<b>Tue 10/27/20</b>	
201	2372	NA	0%	AFTER REMOVING CABLE FROM VAULT # 3 CABLE WILL BE PULLED INTO	1 day	Tue 10/27/20	Tue 10/27/20	199,188FS+1 day
202	2371	NA	0%	AFTER CABLE PULLING FROM VAULT # 1 TO 200 MCALLISTER IS COMPLETE THEN SET UP FOR BACK PULL FROM VAULT #1 TO THE	1 day	Tue 10/27/20	Tue 10/27/20	201SS
203	<b>2377</b>	<b>NA</b>	<b>0%</b>	<b>DAY 6 TERMINATIONS AT 200 MCALLISTER</b>	<b>0.88 days</b>	<b>Wed 10/28/20</b>	<b>Wed 10/28/20</b>	
204	2378	NA	0%	TERMINATIONS AT 200 MCALLISTER WILL BE HOUSED IN A RACK-MOUNT	1 day	Wed 10/28/20	Wed 10/28/20	202
205	2379	NA	0%	TERMINATION TYPE FUSION SPLICE PIGTAIL LC,900UM LSZH FACTORY C	1 day	Wed 10/28/20	Wed 10/28/20	204SS
206	2380	NA	0%	CONNECTOR PANELS WILL BE LC DUPLEX	1 day	Wed 10/28/20	Wed 10/28/20	205SS
207	<b>2376</b>	<b>NA</b>	<b>0%</b>	<b>DAY 7 TERMINATIONS AT 100 MCALLISTER</b>	<b>0.88 days</b>	<b>Fri 10/30/20</b>	<b>Fri 10/30/20</b>	
208	2375	NA	0%	TERMINATIONS AT 100 MCALLISTER WILL BE HOUSED IN A WALL MOUNT	1 day	Fri 10/30/20	Fri 10/30/20	206FS+1 day
209	2374	NA	0%	TERMINATION TYPE WILL BE FUSION SPLICE PIGTAIL LC, 900UM LSZH W	1 day	Fri 10/30/20	Fri 10/30/20	208SS
210	2370	NA	0%	CONNECTOR PANELS WILL BE LC DUPLEX	1 day	Fri 10/30/20	Fri 10/30/20	209SS
211	<b>2386</b>	<b>NA</b>	<b>0%</b>	<b>DAY 8 TESTING</b>	<b>0.88 days</b>	<b>Mon 11/2/20</b>	<b>Mon 11/2/20</b>	
212	2385	NA	0%	PLEASE SEE POST INSTALLATION TESTING GUIDELINES	1 day	Mon 11/2/20	Mon 11/2/20	208,209,210FS+1 day
213	<b>2384</b>	<b>NA</b>	<b>0%</b>	<b>DAY 9 INSTALLATION AT 100 MCALLISTER</b>	<b>0.88 days</b>	<b>Wed 11/4/20</b>	<b>Wed 11/4/20</b>	
214	9942	NA	0%	INSTALL CABLE PULLING LINE THROUGH CONDUIT ON 5TH FLOOR AND RISER PATHWAY TO 3RD FLOOR IDF AND BASEMENT IDF	1 day	Wed 11/4/20	Wed 11/4/20	212FS+1 day
215	9943	NA	0%	FIBER OPTIC REEL WILL BE PLACED ON THE 5TH FLOOR HALLWAY NEAR	1 day	Wed 11/4/20	Wed 11/4/20	212FS+1 day
216	9944	NA	0%	PULL CABLE TO 4TH FLOOR THEN 3RD FLOOR IDF BY WAY OF RISER PATH	1 day	Wed 11/4/20	Wed 11/4/20	212FS+1 day
217	9941	NA	0%	PULL CABLE 4TH/3RD/2ND/1ST FLOORS THEN COMPLETEING PULL TO B	1 day	Wed 11/4/20	Wed 11/4/20	212FS+1 day
218	2383	NA	0%	ONCE INSTALLATION & TESTING IS COMPLETE CEI WILL ASSIST WITH COMMISSIONING OF NEW FIBER RUN FROM 200 MCALLISTER TO 100	1 day	Wed 11/4/20	Wed 11/4/20	212FS+1 day
219	9954	NA	0%	COMPLETE PULL BOTH SINGLE MODE FIBER RUNS	1 day	Wed 11/4/20	Wed 11/4/20	212FS+1 day
220	<b>9953</b>	<b>NA</b>	<b>0%</b>	<b>DAY 10 INSTALLATION AT 100 MCALLISTER</b>	<b>1 day</b>	<b>Wed 11/4/20</b>	<b>Thu 11/5/20</b>	
221	9955	NA	0%	PREPARE FIBER ENDS FOR FUSION SPLICING AT 5TH FLOOR, 3RD FLOOR	1 day	Wed 11/4/20	Thu 11/5/20	219
222	9957	NA	0%	TERMINATIONS AT 100 MCALLISTER 3RD FLOOR IDF WILL BE HOUSED I	1 day	Thu 11/5/20	Thu 11/5/20	221SS
223	9961	NA	0%	TERMINATIONS AT 100 MCALLISTER BASEMENT IDF WILL BE HOUSED I	1 day	Thu 11/5/20	Thu 11/5/20	221SS
224	9958	NA	0%	TERMINATION TYPE FUSION SPLICE PIGTAIL LC,900UM LSZH FACTORY C	1 day	Thu 11/5/20	Thu 11/5/20	221SS
225	9959	NA	0%	CONNECTOR PANELS WILL BE LC DUPLEX	1 day	Thu 11/5/20	Thu 11/5/20	221SS
226	<b>9950</b>	<b>NA</b>	<b>0%</b>	<b>TESTING DAY 11</b>	<b>0.88 days</b>	<b>Fri 11/6/20</b>	<b>Fri 11/6/20</b>	
227	9951	NA	0%	SEE POST INSTALLATION TESTING GUIDELINES	1 day	Fri 11/6/20	Fri 11/6/20	225
228	<b>9948</b>	<b>NA</b>	<b>0%</b>	<b>COMMISSIONING DAY 12</b>	<b>0.88 days</b>	<b>Mon 11/9/20</b>	<b>Mon 11/9/20</b>	

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
229	9949	NA	0%	ONCE INSTALLATION AND TESTING ARE COMPLETE CEI WILL THEN ASSIST WITH COMMISSIONING OF THE NEW FIBER RUN, FROM 200	1 day	Mon 11/9/20	Mon 11/9/20	227FS+1 day
230	9963	NA	0%	FIBER OPTIC CABLE INSTALLATION/TERMINATION/COMMISSIONING COM	1 day	Mon 11/9/20	Mon 11/9/20	229FF
231	<b>122</b>	<b>Tue 9/15/20</b>	<b>35%</b>	<b>TEMPORARY UTILITIES</b>	<b>532.88 days</b>	<b>Tue 9/15/20</b>	<b>Fri 10/7/22</b>	
232	<b>123</b>	<b>Tue 9/15/20</b>	<b>74%</b>	<b>TEMP WATER</b>	<b>532.88 days</b>	<b>Tue 9/15/20</b>	<b>Fri 10/7/22</b>	
233	124	Tue 9/15/20	25%	INSTALL TEMPORARY WATER SERVICE	5 days	Tue 9/15/20	Mon 9/21/20	150,2
234	125	Tue 9/22/20	75%	MAINTAIN TEMPORARY WATER SERVICE	520 days	Tue 9/22/20	Fri 9/30/22	233
235	113	Mon 10/3/22	25%	DISMANTLE TEMPORARY WATER SERVICE	5 days	Mon 10/3/22	Fri 10/7/22	234
236	<b>127</b>	<b>Tue 9/15/20</b>	<b>3%</b>	<b>TEMP POWER</b>	<b>529.88 days</b>	<b>Tue 9/15/20</b>	<b>Tue 10/4/22</b>	
237	128	Tue 9/15/20	100%	MOBILIZE ELECTRICAL (SILVERADO'S SUBCONTRACTOR)	0 days	Tue 9/15/20	Tue 9/15/20	238SS
238	130	Tue 9/15/20	25%	START INSTALL, INSPECT, ENERGIZE TEMP POWER SERVICE	94 days	Tue 9/15/20	Thu 1/14/21	150,2
239	2157	NA	0%	TEMPORARY POWER SERVICE ON	0 days	Thu 1/14/21	Thu 1/14/21	238FF
240	131	NA	0%	MAINTAIN, DISTRIBUTE TEMP POWER	350 days	Fri 1/15/21	Tue 6/7/22	238,239
241	132	NA	0%	INSTALL, MAINTAIN TEMPORARY LIGHTING	221 days	Tue 11/9/21	Tue 9/27/22	240SS,1715
242	133	NA	0%	DISMANTLE TEMP POWER SERVICE	5 days	Fri 9/2/22	Fri 9/9/22	1719,240
243	135	NA	0%	REMOVE TEMPORARY LIGHTING	5 days	Wed 9/28/22	Tue 10/4/22	241
244	<b>144</b>	<b>NA</b>	<b>0%</b>	<b>TOWER CRANES</b>	<b>458 days</b>	<b>Wed 2/24/21</b>	<b>Mon 11/28/22</b>	
245	<b>145</b>	<b>NA</b>	<b>0%</b>	<b>TOWER CRANE 1 HYDE ST</b>	<b>427.25 days</b>	<b>Wed 2/24/21</b>	<b>Mon 10/17/22</b>	
246	<b>10147</b>	<b>NA</b>	<b>0%</b>	<b>(HYDE ST)</b>	<b>52.13 days</b>	<b>Wed 2/24/21</b>	<b>Mon 5/10/21</b>	
247	<b>10148</b>	<b>NA</b>	<b>0%</b>	<b>FOUNDATION - TOWER CRANE #1 (HYDE ST SIDEWALK)</b>	<b>52 days</b>	<b>Wed 2/24/21</b>	<b>Mon 5/10/21</b>	
248	10149	NA	0%	ERRECT TOWER CRANE ANCHOR/STOOL BASE	1 day	Wed 2/24/21	Thu 2/25/21	324
249	10150	NA	0%	ERRECT TOWER CRANE HYDE ST SIDEWALK (RIG IN FRID NIGHT SAT/SUN)	2 days	Thu 4/29/21	Sun 5/2/21	248,324,250SF-1 day,416,439
250	10151	NA	0%	CERTIFY TOWER CRANE HYDE ST SIDEWALK	5 days	Mon 5/3/21	Mon 5/10/21	468SF-15 days
251	146	NA	0%	CRANE IN SERVICE - STRUCTURE HYDE	0 days	Mon 5/10/21	Mon 5/10/21	250FF
252	9930	NA	0%	TOWER CRANE #1 HYDE ST 6 MONTH CERTIFICATION (PROVIDE A BRIDGE FOR C	6 mons	Mon 5/10/21	Fri 10/22/21	251
253	9929	NA	0%	TOWER CRANE #1 HYDE ST 1 YEAR CERTIFICATION	12 mons	Mon 5/10/21	Fri 4/8/22	251
254	9932	NA	0%	TOWER CRANE #1 HYDE ST 18 MONTH CERTIFICATION	18 mons	Mon 5/10/21	Fri 9/23/22	251
255	148	NA	0%	DISMANTLE TOWER CRANE 1 HYDE	5 days	Fri 9/30/22	Fri 10/7/22	251,3561,3342
256	151	NA	0%	POUR CRANE 1 BLOCKOUTS	5 days	Fri 10/7/22	Mon 10/17/22	255
257	<b>153</b>	<b>NA</b>	<b>0%</b>	<b>TOWER CRANE 2 MCALLISTER ST</b>	<b>360 days</b>	<b>Mon 7/12/21</b>	<b>Mon 11/28/22</b>	
258	54	NA	0%	CRANE IN SERVICE - STRUCTURE MCALLISTER	0 days	Mon 7/12/21	Mon 7/12/21	525FF
259	9936	NA	0%	TOWER CRANE #2 MCALLISTER ST 6 MONTH CERTIFICATION (PROVIDE A BRIDGE FOR OSHA AT ONE OF THE TWO CRANES)	6 mons	Mon 7/12/21	Mon 12/27/21	258
260	9937	NA	0%	TOWER CRANE #2 MCALLISTER ST 1 YEAR CERTIFICATION	12 mons	Mon 7/12/21	Mon 6/13/22	258
261	9938	NA	0%	TOWER CRANE #2 MCALLISTER ST 18 MONTH CERTIFICATION	18 mons	Mon 7/12/21	Mon 11/28/22	258
262	74	NA	0%	DISMANTLE TOWER CRANE 2 MCALLISTER	5 days	Fri 9/23/22	Fri 9/30/22	3560,258,3261
263	<b>157</b>	<b>NA</b>	<b>0%</b>	<b>MANLIFTS</b>	<b>235.13 days</b>	<b>Fri 10/22/21</b>	<b>Fri 9/16/22</b>	
264	<b>162</b>	<b>NA</b>	<b>0%</b>	<b>MANLIFTS HYDE ST &amp; MCALLISTER</b>	<b>225.13 days</b>	<b>Fri 10/22/21</b>	<b>Fri 9/16/22</b>	
265	<b>6854</b>	<b>NA</b>	<b>0%</b>	<b>MCALLISTER ST MAN LIFT</b>	<b>230.13 days</b>	<b>Fri 10/22/21</b>	<b>Fri 9/9/22</b>	
266	9748	NA	0%	INSTALL PARTIAL LOADING DOCK RAISED PLATFORM/RAMP	5 days	Wed 11/10/21	Thu 11/18/21	271SF-5 days
267	9747	NA	0%	INSTALL POWER/DISCONNECT MAN LIFT	5 days	Wed 11/10/21	Thu 11/18/21	271SF-5 days
268	9746	NA	0%	FORM/REINF/POUR MAN LIFT PADS	3 days	Mon 11/15/21	Thu 11/18/21	271SF-5 days
269	9744	NA	0%	STRIP DECK L2 (MCALLISTER ST)	1 day	Fri 10/22/21	Fri 10/22/21	805SS
270	10473	NA	0%	SET MANLIFT	1 day	Fri 10/29/21	Fri 10/29/21	805,269
271	6855	NA	0%	INSTALL CERTIFY MANLIFT MCALLISTER	10 days	Mon 11/29/21	Fri 12/10/21	805SS,269SS,876,270
272	<b>9713</b>	<b>NA</b>	<b>0%</b>	<b>MCALLISTER ST MAN LIFT JUMPS (JUMPS START AT 5:00PM)</b>	<b>96.13 days</b>	<b>Fri 12/10/21</b>	<b>Fri 4/29/22</b>	
273	9715	NA	0%	MCALLISTER ML JUMPS TO L3	1 day	Fri 12/10/21	Fri 12/10/21	946

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
274	9719	NA	0%	MCALLISTER ML JUMPS TO L4	0 days	Mon 12/27/21	Mon 12/27/21	989FS+1 day
275	9720	NA	0%	MCALLISTER ML JUMPS TO L5	0 days	Thu 1/6/22	Thu 1/6/22	1032FS+1 day
276	9721	NA	0%	MCALLISTER ML JUMPS TO L6	0 days	Thu 1/20/22	Thu 1/20/22	1075FS+1 day
277	9722	NA	0%	MCALLISTER ML JUMPS TO L7	0 days	Tue 2/1/22	Tue 2/1/22	1118FS+1 day
278	9723	NA	0%	MCALLISTER ML JUMPS TO L8	1 day	Tue 2/15/22	Wed 2/16/22	1162
279	9724	NA	0%	MCALLISTER ML JUMPS TO L9	0 days	Mon 2/28/22	Mon 2/28/22	1206FS+1 day
280	9725	NA	0%	MCALLISTER ML JUMPS TO L10	0 days	Fri 3/11/22	Fri 3/11/22	1250FS+1 day
281	9726	NA	0%	MCALLISTER ML JUMPS TO L11	0 days	Thu 3/24/22	Thu 3/24/22	1294FS+1 day
282	9727	NA	0%	MCALLISTER ML JUMPS TO L12	0 days	Wed 4/6/22	Wed 4/6/22	1337FS+1 day
283	9728	NA	0%	MCALLISTER ML JUMPS TO L13	0 days	Mon 4/18/22	Mon 4/18/22	1381FS+1 day
284	9729	NA	0%	MCALLISTER ML JUMPS TO L14	0 days	Fri 4/29/22	Fri 4/29/22	1426FS+1 day
285	9730	NA	0%	Manlift Jump Roof + 2'-6"above structural deck (Install landing/ramp)	0 days	Fri 4/29/22	Fri 4/29/22	1426FS+1 day
286	6856	NA	0%	<b>DISMANTLE MANLIFT MCALLISTER ST</b>	5 days	Thu 9/1/22	Fri 9/9/22	3690
287	<b>6851</b>	<b>NA</b>	<b>0%</b>	<b>HYDE ST MAN LIFT</b>	<b>231.13 days</b>	<b>Thu 10/28/21</b>	<b>Fri 9/16/22</b>	
288	9751	NA	0%	INSTALL PARTIAL LOADING DOCK RAISED PLATFORM/RAMP	5 days	Thu 10/28/21	Thu 11/4/21	293SF-5 days
289	9752	NA	0%	INSTALL POWER/DISCONNECT MAN LIFT	5 days	Thu 10/28/21	Thu 11/4/21	293SF-5 days
290	9753	NA	0%	FORM/REINF/POUR MAN LIFT PADS	3 days	Mon 11/1/21	Thu 11/4/21	293SF-5 days
291	9745	NA	0%	STRIP DECK L2 HYDE ST	1 day	Tue 11/2/21	Tue 11/2/21	854SS
292	10474	NA	0%	SET MANLIFT (CRITICAL 5 1/2" DIMENSION FOR BENSEN)	1 day	Tue 11/9/21	Tue 11/9/21	854,291
293	163	NA	0%	INSTALL CERTIFY MANLIFT HYDE	10 days	Fri 11/12/21	Mon 11/29/21	854SS,291SS,925,292
294	<b>9718</b>	<b>NA</b>	<b>0%</b>	<b>HYDE ST MAN LIFT JUMPS (JUMPS START AT 5:00PM)</b>	<b>98.25 days</b>	<b>Thu 12/16/21</b>	<b>Wed 5/4/22</b>	
295	9731	NA	0%	ML JUMPS TO L3	0 days	Thu 12/16/21	Thu 12/16/21	967FS+1 day
296	9732	NA	0%	ML JUMPS TO L4	0 days	Tue 1/4/22	Tue 1/4/22	1012FS+1 day
297	9733	NA	0%	ML JUMPS TO L5	0 days	Mon 1/10/22	Mon 1/10/22	1053FS+1 day
298	9734	NA	0%	ML JUMPS TO L6	0 days	Tue 1/25/22	Tue 1/25/22	1096FS+1 day
299	9735	NA	0%	ML JUMPS TO L7	0 days	Fri 2/4/22	Fri 2/4/22	1139FS+1 day
300	9736	NA	0%	ML JUMPS TO L8	0 days	Fri 2/18/22	Fri 2/18/22	1183FS+1 day
301	9737	NA	0%	ML JUMPS TO L9	0 days	Thu 3/3/22	Thu 3/3/22	1227FS+1 day
302	9738	NA	0%	ML JUMPS TO L10	0 days	Wed 3/16/22	Wed 3/16/22	1271FS+1 day
303	9739	NA	0%	ML JUMPS TO L11	0 days	Tue 3/29/22	Tue 3/29/22	1315FS+1 day
304	9740	NA	0%	ML JUMPS TO L12	0 days	Mon 4/11/22	Mon 4/11/22	1358FS+1 day
305	9741	NA	0%	ML JUMPS TO L13	0 days	Thu 4/21/22	Thu 4/21/22	1403FS+1 day
306	9742	NA	0%	ML JUMPS TO L14	0 days	Wed 5/4/22	Wed 5/4/22	1448FS+1 day
307	9743	NA	0%	Manlift Jump Roof + 2'-6"above structural deck (Install landing/ramp)	0 days	Wed 5/4/22	Wed 5/4/22	1448FS+1 day
308	165	NA	0%	<b>DISMANTLE MANLIFT HYDE ST</b>	5 days	Fri 9/9/22	Fri 9/16/22	3690,286
309	<b>8420</b>	<b>Mon 9/14/20</b>	<b>6%</b>	<b>LAYOUT LOG (SURVEYORS)</b>	<b>542.13 days</b>	<b>Mon 9/14/20</b>	<b>Wed 10/26/22</b>	
310	<b>8421</b>	<b>Mon 9/14/20</b>	<b>100%</b>	<b>LAYOUT BLDG. ORIENTATION</b>	<b>5 days</b>	<b>Mon 9/14/20</b>	<b>Fri 9/18/20</b>	
311	8559	Mon 9/14/20	100%	LAYOUT BUILDING CORNERS & OFFSETS	5 days	Mon 9/14/20	Fri 9/18/20	150,2
312	<b>8422</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT CONTROL GRID LINES HYDE ST./GOLDEN GATE ST/MCALLISTER ST</b>	<b>6 days</b>	<b>Tue 1/12/21</b>	<b>Thu 1/21/21</b>	
313	8423	NA	0%	LAYOUT HYDE ST	5 days	Thu 1/14/21	Thu 1/21/21	407SF-1 day
314	8424	NA	0%	LAYOUT MCALLISTER ST	5 days	Tue 1/12/21	Wed 1/20/21	407SF-1 day
315	8501	NA	0%	LAYOUT GOLDEN GATE ST	5 days	Thu 1/14/21	Thu 1/21/21	407SF-1 day
316	<b>8428</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT CONTROL GRID LINES/BENCH MARK ON LAGGING WALLS</b>	<b>5 days</b>	<b>Fri 5/21/21</b>	<b>Fri 5/28/21</b>	
317	8429	NA	0%	Layout Control Grid Lines on Lagging/Bench Marks	1 day	Thu 5/27/21	Fri 5/28/21	468SF-1 day
318	8430	NA	0%	Check Subgrade Elevation	1 day	Fri 5/21/21	Mon 5/24/21	468SF-5 days
319	8431	NA	0%	Bench Mark Set on Lagging Walls	1 day	Thu 5/27/21	Fri 5/28/21	468SF-1 day
320	<b>8432</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT TOWER CRANES</b>	<b>110 days</b>	<b>Fri 1/22/21</b>	<b>Mon 6/28/21</b>	

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
321	<b>8502</b>	<b>NA</b>	<b>0%</b>	<b>TOWER CRANE # 1</b>	<b>24 days</b>	<b>Fri 1/22/21</b>	<b>Thu 2/25/21</b>	
322	8533	NA	0%	LAYOUT PILES/CASINGS	1 day	Fri 1/22/21	Fri 1/22/21	410SS
323	8532	NA	0%	LAYOUT EL.STEEL BEAM BASE	1 day	Mon 2/8/21	Mon 2/8/21	414SS
324	8562	NA	0%	LAYOUT EL. SHIM PLATES ON STEEL BEAM BASE	1 day	Wed 2/24/21	Wed 2/24/21	415
325	8531	NA	0%	PLUMB ANCHOR STOOL BASE	1 day	Thu 2/25/21	Thu 2/25/21	248SS
326	<b>8535</b>	<b>NA</b>	<b>0%</b>	<b>TOWER CRANE # 2</b>	<b>2.88 days</b>	<b>Thu 6/24/21</b>	<b>Mon 6/28/21</b>	
327	8433	NA	0%	LAYOUT ON Water Proofing Rat Slab (NO PAINT)	1 day	Thu 6/24/21	Thu 6/24/21	514SS
328	8434	NA	0%	Plumb Anchor Stool Base	1 day	Mon 6/28/21	Mon 6/28/21	519SS
329	<b>8538</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT ON RAT SLABS</b>	<b>33.88 days</b>	<b>Fri 6/4/21</b>	<b>Wed 7/21/21</b>	
330	8539	NA	0%	MAT #1	1 day	Fri 6/4/21	Fri 6/4/21	477SS
331	8540	NA	0%	MAT #2	1 day	Wed 6/23/21	Thu 6/24/21	493SS
332	8541	NA	0%	MAT #3	1 day	Mon 6/28/21	Tue 6/29/21	528SS
333	8542	NA	0%	MAT #4	1 day	Tue 7/20/21	Wed 7/21/21	543SS
334	<b>8537</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT ON RAT SLAB WATERPROOFING (NO PAINT)</b>	<b>32 days</b>	<b>Fri 6/11/21</b>	<b>Tue 7/27/21</b>	
335	8543	NA	0%	MAT #1	1 day	Fri 6/11/21	Fri 6/11/21	481SS
336	8544	NA	0%	MAT #2	1 day	Tue 7/6/21	Tue 7/6/21	497SS
337	8545	NA	0%	MAT #3	1 day	Tue 7/6/21	Tue 7/6/21	532SS
338	8546	NA	0%	MAT #4	1 day	Tue 7/27/21	Tue 7/27/21	547SS
339	<b>8448</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT ON MAT'S</b>	<b>35 days</b>	<b>Mon 6/28/21</b>	<b>Mon 8/16/21</b>	
340	8449	NA	0%	MAT #1	1 day	Mon 6/28/21	Mon 6/28/21	489
341	8450	NA	0%	MAT #2	1 day	Mon 7/26/21	Mon 7/26/21	505
342	8451	NA	0%	MAT #3	1 day	Mon 8/2/21	Mon 8/2/21	539
343	8504	NA	0%	MAT #4	1 day	Mon 8/16/21	Mon 8/16/21	554
344	<b>8547</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT DECKS</b>	<b>166.13 days</b>	<b>Mon 9/13/21</b>	<b>Fri 5/13/22</b>	
345	<b>8452</b>	<b>NA</b>	<b>0%</b>	<b>Level 1</b>	<b>8 days</b>	<b>Mon 9/13/21</b>	<b>Wed 9/22/21</b>	
346	8506	NA	0%	DECK # 1	1 day	Mon 9/13/21	Mon 9/13/21	694
347	8505	NA	0%	DECK # 2	1 day	Wed 9/22/21	Wed 9/22/21	729
348	<b>8453</b>	<b>NA</b>	<b>0%</b>	<b>Level 2</b>	<b>8 days</b>	<b>Thu 10/21/21</b>	<b>Tue 11/2/21</b>	
349	8508	NA	0%	DECK # 1	0 days	Thu 10/21/21	Thu 10/21/21	804
350	8507	NA	0%	DECK # 2	1 day	Tue 11/2/21	Tue 11/2/21	853
351	<b>8454</b>	<b>NA</b>	<b>0%</b>	<b>Level 3</b>	<b>11 days</b>	<b>Mon 11/15/21</b>	<b>Tue 11/30/21</b>	
352	8511	NA	0%	DECK # 1	1 day	Tue 11/30/21	Tue 11/30/21	878
353	8512	NA	0%	DECK # 2	0 days	Mon 11/15/21	Mon 11/15/21	927
354	<b>8455</b>	<b>NA</b>	<b>0%</b>	<b>Level 5</b>	<b>5 days</b>	<b>Tue 12/28/21</b>	<b>Mon 1/3/22</b>	
355	8514	NA	0%	DECK # 1	1 day	Tue 12/28/21	Tue 12/28/21	991
356	8515	NA	0%	DECK # 2	0 days	Mon 1/3/22	Mon 1/3/22	1012
357	<b>8456</b>	<b>NA</b>	<b>0%</b>	<b>Level 7</b>	<b>3.13 days</b>	<b>Tue 1/25/22</b>	<b>Fri 1/28/22</b>	
358	8517	NA	0%	DECK # 1	1 day	Tue 1/25/22	Tue 1/25/22	1077
359	8518	NA	0%	DECK # 2	0 days	Fri 1/28/22	Fri 1/28/22	1098
360	<b>8570</b>	<b>NA</b>	<b>0%</b>	<b>Level 9</b>	<b>2.88 days</b>	<b>Fri 2/18/22</b>	<b>Tue 2/22/22</b>	
361	8571	NA	0%	DECK # 1	0 days	Fri 2/18/22	Fri 2/18/22	1164
362	8572	NA	0%	DECK # 2	1 day	Tue 2/22/22	Tue 2/22/22	1185
363	<b>8457</b>	<b>NA</b>	<b>0%</b>	<b>Level 11</b>	<b>4.13 days</b>	<b>Tue 3/15/22</b>	<b>Mon 3/21/22</b>	
364	8520	NA	0%	DECK # 1	1 day	Tue 3/15/22	Tue 3/15/22	1252
365	8521	NA	0%	DECK # 2	0 days	Mon 3/21/22	Mon 3/21/22	1273
366	<b>8459</b>	<b>NA</b>	<b>0%</b>	<b>Level 13</b>	<b>2 days</b>	<b>Tue 4/12/22</b>	<b>Thu 4/14/22</b>	
367	8523	NA	0%	DECK # 1	0 days	Tue 4/12/22	Tue 4/12/22	1339FS+1 day

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
368	8524	NA	0%	DECK # 2	1 day	Wed 4/13/22	Thu 4/14/22	1360FS+1 day
369	<b>8509</b>	<b>NA</b>	<b>0%</b>	<b>Level 14</b>	<b>5.88 days</b>	<b>Tue 4/19/22</b>	<b>Tue 4/26/22</b>	
370	8526	NA	0%	DECK # 1	1 day	Tue 4/19/22	Wed 4/20/22	1383
371	8527	NA	0%	DECK # 2	0 days	Tue 4/26/22	Tue 4/26/22	1405FS+1 day
372	<b>8460</b>	<b>NA</b>	<b>0%</b>	<b>Level 15 ROOF</b>	<b>7.13 days</b>	<b>Wed 5/4/22</b>	<b>Fri 5/13/22</b>	
373	8529	NA	0%	DECK # 1	1 day	Wed 5/4/22	Wed 5/4/22	1428FS+1 day
374	8530	NA	0%	DECK # 2	0 days	Fri 5/13/22	Fri 5/13/22	1451FS+1 day
375	<b>8499</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT SITEWORK</b>	<b>340.13 days</b>	<b>Thu 6/17/21</b>	<b>Wed 10/26/22</b>	
376	8500	NA	0%	HYDE ST. Layout 10'-0" offsets Sidewalk Curb Flow Finish EL.	1 day	Wed 10/19/22	Thu 10/20/22	3817SS
377	8549	NA	0%	MCALLISTER ST. Layout 10'-0" offsets Sidewalk Curb Flow Finish EL.	1 day	Tue 10/25/22	Wed 10/26/22	3801SS
378	8550	NA	0%	GOLDEN GATE ST. Layout 10'-0" offsets Sidewalk Curb Flow Finish EL.	1 day	Mon 9/26/22	Tue 9/27/22	3829SS
379	8554	NA	0%	LAYOUT & STAKE HYDE STORM & SEWER	5 days	Thu 6/17/21	Wed 6/23/21	456,452
380	8555	NA	0%	LAYOUT & STAKE MCALLISTER STORM & SEWER	5 days	Thu 6/24/21	Wed 6/30/21	379
381	8556	NA	0%	LAYOUT & STAKE MCALLISTER METERED WATER	5 days	Thu 7/1/21	Thu 7/8/21	380
382	8557	NA	0%	LAYOUT AND STAKE HYDRANT RELOCATION	5 days	Fri 7/9/21	Thu 7/15/21	381
383	8558	NA	0%	LAYOUT & STAKE FIRE SERVICE LATERALS	5 days	Fri 7/16/21	Thu 7/22/21	382
384	166	Mon 9/14/20	5%	SITEWORK	394.13 days	Mon 9/14/20	Mon 3/28/22	
385	<b>167</b>	<b>Mon 9/14/20</b>	<b>18%</b>	<b>DEMOLITION &amp; ABATEMENT</b>	<b>111 days</b>	<b>Mon 9/14/20</b>	<b>Fri 2/5/21</b>	
386	<b>168</b>	<b>Mon 9/14/20</b>	<b>44%</b>	<b>ABATEMENT</b>	<b>45.88 days</b>	<b>Mon 9/14/20</b>	<b>Mon 11/16/20</b>	
387	9693	Mon 9/14/20	100%	ROOF ABATEMENT	7 days	Mon 9/14/20	Tue 9/22/20	2SS
388	9694	Wed 9/23/20	100%	4TH FLOOR ABATEMENT	14 days	Wed 9/23/20	Sat 10/10/20	387
389	9695	Tue 10/6/20	25%	3RD FLOOR/3RD FLOOR MEZZANIE-ABATEMENT	19 days	Tue 10/6/20	Wed 10/28/20	388FS-5 days
390	9696	NA	0%	2ND FLOOR/2ND FLOOR MEZZANIE-ABATEMENT	19 days	Sat 10/24/20	Mon 11/16/20	389FS-4 days
391	<b>181</b>	<b>NA</b>	<b>0%</b>	<b>STRUCTURAL DEMO (INCLUDES SATURDAY'S /EXLUDES HOLIDAY SATURDAYS)</b>	<b>65.88 days</b>	<b>Fri 10/30/20</b>	<b>Fri 2/5/21</b>	
392	9704	NA	0%	PENTHOUSE DEMO	9 days	Fri 10/30/20	Mon 11/9/20	390SS+5 days
393	9705	NA	0%	ROOF DEMO	10 days	Tue 11/10/20	Sat 11/21/20	392
394	9706	NA	0%	4TH FLOOR DEMO	13 days	Mon 11/23/20	Wed 12/9/20	393
395	9701	NA	0%	3RD FLOOR/3RD FLOOR MEZZANIE-DEMO	13 days	Fri 12/4/20	Fri 12/18/20	394FS-5 days
396	9702	NA	0%	2ND FLOOR/2ND FLOOR MEZZANIE-DEMO	13 days	Wed 12/16/20	Mon 1/4/21	395FS-3 days
397	9703	NA	0%	1ST FLOOR/1ST FLOOR MEZZANIE-DEMO	10 days	Tue 1/5/21	Fri 1/15/21	396
398	10136	NA	0%	BASEMENT DEMO	4 days	Sat 1/16/21	Thu 1/21/21	397
399	10139	NA	0%	BELOW GRADE/SHORING/EXCAVATION-START DATE	0 days	Thu 1/21/21	Thu 1/21/21	398FF
400	10135	NA	0%	BUILD RUBBLE PILE FOR GG CUTOFF WALL	5 days	Sat 1/16/21	Fri 1/22/21	397
401	10000	NA	0%	EXPOSE, DEMO FTGS, TB'S IMPACTING SHORING	10 days	Mon 1/25/21	Fri 2/5/21	404,403,402,400
402	9708	NA	0%	COMPLETE STRUC DEMO - ROOF TO LEVEL 2	0 days	Thu 1/21/21	Thu 1/21/21	399SS
403	9709	NA	0%	COMPLETE AREA 1 - DEMO TO B01, LEAVE BRACE FRAME L01 TO B01	0 days	Thu 1/21/21	Thu 1/21/21	402FF
404	9710	NA	0%	COMPLETE AREA 2 - DEMO TO B01 LEAVING BRACE STRUCTURE	0 days	Thu 1/21/21	Thu 1/21/21	402FF,403FF
405	<b>185</b>	<b>NA</b>	<b>0%</b>	<b>SHORING/EXCAVATION/LAGGING/TIEBACKS/CUT OFFWALLS/PILES</b>	<b>294.13 days</b>	<b>Thu 1/21/21</b>	<b>Mon 3/28/22</b>	
406	<b>187</b>	<b>NA</b>	<b>0%</b>	<b>HYDE &amp; MCALLISTER SHORING LOCATIONS</b>	<b>125 days</b>	<b>Thu 1/21/21</b>	<b>Fri 7/16/21</b>	
407	34	NA	0%	MOBILIZE SHORING	0 days	Thu 1/21/21	Thu 1/21/21	117,127,311,402,403,404
408	<b>10025</b>	<b>NA</b>	<b>0%</b>	<b>TOWER CRANE #1 (HYDE ST SIDEWALK)</b>	<b>22 days</b>	<b>Thu 1/21/21</b>	<b>Tue 2/23/21</b>	
409	10026	NA	0%	BUILD RUBBLE PILE FOR MALCOM'S RIG TO INSTALL 4 CASINGS/PILES FOR	0 days	Thu 1/21/21	Thu 1/21/21	407FF
410	10027	NA	0%	LAYOUT PILES/CASINGS	1 day	Thu 1/21/21	Fri 1/22/21	409
411	10028	NA	0%	MOB DRILL EQUIPMENT	5 days	Thu 1/21/21	Thu 1/28/21	409
412	10029	NA	0%	INSTALL TOWER CRANE FOUNDATION CASINGS/PILES	5 days	Thu 1/28/21	Thu 2/4/21	410,411
413	10030	NA	0%	DEMOB DRILL EQUIPMENT	1 day	Thu 2/4/21	Fri 2/5/21	412
414	10031	NA	0%	LAYOUT EL.STEEL BEAM BASE	1 day	Fri 2/5/21	Mon 2/8/21	413

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
415	10032	NA	0%	INSTALL STEEL BEAM BASE STRUCTURE	10 days	Mon 2/8/21	Tue 2/23/21	413,414
416	10033	NA	0%	TOWER CRANE # 1 HYDE ST SIDEWALK FOUNDATION/BASE COMPLETE	0 days	Tue 2/23/21	Tue 2/23/21	415FF
417	<b>10088</b>	<b>NA</b>	<b>0%</b>	<b>SHORING LOCATION MAT # 1, MAT # 2</b>	<b>102.88 days</b>	<b>Fri 1/22/21</b>	<b>Wed 6/16/21</b>	
418	10036	NA	0%	INSTALL SOLDIER PILES MCALLISTER	5 days	Fri 1/22/21	Thu 1/28/21	407,311,403
419	10118	NA	0%	INSTALL SOLDIER PILES HYDE	10 days	Fri 1/29/21	Thu 2/11/21	418
420	10119	NA	0%	INSTALL LAGGING TO BASEMENT HYDE	15 days	Fri 1/29/21	Fri 2/19/21	419SS
421	10037	NA	0%	INSTALL LAGGING TO BASEMENT MCALLISTER	15 days	Fri 1/29/21	Fri 2/19/21	418
422	10061	NA	0%	DEMO BRACE FRAME, LEAVE CSM ZONE	5 days	Mon 2/22/21	Fri 2/26/21	421,420
423	10062	NA	0%	INSTALL CSM STAGING AREA	5 days	Mon 3/1/21	Fri 3/5/21	422
424	9978	NA	0%	INSTALL GOLDEN GATE CUTOFF WALL	5 days	Mon 3/8/21	Fri 3/12/21	423,401
425	10042	NA	0%	INSTALL GG TIEBACKS	5 days	Mon 3/15/21	Fri 3/19/21	424
426	190	NA	0%	REMOVE RUBBLE PILE, DEMO TO EXISTING B01	5 days	Mon 3/15/21	Fri 3/19/21	424
427	9980	NA	0%	REMOVE D LINE FOUNDATION	5 days	Mon 3/22/21	Fri 3/26/21	426,424
428	10063	NA	0%	DEMO SLAB FOR PILE TEST ZONE	10 days	Mon 3/1/21	Fri 3/12/21	422
429	10122	NA	0%	MOBILIZE MASS EXCAVATION	0 days	Fri 3/12/21	Fri 3/12/21	428
430	10123	NA	0%	MASS EX & LAG TO PAD - PILE TEST ZONE	10 days	Mon 3/15/21	Fri 3/26/21	429,428
431	10125	NA	0%	MOBILIZE DEEP FOUNDATION TEST PROGRAM	0 days	Mon 3/29/21	Mon 3/29/21	121,438,439SS,430
432	10127	NA	0%	TEST PROGRAM	20 days	Mon 3/29/21	Fri 4/23/21	121,465,438,439SS,430,431
433	10128	NA	0%	OFFSITE FABRICATION	30 days	Mon 4/26/21	Mon 6/7/21	432
434	10129	NA	0%	INSTALL STAGING AREA - DEEP FOUNDATION	5 days	Mon 4/26/21	Fri 4/30/21	432
435	10131	NA	0%	MOBILIZE PRODUCTION PILES	0 days	Fri 5/21/21	Fri 5/21/21	433SS+20 days,434,430
436	9981	NA	0%	INSTALL D LINE CUTOFF WALL	15 days	Mon 3/29/21	Fri 4/16/21	427
437	9982	NA	0%	INSTALL D LINE TIEBACKS - ROW 1	15 days	Mon 4/5/21	Fri 4/23/21	436FF+40 hrs,425
438	10069	NA	0%	INSTALL 1 LINE TIEBACKS - TEST ZONE	5 days	Mon 3/15/21	Fri 3/19/21	430SF+40 hrs
439	10070	NA	0%	INSTALL A LINE TIEBACKS	10 days	Mon 3/29/21	Fri 4/9/21	430
440	10049	NA	0%	REMOVE S.O.G., FOUNDATON MAT # 1, MAT # 2, MAT # 3	5 days	Mon 4/26/21	Fri 4/30/21	403,437
441	10094	NA	0%	MASS EX - MAT # 1, MAT # 2 & MAT # 3 (15 DAY DURATION INCLUDES 2 S	12 days	Mon 5/3/21	Tue 5/18/21	440
442	10095	NA	0%	INSTALL D LINE TIEBACKS - ROW 2	5 days	Wed 5/5/21	Tue 5/11/21	441SS+2 days
443	232	NA	0%	PRODUCTION PILES - MAT # 1 COMPLETE	5 days	Mon 5/24/21	Fri 5/28/21	433SS+20 days,434,435
444	10108	NA	0%	MOBILIZE STRUCTURAL CONCRETE	0 days	Fri 5/28/21	Fri 5/28/21	468SS
445	10046	NA	0%	INSTALL 6 LINE CUTOFF WALL MCALLISTER	10 days	Mon 4/19/21	Fri 4/30/21	436
446	10047	NA	0%	INSTALL 6 LINE TIEBACKS	20 days	Mon 5/3/21	Fri 5/28/21	445,436FF+40 hrs
447	231	NA	0%	PRODUCTION PILES - MAT # 2	12 days	Tue 6/1/21	Wed 6/16/21	443,442
448	<b>10089</b>	<b>NA</b>	<b>0%</b>	<b>SHORING LOCATION MAT # 3</b>	<b>37.88 days</b>	<b>Mon 5/3/21</b>	<b>Wed 6/23/21</b>	
449	9996	NA	0%	INSTALL 1/I LINE CUTOFF WALL	10 days	Mon 5/3/21	Fri 5/14/21	445
450	10057	NA	0%	DISMANTLE CSM STAGING AREA	2 days	Mon 5/17/21	Tue 5/18/21	449
451	9997	NA	0%	INSTALL 1 LINE TIEBACKS	5 days	Tue 6/1/21	Mon 6/7/21	449SF+40 hrs,446
452	10116	NA	0%	MASS EX - MCALLISTER MAT # 3	10 days	Mon 5/3/21	Fri 5/14/21	440
453	10110	NA	0%	PRODUCTION PILES - COMPLETE AT MAT # 3	5 days	Thu 6/17/21	Wed 6/23/21	447,452
454	<b>10112</b>	<b>NA</b>	<b>0%</b>	<b>SHORING LOCATION MAT # 4</b>	<b>33.88 days</b>	<b>Tue 6/1/21</b>	<b>Fri 7/16/21</b>	
455	10111	NA	0%	REMOVE S.O.G., FOUNDATION MAT # 4 (5 DAY DURATION INCLUDES 1 SA	4 days	Tue 6/1/21	Fri 6/4/21	450,451SS
456	10040	NA	0%	MASS EX - MCALLISTER, STAIR CORE 1 MAT # 4 (10 DAY DURATION INCLU	8 days	Mon 6/7/21	Wed 6/16/21	455
457	10113	NA	0%	EXCAVATION FOR TOWER CRANE FOOTING	3 days	Wed 6/16/21	Mon 6/21/21	456,452SS
458	233	NA	0%	PRODUCTION PILES - MAT # 4	14 days	Thu 6/24/21	Wed 7/14/21	453,456FS-1 day
459	10137	NA	0%	DEMOB DRILL RIG & EQUIPMENT	2 days	Wed 7/14/21	Fri 7/16/21	458
460	<b>2307</b>	<b>NA</b>	<b>0%</b>	<b>DEWATERING</b>	<b>259.13 days</b>	<b>Mon 3/15/21</b>	<b>Mon 3/28/22</b>	
461	2306	NA	0%	DEWATERING STARTS @ START OF FIRST ROW TIEBACKS	0 days	Mon 3/15/21	Mon 3/15/21	425SS

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
462	2305	NA	0%	DEWATERING DECOMMISSION STARTS (Per RFI #16 & #123 L12 Decks Poured)	0 days	Mon 3/28/22	Mon 3/28/22	1294,1315
463	<b>221</b>	<b>NA</b>	<b>0%</b>	<b>DEEP FOUNDATION</b>	<b>0 days</b>	<b>Mon 3/29/21</b>	<b>Mon 3/29/21</b>	
464	<b>222</b>	<b>NA</b>	<b>0%</b>	<b>TEST &amp; FABRICATION</b>	<b>0 days</b>	<b>Mon 3/29/21</b>	<b>Mon 3/29/21</b>	
465	223	NA	0%	MOBILIZE DEEP FOUNDATION TEST PROGRAM	0 days	Mon 3/29/21	Mon 3/29/21	121,438,439SS,430
466	<b>235</b>	<b>NA</b>	<b>0%</b>	<b>STRUCTURAL CONCRETE</b>	<b>243.13 days</b>	<b>Mon 5/24/21</b>	<b>Fri 5/13/22</b>	
467	10132	NA	0%	EARLY MOB STRUCTURE LAYOUT	0 days	Mon 5/24/21	Mon 5/24/21	468FS-5 days
468	236	NA	0%	MOBILIZE STRUCTURAL CONCRETE	0 days	Fri 5/28/21	Fri 5/28/21	443
469	50	NA	0%	PODIUM CONCRETE COMPLETE (EXCEPT TC BO'S)	0 days	Fri 11/26/21	Fri 11/26/21	925,876
470	241	NA	0%	FINAL DECK POUR	0 days	Tue 5/3/22	Tue 5/3/22	1448,1426
471	42	NA	0%	STRUCTURAL CONCRETE COMPLETE	0 days	Thu 5/12/22	Thu 5/12/22	470,1451,1429
472	248	NA	0%	MOBILIZE UG PLUMBING	0 days	Fri 5/28/21	Fri 5/28/21	443
473	<b>249</b>	<b>NA</b>	<b>0%</b>	<b>FONDATION LEVEL:</b>	<b>66 days</b>	<b>Fri 5/28/21</b>	<b>Wed 9/1/21</b>	
474	<b>6188</b>	<b>NA</b>	<b>0%</b>	<b>HYDE ST</b>	<b>42.13 days</b>	<b>Fri 5/28/21</b>	<b>Tue 7/27/21</b>	
475	<b>268</b>	<b>NA</b>	<b>0%</b>	<b>MAT POUR # 1 (HYDE ST)</b>	<b>22.13 days</b>	<b>Fri 5/28/21</b>	<b>Tue 6/29/21</b>	
476	269	NA	0%	EXCAVATION FOR MAT # 1/GRADE BEAMS	5 days	Fri 5/28/21	Fri 6/4/21	468,443
477	270	NA	0%	LAYOUT RAT SLAB MAT # 1	1 day	Fri 6/4/21	Fri 6/4/21	476FF+1 hr
478	271	NA	0%	<b>POUR RAT SLAB &amp; GRADE BEAMS</b>	1 day	Mon 6/7/21	Mon 6/7/21	477
479	272	NA	0%	INSTALL WATERPROOFING	3 days	Tue 6/8/21	Thu 6/10/21	478FS+1 hr
480	10461	NA	0%	POUR PROTECTION SLAB (POUR 5:00PM)	1.13 days	Thu 6/10/21	Thu 6/10/21	479FF
481	8564	NA	0%	LAYOUT ON WATERPROOFING-NO PAINT /LAYOUT ON PROTECTION SLAB OK PAINT	1 day	Fri 6/11/21	Fri 6/11/21	480
482	6179	NA	0%	MEPS INSTALL RAT SLAB ANCHORS/WP	2 days	Fri 6/11/21	Mon 6/14/21	479,481SS
483	273	NA	0%	INSTALL BOTTOM MAT REINFORCEMENT	5 days	Fri 6/11/21	Thu 6/17/21	479,481SS,250
484	274	NA	0%	MEPS ROUGH IN	5 days	Fri 6/18/21	Thu 6/24/21	483,482
485	275	NA	0%	INSTALL TOP MAT REINFORCEMENT	5 days	Fri 6/18/21	Thu 6/24/21	479,483,250
486	276	NA	0%	INSTALL DOWELS	1 day	Fri 6/25/21	Fri 6/25/21	485
487	277	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Fri 6/25/21	Fri 6/25/21	486FF
488	278	NA	0%	INSPECTION	1 day	Fri 6/25/21	Fri 6/25/21	487FF,484FF
489	279	NA	0%	<b>POUR MAT #1</b>	1 day	Sat 6/26/21	Sat 6/26/21	488FS+1 day
490	280	NA	0%	STRIP & CLEANUP	2 days	Mon 6/28/21	Tue 6/29/21	489
491	<b>281</b>	<b>NA</b>	<b>0%</b>	<b>MAT POUR #2:</b>	<b>29.13 days</b>	<b>Wed 6/16/21</b>	<b>Tue 7/27/21</b>	
492	282	NA	0%	EXCAVATION FOR MAT # 2/GRADE BEAMS	6 days	Wed 6/16/21	Thu 6/24/21	447
493	283	NA	0%	LAYOUT RAT SLAB MAT# 2	1 day	Wed 6/23/21	Thu 6/24/21	492FF
494	284	NA	0%	<b>POUR RAT SLAB &amp; GRADE BEAMS</b>	0 days	Fri 6/25/21	Fri 6/25/21	493FS+1 day
495	285	NA	0%	INSTALL WATERPROOFING	5 days	Mon 6/28/21	Fri 7/2/21	494,490SS
496	10462	NA	0%	POUR PROTECTION SLAB (POUR 5:00PM)	1 day	Thu 7/1/21	Fri 7/2/21	495FF
497	8565	NA	0%	LAYOUT ON WATERPROOFING-NO PAINT /LAYOUT ON PROTECTION SLAB OK PAINT	1 day	Tue 7/6/21	Tue 7/6/21	496
498	6181	NA	0%	MEPS INSTALL RAT SLAB ANCHORS/WP	2 days	Tue 7/6/21	Wed 7/7/21	495,497SS
499	286	NA	0%	INSTALL BOTTOM MAT REINFORCEMENT	5 days	Tue 7/6/21	Tue 7/13/21	495,498FS-1 day,485
500	6177	NA	0%	MEPS ROUGH IN	5 days	Wed 7/7/21	Wed 7/14/21	498
501	6182	NA	0%	INSTALL TOP MAT REINFORCEMENT	5 days	Tue 7/13/21	Tue 7/20/21	499
502	287	NA	0%	INSTALL DOWELS	1 day	Tue 7/20/21	Wed 7/21/21	499,501
503	6187	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	2 days	Mon 7/19/21	Wed 7/21/21	502FF
504	6186	NA	0%	INSPECTION	1 day	Wed 7/21/21	Wed 7/21/21	500FF,502FF,503SS
505	6185	NA	0%	<b>POUR MAT #2</b>	1 day	Fri 7/23/21	Sat 7/24/21	504FS+2 days
506	6184	NA	0%	STRIP & CLEANUP	2 days	Mon 7/26/21	Tue 7/27/21	505

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
507	<b>343</b>	<b>NA</b>	<b>0%</b>	<b>MCALLISTER ST</b>	<b>52 days</b>	<b>Mon 6/21/21</b>	<b>Wed 9/1/21</b>	
508	<b>344</b>	<b>NA</b>	<b>0%</b>	<b>FOUNDATION - TOWER CRANE #2:</b>	<b>14 days</b>	<b>Mon 6/21/21</b>	<b>Mon 7/12/21</b>	
509	345	NA	0%	EXCAVATE FOR TOWER CRANE FOOTING	0 days	Mon 6/21/21	Mon 6/21/21	457FF
510	346	NA	0%	LAYOUT RAT SLAB TOWER CRANE # 2	1 day	Mon 6/21/21	Tue 6/22/21	509
511	347	NA	0%	<b>POUR RAT SLAB</b>	1 day	Mon 6/21/21	Tue 6/22/21	510FF
512	355	NA	0%	SET FOOTING FORMWORK	1 day	Tue 6/22/21	Wed 6/23/21	511
513	348	NA	0%	INSTALL WATERPROOFING	1 day	Tue 6/22/21	Wed 6/23/21	511
514	8566	NA	0%	LAYOUT ON WATERPROOFING (NO PAINT)	1 day	Wed 6/23/21	Thu 6/24/21	513
515	349	NA	0%	INSTALL BOTTOM MAT REINFORCEMENT	1 day	Fri 6/25/21	Fri 6/25/21	513FS+1 day,514
516	350	NA	0%	MEPS ROUGH IN	1 day	Fri 6/25/21	Fri 6/25/21	515SS
517	351	NA	0%	FORM PEDESTALS	1 day	Thu 6/24/21	Fri 6/25/21	515FF
518	352	NA	0%	POUR PEDESTALS	1 day	Thu 6/24/21	Fri 6/25/21	517FF,512FF
519	354	NA	0%	SET CRANE BASE	1 day	Mon 6/28/21	Mon 6/28/21	518
520	356	NA	0%	INSTALL TOP MAT REINFORCEMENT	1 day	Tue 6/29/21	Tue 6/29/21	519,515,516
521	357	NA	0%	INSPECTION	1 day	Tue 6/29/21	Tue 6/29/21	520FF
522	358	NA	0%	<b>TOWER CRANE FOUNDATION POUR</b>	1 day	Mon 6/28/21	Tue 6/29/21	521FF
523	359	NA	0%	CURE	4 edays	Tue 6/29/21	Sat 7/3/21	522
524	360	NA	0%	SET TOWER CRANE	2 days	Sat 7/3/21	Sun 7/4/21	523
525	154	NA	0%	CERTIFY TOWER CRANE	5 days	Tue 7/6/21	Mon 7/12/21	524
526	<b>361</b>	<b>NA</b>	<b>0%</b>	<b>MAT POUR # 3</b>	<b>30.13 days</b>	<b>Tue 6/22/21</b>	<b>Tue 8/3/21</b>	
527	362	NA	0%	EXCAVATION MAT # 3/GRADE BEAMS	5 days	Tue 6/22/21	Tue 6/29/21	453FS-1 day
528	363	NA	0%	LAYOUT RAT SLAB MAT # 3	1 day	Mon 6/28/21	Tue 6/29/21	527FF
529	364	NA	0%	<b>POUR RAT SLAB &amp; GRADE BEAMS</b>	1 day	Wed 6/30/21	Wed 6/30/21	528
530	365	NA	0%	INSTALL WATERPROOFING	2 days	Thu 7/1/21	Fri 7/2/21	529,513
531	10463	NA	0%	POUR PROTECTION SLAB (POUR 5:00PM)	1 day	Thu 7/1/21	Fri 7/2/21	530FF
532	8567	NA	0%	LAYOUT ON WATERPROOFING-NO PAINT /LAYOUT ON PROTECTION SLAB	1 day	Fri 7/2/21	Mon 7/5/21	531
533	6189	NA	0%	MEPS INSTALL RAT SLAB ANCHORS/WP	2 days	Fri 7/2/21	Tue 7/6/21	530,532SS
534	366	NA	0%	INSTALL BOTTOM MAT REINFORCEMENT	5 days	Mon 7/19/21	Fri 7/23/21	530FF,533,525,501FS-2 days
535	367	NA	0%	MEPS ROUGH IN	5 days	Fri 7/23/21	Fri 7/30/21	534
536	368	NA	0%	INSTALL TOP MAT REINFORCEMENT	5 days	Fri 7/23/21	Fri 7/30/21	534
537	369	NA	0%	INSTALL DOWELS	1 day	Thu 7/29/21	Fri 7/30/21	536FF
538	370	NA	0%	INSPECTION	1 day	Thu 7/29/21	Fri 7/30/21	537FF,535FF
539	<b>371</b>	<b>NA</b>	<b>0%</b>	<b>POUR MAT # 3</b>	<b>1 day</b>	<b>Fri 7/30/21</b>	<b>Sat 7/31/21</b>	<b>538,506</b>
540	372	NA	0%	STRIP & CLEANUP	2 days	Mon 8/2/21	Tue 8/3/21	539
541	<b>373</b>	<b>NA</b>	<b>0%</b>	<b>MAT POUR # 4</b>	<b>25.13 days</b>	<b>Tue 7/13/21</b>	<b>Tue 8/17/21</b>	
542	374	NA	0%	EXCAVATION MAT # 4/GRADE BEAMS	5 days	Tue 7/13/21	Tue 7/20/21	458FS-1 day
543	375	NA	0%	LAYOUT RAT SLAB MAT # 4	0 days	Tue 7/20/21	Tue 7/20/21	542FF
544	<b>376</b>	<b>NA</b>	<b>0%</b>	<b>POUR RAT SLAB &amp; GRADE BEAMS</b>	<b>1 day</b>	<b>Wed 7/21/21</b>	<b>Wed 7/21/21</b>	<b>543</b>
545	377	NA	0%	INSTALL WATERPROOFING	3 days	Thu 7/22/21	Mon 7/26/21	544
546	10464	NA	0%	POUR PROTECTION SLAB (POUR 5:00PM)	1 day	Fri 7/23/21	Mon 7/26/21	545FF
547	8568	NA	0%	LAYOUT ON WATERPROOFING-NO PAINT /LAYOUT ON PROTECTION SLAB OK PAINT	1 day	Tue 7/27/21	Tue 7/27/21	546
548	6190	NA	0%	MEPS INSTALL RAT SLAB ANCHORS/WP	2 days	Tue 7/27/21	Wed 7/28/21	545,547SS
549	378	NA	0%	INSTALL BOTTOM MAT REINFORCEMENT	5 days	Thu 7/29/21	Wed 8/4/21	545,548,536FS-5 days,540FF
550	6192	NA	0%	MEPS ROUGH IN	5 days	Thu 8/5/21	Wed 8/11/21	549
551	6191	NA	0%	INSTALL TOP MAT REINFORCEMENT	6 days	Thu 8/5/21	Thu 8/12/21	549
552	379	NA	0%	INSTALL DOWELS	1 day	Fri 8/13/21	Fri 8/13/21	551



University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
553	6195	NA	0%	INSPECTION	1 day	Fri 8/13/21	Fri 8/13/21	550FF,552FF
554	<b>6196</b>	<b>NA</b>	<b>0%</b>	<b>POUR MAT # 4</b>	<b>1 day</b>	<b>Sat 8/14/21</b>	<b>Sat 8/14/21</b>	<b>553FF+1 day</b>
555	6194	NA	0%	STRIP & CLEANUP	2 days	Mon 8/16/21	Tue 8/17/21	554
556	<b>6199</b>	<b>NA</b>	<b>0%</b>	<b>PERIMETER WALLS (CIP):</b>	<b>47.88 days</b>	<b>Mon 6/28/21</b>	<b>Wed 9/1/21</b>	
557	<b>6200</b>	<b>NA</b>	<b>0%</b>	<b>ONE-SIDED WALL #1:</b>	<b>7.88 days</b>	<b>Mon 6/28/21</b>	<b>Wed 7/7/21</b>	
558	6201	NA	0%	INSTALL WATERPROOFING	2 days	Mon 6/28/21	Tue 6/29/21	489
559	6202	NA	0%	INSTALL REINFORCEMENT	2 days	Wed 6/30/21	Thu 7/1/21	558
560	6322	NA	0%	MEPS ROUGH IN	2 days	Wed 6/30/21	Thu 7/1/21	559FF
561	6203	NA	0%	SET ONE-SIDED WALL FORMWORK	2 days	Fri 7/2/21	Tue 7/6/21	559,560
562	6204	NA	0%	INSPECTION	1 day	Tue 7/6/21	Tue 7/6/21	561FF
563	6205	NA	0%	POUR WALL #1	1 day	Tue 7/6/21	Tue 7/6/21	562FF
564	6206	NA	0%	STRIP & CLEANUP	1 day	Tue 7/6/21	Wed 7/7/21	563
565	<b>6207</b>	<b>NA</b>	<b>0%</b>	<b>ONE-SIDED WALL #2:</b>	<b>8.88 days</b>	<b>Wed 6/30/21</b>	<b>Mon 7/12/21</b>	
566	6208	NA	0%	INSTALL WATERPROOFING	2 days	Wed 6/30/21	Thu 7/1/21	558
567	6209	NA	0%	INSTALL REINFORCEMENT	2 days	Fri 7/2/21	Tue 7/6/21	559,566
568	6324	NA	0%	MEPS ROUGH IN	2 days	Fri 7/2/21	Tue 7/6/21	567FF
569	6210	NA	0%	SET ONE-SIDED WALL FORMWORK	2 days	Wed 7/7/21	Thu 7/8/21	563,567,568,564SS
570	6211	NA	0%	INSPECTION	1 day	Thu 7/8/21	Thu 7/8/21	569FF
571	6212	NA	0%	POUR WALL #2	1 day	Fri 7/9/21	Fri 7/9/21	570
572	6213	NA	0%	STRIP & CLEANUP	1 day	Fri 7/9/21	Mon 7/12/21	571
573	<b>6214</b>	<b>NA</b>	<b>0%</b>	<b>ONE-SIDED WALL #3:</b>	<b>9.88 days</b>	<b>Fri 7/2/21</b>	<b>Thu 7/15/21</b>	
574	6215	NA	0%	INSTALL WATERPROOFING	2 days	Fri 7/2/21	Tue 7/6/21	566
575	6216	NA	0%	INSTALL REINFORCEMENT	2 days	Wed 7/7/21	Thu 7/8/21	567,574
576	6326	NA	0%	MEPS ROUGH IN	2 days	Wed 7/7/21	Thu 7/8/21	575FF
577	6217	NA	0%	SET ONE-SIDED WALL FORMWORK	2 days	Mon 7/12/21	Tue 7/13/21	571,575,576
578	6218	NA	0%	INSPECTION	1 day	Tue 7/13/21	Tue 7/13/21	577FF
579	6219	NA	0%	POUR WALL #3	1 day	Wed 7/14/21	Wed 7/14/21	578,572
580	6220	NA	0%	STRIP & CLEANUP	1 day	Thu 7/15/21	Thu 7/15/21	579
581	<b>6221</b>	<b>NA</b>	<b>0%</b>	<b>ONE-SIDED WALL #4:</b>	<b>9.88 days</b>	<b>Wed 7/7/21</b>	<b>Tue 7/20/21</b>	
582	6222	NA	0%	INSTALL WATERPROOFING	2 days	Wed 7/7/21	Thu 7/8/21	574
583	6223	NA	0%	INSTALL REINFORCEMENT	2 days	Fri 7/9/21	Mon 7/12/21	575,582
584	6328	NA	0%	MEPS ROUGH IN	2 days	Fri 7/9/21	Mon 7/12/21	583FF
585	6224	NA	0%	SET ONE-SIDED WALL FORMWORK	2 days	Thu 7/15/21	Fri 7/16/21	579,583,584
586	6225	NA	0%	INSPECTION	1 day	Fri 7/16/21	Fri 7/16/21	585FF
587	6226	NA	0%	POUR WALL #4	1 day	Mon 7/19/21	Mon 7/19/21	586,580
588	6227	NA	0%	STRIP & CLEANUP	1 day	Tue 7/20/21	Tue 7/20/21	587
589	<b>6228</b>	<b>NA</b>	<b>0%</b>	<b>ONE-SIDED WALL #5:</b>	<b>7.88 days</b>	<b>Mon 8/2/21</b>	<b>Wed 8/11/21</b>	
590	6229	NA	0%	INSTALL WATERPROOFING	2 days	Mon 8/2/21	Tue 8/3/21	582,539
591	6230	NA	0%	INSTALL REINFORCEMENT	2 days	Wed 8/4/21	Thu 8/5/21	583,590
592	6330	NA	0%	MEPS ROUGH IN	2 days	Wed 8/4/21	Thu 8/5/21	591FF
593	6231	NA	0%	SET ONE-SIDED WALL FORMWORK	2 days	Fri 8/6/21	Mon 8/9/21	587,591,592
594	6232	NA	0%	INSPECTION	1 day	Mon 8/9/21	Mon 8/9/21	593FF
595	6233	NA	0%	POUR WALL #5	1 day	Tue 8/10/21	Tue 8/10/21	594,588
596	6234	NA	0%	STRIP & CLEANUP	1 day	Wed 8/11/21	Wed 8/11/21	595
597	<b>6235</b>	<b>NA</b>	<b>0%</b>	<b>ONE-SIDED WALL #6:</b>	<b>8.88 days</b>	<b>Wed 8/4/21</b>	<b>Mon 8/16/21</b>	
598	6236	NA	0%	INSTALL WATERPROOFING	2 days	Wed 8/4/21	Thu 8/5/21	590
599	6237	NA	0%	INSTALL REINFORCEMENT	2 days	Fri 8/6/21	Mon 8/9/21	591,598

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
600	6332	NA	0%	MEPS ROUGH IN	2 days	Fri 8/6/21	Mon 8/9/21	599FF
601	6238	NA	0%	SET ONE-SIDED WALL FORMWORK	2 days	Wed 8/11/21	Thu 8/12/21	595,599,600
602	6239	NA	0%	INSPECTION	1 day	Thu 8/12/21	Thu 8/12/21	601FF
603	6240	NA	0%	POUR WALL #6	1 day	Fri 8/13/21	Fri 8/13/21	602,596
604	6241	NA	0%	STRIP & CLEANUP	1 day	Mon 8/16/21	Mon 8/16/21	603
605	<b>6242</b>	<b>NA</b>	<b>0%</b>	<b>ONE-SIDED WALL #7:</b>	<b>7.88 days</b>	<b>Mon 8/16/21</b>	<b>Wed 8/25/21</b>	
606	6243	NA	0%	INSTALL WATERPROOFING	2 days	Mon 8/16/21	Tue 8/17/21	598,554
607	6244	NA	0%	INSTALL REINFORCEMENT	2 days	Wed 8/18/21	Thu 8/19/21	599,606
608	6334	NA	0%	MEPS ROUGH IN	2 days	Wed 8/18/21	Thu 8/19/21	607FF
609	6245	NA	0%	SET ONE-SIDED WALL FORMWORK	2 days	Fri 8/20/21	Mon 8/23/21	603,607,608
610	6246	NA	0%	INSPECTION	1 day	Mon 8/23/21	Mon 8/23/21	609FF
611	6247	NA	0%	POUR WALL #7	1 day	Tue 8/24/21	Tue 8/24/21	610,604
612	6248	NA	0%	STRIP & CLEANUP	1 day	Wed 8/25/21	Wed 8/25/21	611
613	<b>6249</b>	<b>NA</b>	<b>0%</b>	<b>ONE-SIDED WALL #8:</b>	<b>10.88 days</b>	<b>Wed 8/18/21</b>	<b>Wed 9/1/21</b>	
614	6250	NA	0%	INSTALL WATERPROOFING	2 days	Wed 8/18/21	Thu 8/19/21	606
615	6251	NA	0%	INSTALL REINFORCEMENT	2 days	Fri 8/20/21	Mon 8/23/21	607,614
616	6336	NA	0%	MEPS ROUGH IN	2 days	Fri 8/20/21	Mon 8/23/21	615FF
617	6252	NA	0%	SET ONE-SIDED WALL FORMWORK	2 days	Wed 8/25/21	Thu 8/26/21	611,615,616
618	6253	NA	0%	INSPECTION	1 day	Thu 8/26/21	Thu 8/26/21	617FF
619	6254	NA	0%	POUR WALL #8	1 day	Tue 8/31/21	Tue 8/31/21	618FS+2 days,612
620	6255	NA	0%	STRIP & CLEANUP	1 day	Wed 9/1/21	Wed 9/1/21	619
621	<b>6263</b>	<b>NA</b>	<b>0%</b>	<b>VERTICAL - COREWALLS:</b>	<b>23.88 days</b>	<b>Mon 7/26/21</b>	<b>Thu 8/26/21</b>	
622	<b>6264</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL #1:</b>	<b>8.88 days</b>	<b>Mon 7/26/21</b>	<b>Thu 8/5/21</b>	
623	6265	NA	0%	INSTALL REINFORCEMENT	3 days	Mon 7/26/21	Wed 7/28/21	505
624	6266	NA	0%	LEADSIDE WALL FORMWORK	2 days	Thu 7/29/21	Fri 7/30/21	623
625	6340	NA	0%	MEPS ROUGH IN	1 day	Mon 8/2/21	Mon 8/2/21	624
626	6267	NA	0%	DOUBLE UP FORMWORK	2 days	Mon 8/2/21	Tue 8/3/21	624,625SS
627	6268	NA	0%	INSPECTION	1 day	Tue 8/3/21	Tue 8/3/21	626FF
628	6269	NA	0%	POUR COREWALL	1 day	Wed 8/4/21	Wed 8/4/21	627
629	6270	NA	0%	STRIP & CLEANUP	1 day	Thu 8/5/21	Thu 8/5/21	628
630	<b>6271</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL #2:</b>	<b>9.88 days</b>	<b>Thu 7/29/21</b>	<b>Wed 8/11/21</b>	
631	6272	NA	0%	INSTALL REINFORCEMENT	3 days	Thu 7/29/21	Mon 8/2/21	623
632	6273	NA	0%	LEADSIDE WALL FORMWORK	2 days	Wed 8/4/21	Thu 8/5/21	626,631,629FF
633	6342	NA	0%	MEPS ROUGH IN	2 days	Wed 8/4/21	Thu 8/5/21	632FF
634	6274	NA	0%	DOUBLE UP FORMWORK	2 days	Fri 8/6/21	Mon 8/9/21	632,633
635	6275	NA	0%	INSPECTION	1 day	Mon 8/9/21	Mon 8/9/21	634FF
636	6276	NA	0%	POUR COREWALL	1 day	Tue 8/10/21	Tue 8/10/21	635
637	6277	NA	0%	STRIP & CLEANUP	1 day	Wed 8/11/21	Wed 8/11/21	636
638	<b>6278</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL #3:</b>	<b>8.88 days</b>	<b>Mon 8/16/21</b>	<b>Thu 8/26/21</b>	
639	6279	NA	0%	INSTALL REINFORCEMENT	3 days	Mon 8/16/21	Wed 8/18/21	554
640	6280	NA	0%	LEADSIDE WALL FORMWORK	2 days	Thu 8/19/21	Fri 8/20/21	639
641	6345	NA	0%	MEPS ROUGH IN	2 days	Thu 8/19/21	Fri 8/20/21	640FF
642	6281	NA	0%	DOUBLE UP FORMWORK	2 days	Mon 8/23/21	Tue 8/24/21	640,641
643	6282	NA	0%	INSPECTION	1 day	Tue 8/24/21	Tue 8/24/21	642FF
644	6283	NA	0%	POUR COREWALL	1 day	Wed 8/25/21	Wed 8/25/21	643
645	6284	NA	0%	STRIP & CLEANUP CORE WALL # 3	1 day	Thu 8/26/21	Thu 8/26/21	644
646	<b>6285</b>	<b>NA</b>	<b>0%</b>	<b>VERTICAL - COLUMNS:</b>	<b>17.88 days</b>	<b>Thu 7/29/21</b>	<b>Mon 8/23/21</b>	

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
647	<b>6286</b>	<b>NA</b>	<b>0%</b>	<b>COLUMN POUR #1:</b>	<b>3.88 days</b>	<b>Thu 7/29/21</b>	<b>Tue 8/3/21</b>	
648	6287	NA	0%	INSTALL REINFORCEMENT	1 day	Thu 7/29/21	Thu 7/29/21	623,489
649	6288	NA	0%	FORM COLUMNS	2 days	Fri 7/30/21	Mon 8/2/21	648
650	6289	NA	0%	INSPECTION	1 day	Mon 8/2/21	Mon 8/2/21	649FF
651	6290	NA	0%	COLUMN POUR #1	1 day	Mon 8/2/21	Mon 8/2/21	650FF
652	6291	NA	0%	STRIP & CLEANUP	1 day	Tue 8/3/21	Tue 8/3/21	651
653	<b>6292</b>	<b>NA</b>	<b>0%</b>	<b>COLUMN POUR #2:</b>	<b>4.88 days</b>	<b>Fri 7/30/21</b>	<b>Thu 8/5/21</b>	
654	6293	NA	0%	INSTALL REINFORCEMENT	1 day	Fri 7/30/21	Fri 7/30/21	648,505
655	6294	NA	0%	FORM COLUMNS	2 days	Tue 8/3/21	Wed 8/4/21	651,654,652SS
656	6295	NA	0%	INSPECTION	1 day	Wed 8/4/21	Wed 8/4/21	655FF
657	6296	NA	0%	COLUMN POUR #2	1 day	Wed 8/4/21	Wed 8/4/21	656FF
658	6297	NA	0%	STRIP & CLEANUP	1 day	Thu 8/5/21	Thu 8/5/21	657
659	<b>6298</b>	<b>NA</b>	<b>0%</b>	<b>COLUMN POUR #3:</b>	<b>5.88 days</b>	<b>Mon 8/2/21</b>	<b>Mon 8/9/21</b>	
660	6299	NA	0%	INSTALL REINFORCEMENT	1 day	Mon 8/2/21	Mon 8/2/21	654,539
661	6300	NA	0%	FORM COLUMNS	2 days	Thu 8/5/21	Fri 8/6/21	657,660,658SS
662	6301	NA	0%	INSPECTION	1 day	Fri 8/6/21	Fri 8/6/21	661FF
663	6302	NA	0%	COLUMN POUR #3:	1 day	Fri 8/6/21	Fri 8/6/21	662FF
664	6303	NA	0%	STRIP & CLEANUP	1 day	Mon 8/9/21	Mon 8/9/21	663
665	<b>6304</b>	<b>NA</b>	<b>0%</b>	<b>COLUMN POUR #4:</b>	<b>6.88 days</b>	<b>Tue 8/3/21</b>	<b>Wed 8/11/21</b>	
666	6305	NA	0%	INSTALL REINFORCEMENT	1 day	Tue 8/3/21	Tue 8/3/21	660
667	6306	NA	0%	FORM COLUMNS	2 days	Mon 8/9/21	Tue 8/10/21	663,666,664SS
668	6307	NA	0%	INSPECTION	1 day	Tue 8/10/21	Tue 8/10/21	667FF
669	6308	NA	0%	COLUMN POUR #4:	1 day	Tue 8/10/21	Tue 8/10/21	668FF
670	6309	NA	0%	STRIP & CLEANUP	1 day	Wed 8/11/21	Wed 8/11/21	669
671	<b>6310</b>	<b>NA</b>	<b>0%</b>	<b>COLUMN POUR #5:</b>	<b>3.88 days</b>	<b>Mon 8/16/21</b>	<b>Thu 8/19/21</b>	
672	6311	NA	0%	INSTALL REINFORCEMENT	1 day	Mon 8/16/21	Mon 8/16/21	666,554
673	6312	NA	0%	FORM COLUMNS	2 days	Tue 8/17/21	Wed 8/18/21	669,672,670SS
674	6313	NA	0%	INSPECTION	1 day	Wed 8/18/21	Wed 8/18/21	673FF
675	6314	NA	0%	COLUMN POUR #5:	1 day	Wed 8/18/21	Wed 8/18/21	674FF
676	6315	NA	0%	STRIP & CLEANUP	1 day	Thu 8/19/21	Thu 8/19/21	675
677	<b>6316</b>	<b>NA</b>	<b>0%</b>	<b>COLUMN POUR #6:</b>	<b>4.88 days</b>	<b>Tue 8/17/21</b>	<b>Mon 8/23/21</b>	
678	6317	NA	0%	INSTALL REINFORCEMENT	1 day	Tue 8/17/21	Tue 8/17/21	672
679	6318	NA	0%	FORM COLUMNS	2 days	Thu 8/19/21	Fri 8/20/21	675,678,676FS-1 day
680	6319	NA	0%	INSPECTION	1 day	Fri 8/20/21	Fri 8/20/21	679FF
681	6320	NA	0%	COLUMN POUR #6:	1 day	Fri 8/20/21	Fri 8/20/21	680FF
682	6321	NA	0%	STRIP & CLEANUP	1 day	Mon 8/23/21	Mon 8/23/21	681
683	<b>438</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 1</b>	<b>25 days</b>	<b>Wed 9/1/21</b>	<b>Wed 10/6/21</b>	
684	<b>439</b>	<b>NA</b>	<b>0%</b>	<b>AREA 1 - MCALLISTER STREET (A1/A2)</b>	<b>13 days</b>	<b>Wed 9/1/21</b>	<b>Mon 9/20/21</b>	
685	<b>440</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDED DECK - POUR #1: (7 DAY CYCLE)</b>	<b>12.13 days</b>	<b>Wed 9/1/21</b>	<b>Fri 9/17/21</b>	
686	441	NA	0%	PROSHORE SHORING	3 days	Wed 9/1/21	Mon 9/6/21	644,681,620,555,682,1466SS,1
687	442	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Fri 9/3/21	Mon 9/6/21	686FF
688	443	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Fri 9/3/21	Mon 9/6/21	687FF
689	444	NA	0%	REBAR BOTTOM	2 days	Mon 9/6/21	Wed 9/8/21	688
690	445	NA	0%	MEPS ROUGH IN	1 day	Tue 9/7/21	Wed 9/8/21	689FF
691	446	NA	0%	REBAR TOP	1 day	Wed 9/8/21	Thu 9/9/21	689
692	447	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Wed 9/8/21	Thu 9/9/21	691FF
693	448	NA	0%	INSPECTION	1 day	Wed 9/8/21	Thu 9/9/21	692FF,690

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
694	449	NA	0%	<b>POUR DECK L1 MCALLISTER</b>	1 day	Thu 9/9/21	Fri 9/10/21	693
695	450	NA	0%	CURE	3 edays	Thu 9/9/21	Sun 9/12/21	694SS
696	451	NA	0%	STRIP DECK L1 (MCALLISTER ST)	5 days	Mon 9/13/21	Fri 9/17/21	695
697	<b>452</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL</b>	<b>8 days</b>	<b>Mon 9/6/21</b>	<b>Thu 9/16/21</b>	
698	453	NA	0%	INSTALL REINFORCEMENT	3 days	Mon 9/6/21	Thu 9/9/21	691FF
699	454	NA	0%	LEADSIDE WALL FORMWORK	1 day	Fri 9/10/21	Mon 9/13/21	694
700	6347	NA	0%	MEPS ROUGH IN	1 day	Fri 9/10/21	Mon 9/13/21	699FF
701	455	NA	0%	DOUBLE UP FORMWORK	1 day	Mon 9/13/21	Tue 9/14/21	699,700
702	456	NA	0%	INSPECTION	1 day	Mon 9/13/21	Tue 9/14/21	701FF
703	457	NA	0%	POUR COREWALL	1 day	Tue 9/14/21	Wed 9/15/21	702
704	458	NA	0%	STRIP & CLEANUP	1 day	Wed 9/15/21	Thu 9/16/21	703
705	<b>459</b>	<b>NA</b>	<b>0%</b>	<b>COLUMNNS</b>	<b>7 days</b>	<b>Mon 9/6/21</b>	<b>Wed 9/15/21</b>	
706	460	NA	0%	SET COLUMN REINFORCEMENT	3 days	Mon 9/6/21	Thu 9/9/21	691FF
707	461	NA	0%	FORM COLUMNS #1	1 day	Fri 9/10/21	Mon 9/13/21	694,706
708	462	NA	0%	INSPECTION	1 day	Fri 9/10/21	Mon 9/13/21	707FF
709	463	NA	0%	POUR COLUMNNS #1	1 day	Mon 9/13/21	Tue 9/14/21	707
710	464	NA	0%	STRIP COLUMNNS MCALLISTER L 1	1 day	Tue 9/14/21	Wed 9/15/21	709
711	<b>6349</b>	<b>NA</b>	<b>0%</b>	<b>ONE-SIDED WALL #1:</b>	<b>6 days</b>	<b>Mon 9/13/21</b>	<b>Mon 9/20/21</b>	
712	6350	NA	0%	INSTALL WATERPROOFING	2 days	Mon 9/13/21	Tue 9/14/21	694
713	6351	NA	0%	INSTALL REINFORCEMENT	1 day	Wed 9/15/21	Wed 9/15/21	712
714	6357	NA	0%	MEPS ROUGH IN	1 day	Wed 9/15/21	Wed 9/15/21	713FF
715	6352	NA	0%	SET ONE-SIDED WALL FORMWORK	1 day	Thu 9/16/21	Thu 9/16/21	713,714
716	6353	NA	0%	INSPECTION	1 day	Thu 9/16/21	Thu 9/16/21	715FF
717	6354	NA	0%	POUR WALL	1 day	Fri 9/17/21	Fri 9/17/21	716
718	6355	NA	0%	STRIP & CLEANUP	1 day	Mon 9/20/21	Mon 9/20/21	717
719	<b>473</b>	<b>NA</b>	<b>0%</b>	<b>AREA 2 - HYDE STREET (B1)</b>	<b>22 days</b>	<b>Mon 9/6/21</b>	<b>Wed 10/6/21</b>	
720	<b>474</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDED DECK - POUR #2 (11 DAY CYCLE):</b>	<b>18 days</b>	<b>Mon 9/6/21</b>	<b>Thu 9/30/21</b>	
721	475	NA	0%	PROSHORE SHORING	5 days	Mon 9/6/21	Mon 9/13/21	686,1464SS,1469SS,1470SS
722	476	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Fri 9/10/21	Mon 9/13/21	721FF
723	477	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Fri 9/10/21	Mon 9/13/21	722FF
724	478	NA	0%	REBAR BOTTOM	3 days	Mon 9/13/21	Thu 9/16/21	723
725	479	NA	0%	MEPS ROUGH IN	1 day	Thu 9/16/21	Fri 9/17/21	724
726	480	NA	0%	REBAR TOP	2 days	Thu 9/16/21	Mon 9/20/21	724
727	481	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Fri 9/17/21	Mon 9/20/21	726FF
728	482	NA	0%	INSPECTION	1 day	Fri 9/17/21	Mon 9/20/21	727FF
729	483	NA	0%	<b>POUR DECK L1 HYDE</b>	1 day	Mon 9/20/21	Tue 9/21/21	728
730	484	NA	0%	CURE	3 edays	Mon 9/20/21	Thu 9/23/21	729SS
731	485	NA	0%	STRIP DECK	5 days	Thu 9/23/21	Thu 9/30/21	730
732	<b>486</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL # 1</b>	<b>9 days</b>	<b>Mon 9/13/21</b>	<b>Fri 9/24/21</b>	
733	487	NA	0%	INSTALL REINFORCEMENT	5 days	Mon 9/13/21	Mon 9/20/21	724SS
734	488	NA	0%	LEADSIDE WALL FORMWORK	1 day	Tue 9/21/21	Wed 9/22/21	729
735	6367	NA	0%	MEPS ROUGH IN	1 day	Tue 9/21/21	Wed 9/22/21	734FF
736	489	NA	0%	DOUBLE UP FORMWORK	1 day	Wed 9/22/21	Thu 9/23/21	734,735
737	490	NA	0%	INSPECTION	1 day	Wed 9/22/21	Thu 9/23/21	736FF
738	491	NA	0%	POUR COREWALL	1 day	Wed 9/22/21	Thu 9/23/21	737FF
739	492	NA	0%	STRIP & CLEANUP	1 day	Thu 9/23/21	Fri 9/24/21	738
740	<b>6359</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL #2:</b>	<b>6 days</b>	<b>Mon 9/20/21</b>	<b>Tue 9/28/21</b>	

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
741	6360	NA	0%	INSTALL REINFORCEMENT	5 days	Mon 9/20/21	Mon 9/27/21	726
742	6361	NA	0%	LEADSIDE WALL FORMWORK	1 day	Wed 9/22/21	Thu 9/23/21	734
743	6369	NA	0%	MEPS ROUGH IN	1 day	Wed 9/22/21	Thu 9/23/21	742FF
744	6362	NA	0%	DOUBLE UP FORMWORK	1 day	Thu 9/23/21	Fri 9/24/21	742,743
745	6363	NA	0%	INSPECTION	1 day	Thu 9/23/21	Fri 9/24/21	744FF
746	6364	NA	0%	POUR COREWALL	1 day	Fri 9/24/21	Mon 9/27/21	745
747	6365	NA	0%	STRIP & CLEANUP	1 day	Mon 9/27/21	Tue 9/28/21	746
748	<b>493</b>	<b>NA</b>	<b>0%</b>	<b>COLUMNS</b>	<b>10 days</b>	<b>Mon 9/13/21</b>	<b>Mon 9/27/21</b>	
749	494	NA	0%	SET COLUMN REINFORCEMENT	5 days	Mon 9/13/21	Mon 9/20/21	726FF
750	495	NA	0%	FORM COLUMNS #1	1 day	Tue 9/21/21	Wed 9/22/21	729
751	496	NA	0%	INSPECTION	1 day	Tue 9/21/21	Wed 9/22/21	750FF
752	497	NA	0%	POUR COLUMNS #1	1 day	Tue 9/21/21	Wed 9/22/21	751FF
753	498	NA	0%	STRIP COLUMNS	1 day	Wed 9/22/21	Thu 9/23/21	752
754	499	NA	0%	FORM COLUMNS #2	1 day	Wed 9/22/21	Thu 9/23/21	753SS
755	500	NA	0%	INSPECTION	1 day	Wed 9/22/21	Thu 9/23/21	754FF
756	501	NA	0%	POUR COLUMNS #2	1 day	Thu 9/23/21	Fri 9/24/21	755
757	502	NA	0%	STRIP COLUMNS # 2 L 1 HYDE	1 day	Fri 9/24/21	Mon 9/27/21	756
758	<b>6371</b>	<b>NA</b>	<b>0%</b>	<b>ONE-SIDED WALL #2:</b>	<b>5 days</b>	<b>Tue 9/21/21</b>	<b>Tue 9/28/21</b>	
759	6372	NA	0%	INSTALL WATERPROOFING	1 day	Tue 9/21/21	Wed 9/22/21	729
760	6373	NA	0%	INSTALL REINFORCEMENT	1 day	Wed 9/22/21	Thu 9/23/21	759
761	6400	NA	0%	MEPS ROUGH IN	1 day	Wed 9/22/21	Thu 9/23/21	760FF
762	6374	NA	0%	SET ONE-SIDED WALL FORMWORK	1 day	Thu 9/23/21	Fri 9/24/21	760,761
763	6375	NA	0%	INSPECTION	1 day	Thu 9/23/21	Fri 9/24/21	762FF
764	6376	NA	0%	POUR WALL	1 day	Fri 9/24/21	Mon 9/27/21	763
765	6377	NA	0%	STRIP & CLEANUP	1 day	Mon 9/27/21	Tue 9/28/21	764
766	<b>6378</b>	<b>NA</b>	<b>0%</b>	<b>ONE-SIDED WALL #3:</b>	<b>6 days</b>	<b>Wed 9/22/21</b>	<b>Thu 9/30/21</b>	
767	6379	NA	0%	INSTALL WATERPROOFING	1 day	Wed 9/22/21	Thu 9/23/21	759
768	6380	NA	0%	INSTALL REINFORCEMENT	1 day	Thu 9/23/21	Fri 9/24/21	760,767
769	6402	NA	0%	MEPS ROUGH IN	1 day	Thu 9/23/21	Fri 9/24/21	768FF
770	6381	NA	0%	SET ONE-SIDED WALL FORMWORK	1 day	Mon 9/27/21	Tue 9/28/21	764,768,769
771	6382	NA	0%	INSPECTION	1 day	Mon 9/27/21	Tue 9/28/21	770FF
772	6383	NA	0%	POUR WALL	1 day	Tue 9/28/21	Wed 9/29/21	771
773	6384	NA	0%	STRIP & CLEANUP	1 day	Wed 9/29/21	Thu 9/30/21	772
774	<b>6385</b>	<b>NA</b>	<b>0%</b>	<b>ONE-SIDED WALL #4:</b>	<b>7 days</b>	<b>Thu 9/23/21</b>	<b>Mon 10/4/21</b>	
775	6386	NA	0%	INSTALL WATERPROOFING	1 day	Thu 9/23/21	Fri 9/24/21	767
776	6387	NA	0%	INSTALL REINFORCEMENT	1 day	Fri 9/24/21	Mon 9/27/21	768,775
777	6404	NA	0%	MEPS ROUGH IN	1 day	Fri 9/24/21	Mon 9/27/21	776FF
778	6388	NA	0%	SET ONE-SIDED WALL FORMWORK	1 day	Wed 9/29/21	Thu 9/30/21	772,776,777
779	6389	NA	0%	INSPECTION	1 day	Wed 9/29/21	Thu 9/30/21	778FF
780	6390	NA	0%	POUR WALL	1 day	Thu 9/30/21	Fri 10/1/21	779
781	6391	NA	0%	STRIP & CLEANUP	1 day	Fri 10/1/21	Mon 10/4/21	780
782	<b>6392</b>	<b>NA</b>	<b>0%</b>	<b>ONE-SIDED WALL #5:</b>	<b>8 days</b>	<b>Fri 9/24/21</b>	<b>Wed 10/6/21</b>	
783	6393	NA	0%	INSTALL WATERPROOFING	1 day	Fri 9/24/21	Mon 9/27/21	775
784	6394	NA	0%	INSTALL REINFORCEMENT	1 day	Mon 9/27/21	Tue 9/28/21	776,783
785	6406	NA	0%	MEPS ROUGH IN	1 day	Mon 9/27/21	Tue 9/28/21	784FF
786	6395	NA	0%	SET ONE-SIDED WALL FORMWORK	1 day	Fri 10/1/21	Mon 10/4/21	780,784,785
787	6396	NA	0%	INSPECTION	1 day	Fri 10/1/21	Mon 10/4/21	786FF

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
788	6397	NA	0%	POUR WALL	1 day	Mon 10/4/21	Tue 10/5/21	787
789	6398	NA	0%	STRIP & CLEANUP	1 day	Tue 10/5/21	Wed 10/6/21	788
790	<b>525</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 2</b>	<b>32 days</b>	<b>Fri 9/24/21</b>	<b>Mon 11/8/21</b>	
791	<b>526</b>	<b>NA</b>	<b>0%</b>	<b>AREA 1 - MCALLISTER STREET (A1/A2)</b>	<b>25 days</b>	<b>Fri 9/24/21</b>	<b>Thu 10/28/21</b>	
792	<b>527</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDED DECK - POUR #1 (15 DAY CYCLE):</b>	<b>25 days</b>	<b>Fri 9/24/21</b>	<b>Thu 10/28/21</b>	
793	528	NA	0%	PROSHORE SHORING	6 days	Fri 9/24/21	Fri 10/1/21	738,704,1462SS,696SS
794	530	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Thu 9/30/21	Fri 10/1/21	793FF
795	531	NA	0%	BEAMS	3 days	Fri 10/1/21	Wed 10/6/21	794
796	532	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Wed 10/6/21	Thu 10/7/21	795
797	533	NA	0%	REBAR BOTTOM	3 days	Thu 10/7/21	Tue 10/12/21	796
798	534	NA	0%	MEPS ROUGH IN	1 day	Mon 10/11/21	Tue 10/12/21	797FF
799	535	NA	0%	REBAR TOP (3day)	2 days	Wed 10/13/21	Fri 10/15/21	798FS+1 day
800	536	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Thu 10/14/21	Fri 10/15/21	799FF
801	537	NA	0%	INSPECTION	1 day	Fri 10/15/21	Fri 10/15/21	800FF
802	159	NA	0%	<b>POUR DECK L2 (AREA 1- MCALLISTER ST)</b>	1 day	Mon 10/18/21	Mon 10/18/21	801FS+1 hr
803	538	NA	0%	CURE	3 edays	Mon 10/18/21	Thu 10/21/21	802SS
804	539	NA	0%	STRESS L2 MCALLISTER	1 day	Thu 10/21/21	Thu 10/21/21	803
805	540	NA	0%	STRIP DECK L2 (MCALLISTER ST)	5 days	Fri 10/22/21	Thu 10/28/21	804
806	<b>541</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL-POUR # 1</b>	<b>9.13 days</b>	<b>Fri 10/8/21</b>	<b>Thu 10/21/21</b>	
807	542	NA	0%	LEADSIDE WALL FORMWORK	1 day	Tue 10/19/21	Tue 10/19/21	802
808	543	NA	0%	INSTALL REINFORCEMENT	5 days	Fri 10/8/21	Fri 10/15/21	799FF
809	6408	NA	0%	MEPS ROUGH IN	1 day	Thu 10/14/21	Fri 10/15/21	808FF
810	544	NA	0%	DOUBLE UP FORMWORK	1 day	Wed 10/20/21	Wed 10/20/21	802,809,807
811	545	NA	0%	INSPECTION	1 day	Wed 10/20/21	Wed 10/20/21	810FF
812	546	NA	0%	POUR COREWALL	1 day	Wed 10/20/21	Wed 10/20/21	811FF
813	547	NA	0%	STRIP & CLEANUP	1 day	Thu 10/21/21	Thu 10/21/21	812
814	<b>6410</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL - POUR #2:</b>	<b>10.13 days</b>	<b>Fri 10/8/21</b>	<b>Fri 10/22/21</b>	
815	6411	NA	0%	LEADSIDE WALL FORMWORK	1 day	Wed 10/20/21	Wed 10/20/21	807
816	6412	NA	0%	INSTALL REINFORCEMENT	5 days	Fri 10/8/21	Fri 10/15/21	799FF
817	6425	NA	0%	MEPS ROUGH IN	1 day	Thu 10/14/21	Fri 10/15/21	816FF
818	6413	NA	0%	DOUBLE UP FORMWORK	1 day	Thu 10/21/21	Thu 10/21/21	815,816,817
819	6414	NA	0%	INSPECTION	1 day	Thu 10/21/21	Thu 10/21/21	818FF
820	6415	NA	0%	POUR COREWALL	1 day	Thu 10/21/21	Thu 10/21/21	819FF
821	6416	NA	0%	STRIP & CLEANUP	1 day	Fri 10/22/21	Fri 10/22/21	820
822	<b>6417</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL - POUR #3:</b>	<b>12.13 days</b>	<b>Fri 10/8/21</b>	<b>Tue 10/26/21</b>	
823	6418	NA	0%	LEADSIDE WALL FORMWORK	1 day	Fri 10/22/21	Fri 10/22/21	818
824	6419	NA	0%	INSTALL REINFORCEMENT	5 days	Fri 10/8/21	Fri 10/15/21	799FF
825	6427	NA	0%	MEPS ROUGH IN	1 day	Thu 10/14/21	Fri 10/15/21	824FF
826	6420	NA	0%	DOUBLE UP FORMWORK	1 day	Mon 10/25/21	Mon 10/25/21	823,825
827	6421	NA	0%	INSPECTION	1 day	Mon 10/25/21	Mon 10/25/21	826FF
828	6422	NA	0%	POUR COREWALL	1 day	Mon 10/25/21	Mon 10/25/21	827FF
829	6423	NA	0%	STRIP & CLEANUP	1 day	Tue 10/26/21	Tue 10/26/21	828
830	<b>548</b>	<b>NA</b>	<b>0%</b>	<b>COLUMNS</b>	<b>14.13 days</b>	<b>Wed 10/6/21</b>	<b>Tue 10/26/21</b>	
831	549	NA	0%	SET COLUMN REINFORCEMENT	7 days	Wed 10/6/21	Fri 10/15/21	799FF
832	550	NA	0%	FORM COLUMNS	1 day	Tue 10/19/21	Tue 10/19/21	802,831
833	551	NA	0%	INSPECTION	1 day	Tue 10/19/21	Tue 10/19/21	832FF
834	552	NA	0%	POUR COLUMNS #1	1 day	Tue 10/19/21	Tue 10/19/21	832FF,833SS

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
835	553	NA	0%	STRIP COLUMNS MCALLISTER L 2	2 days	Wed 10/20/21	Thu 10/21/21	834
836	554	NA	0%	FORM COLUMNS	1 day	Fri 10/22/21	Fri 10/22/21	835
837	555	NA	0%	INSPECTION	1 day	Fri 10/22/21	Fri 10/22/21	836FF
838	556	NA	0%	POUR COLUMNS #2	2 days	Fri 10/22/21	Mon 10/25/21	837SS
839	557	NA	0%	STRIP COLUMNS MCALLISTER L 2	1 day	Tue 10/26/21	Tue 10/26/21	838
840	<b>558</b>	<b>NA</b>	<b>0%</b>	<b>AREA 2 - HYDE STREET (B1)</b>	<b>25 days</b>	<b>Fri 10/1/21</b>	<b>Mon 11/8/21</b>	
841	<b>559</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDED DECK - POUR #2 (11 DAY CYCLE):</b>	<b>25 days</b>	<b>Fri 10/1/21</b>	<b>Mon 11/8/21</b>	
842	560	NA	0%	PROSHORE SHORING	5 days	Fri 10/1/21	Fri 10/8/21	1644FF,793
843	562	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Thu 10/7/21	Fri 10/8/21	842FF
844	563	NA	0%	INSTALL BOX BEAMS (SS)	8 days	Fri 10/8/21	Wed 10/20/21	843
845	564	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Wed 10/20/21	Thu 10/21/21	844
846	565	NA	0%	REBAR BOTTOM	3 days	Thu 10/21/21	Tue 10/26/21	799,845
847	566	NA	0%	MEPS ROUGH IN	1 day	Mon 10/25/21	Tue 10/26/21	846FF
848	567	NA	0%	REBAR TOP	2 days	Tue 10/26/21	Thu 10/28/21	847
849	568	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Wed 10/27/21	Thu 10/28/21	848FF
850	569	NA	0%	INSPECTION	1 day	Wed 10/27/21	Thu 10/28/21	849FF
851	570	NA	0%	<b>POUR DECK L2 HYDE</b>	1 day	Fri 10/29/21	Fri 10/29/21	850
852	571	NA	0%	CURE	3 edays	Fri 10/29/21	Mon 11/1/21	851SS
853	572	NA	0%	STRESS L 2 HYDE	1 day	Mon 11/1/21	Mon 11/1/21	852
854	573	NA	0%	STRIP DECK L2 HYDE ST	5 days	Tue 11/2/21	Mon 11/8/21	853
855	<b>6429</b>	<b>NA</b>	<b>0%</b>	<b>SHEARWALL/COLUMNS:</b>	<b>5 days</b>	<b>Tue 10/26/21</b>	<b>Tue 11/2/21</b>	
856	6430	NA	0%	SET COLUMN REINFORCEMENT	2 days	Tue 10/26/21	Thu 10/28/21	848FF
857	6436	NA	0%	LEADSIDE WALL FORMWORK	1 day	Fri 10/29/21	Mon 11/1/21	851,856
858	6439	NA	0%	MEPS ROUGH IN	1 day	Fri 10/29/21	Mon 11/1/21	857FF
859	6437	NA	0%	DOUBLE UP FORMWORK	0 days	Mon 11/1/21	Mon 11/1/21	857FF,858
860	6431	NA	0%	FORM COLUMNS	1 day	Fri 10/29/21	Mon 11/1/21	851,838
861	6432	NA	0%	INSPECTION	1 day	Fri 10/29/21	Mon 11/1/21	860FF
862	6433	NA	0%	POUR COLUMNS #1	1 day	Mon 11/1/21	Tue 11/2/21	861FF,859SS
863	6434	NA	0%	STRIP COLUMNS	1 day	Mon 11/1/21	Tue 11/2/21	862FF
864	<b>587</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 3</b>	<b>26 days</b>	<b>Fri 10/22/21</b>	<b>Thu 12/2/21</b>	
865	<b>588</b>	<b>NA</b>	<b>0%</b>	<b>AREA 1 - MCALLISTER STREET (A1/A2)</b>	<b>29.13 days</b>	<b>Fri 10/22/21</b>	<b>Thu 12/2/21</b>	
866	<b>589</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDED DECK - POUR #1 (15 Day Cycle):</b>	<b>29.13 days</b>	<b>Fri 10/22/21</b>	<b>Thu 12/2/21</b>	
867	590	NA	0%	PROSHORE SHORING	7 days	Fri 10/22/21	Tue 11/2/21	1654FF,834,812FS+1 day,842,8
868	592	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Mon 11/1/21	Tue 11/2/21	867FF
869	593	NA	0%	SET BOX BEAMS (SS)	10 days	Tue 11/2/21	Tue 11/16/21	868,1641FF
870	595	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Tue 11/16/21	Wed 11/17/21	869
871	596	NA	0%	REBAR BOTTOM	4 days	Wed 11/17/21	Tue 11/23/21	870
872	597	NA	0%	MEPS ROUGH IN	1 day	Mon 11/22/21	Tue 11/23/21	871FF
873	598	NA	0%	REBAR TOP	3 days	Tue 11/23/21	Fri 11/26/21	871
874	599	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Thu 11/25/21	Fri 11/26/21	873FF
875	600	NA	0%	INSPECTION	0 days	Fri 11/26/21	Fri 11/26/21	874FF,872SS
876	240	NA	0%	<b>POUR DECK L3 MCALLISTER</b>	1 day	Wed 11/24/21	Fri 11/26/21	875FF,1653
877	602	NA	0%	CURE	3 edays	Wed 11/24/21	Sat 11/27/21	876SS
878	603	NA	0%	STRESS L 3 MCALLISTER	1 day	Mon 11/29/21	Mon 11/29/21	877
879	604	NA	0%	STRIP DECK L3 MCALLISTER	3 days	Tue 11/30/21	Thu 12/2/21	878
880	<b>6441</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL #1:</b>	<b>22 days</b>	<b>Mon 11/1/21</b>	<b>Wed 12/1/21</b>	
881	6442	NA	0%	LEADSIDE WALL FORMWORK	1 day	Mon 11/1/21	Tue 11/2/21	867FF

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
882	6443	NA	0%	INSTALL REINFORCEMENT	5 days	Fri 11/19/21	Fri 11/26/21	873FF
883	6444	NA	0%	DOUBLE UP FORMWORK	1 day	Fri 11/26/21	Mon 11/29/21	881,882
884	6445	NA	0%	INSPECTION	1 day	Fri 11/26/21	Mon 11/29/21	883FF
885	6446	NA	0%	POUR COREWALL	1 day	Mon 11/29/21	Tue 11/30/21	884FF+1 day
886	6447	NA	0%	STRIP & CLEANUP	1 day	Tue 11/30/21	Wed 12/1/21	885
887	<b>6448</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL - #2:</b>	<b>22 days</b>	<b>Mon 11/1/21</b>	<b>Wed 12/1/21</b>	
888	6449	NA	0%	LEADSIDE WALL FORMWORK	1 day	Mon 11/1/21	Tue 11/2/21	867FF
889	6450	NA	0%	INSTALL REINFORCEMENT	5 days	Fri 11/19/21	Fri 11/26/21	873FF,888
890	6451	NA	0%	DOUBLE UP FORMWORK	1 day	Mon 11/29/21	Tue 11/30/21	883,889
891	6452	NA	0%	INSPECTION	1 day	Mon 11/29/21	Tue 11/30/21	890FF
892	6453	NA	0%	POUR COREWALL	1 day	Mon 11/29/21	Tue 11/30/21	891FF
893	6454	NA	0%	STRIP & CLEANUP	1 day	Tue 11/30/21	Wed 12/1/21	892,886SS
894	<b>6455</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL - #3:</b>	<b>22 days</b>	<b>Mon 11/1/21</b>	<b>Wed 12/1/21</b>	
895	6456	NA	0%	LEADSIDE WALL FORMWORK	1 day	Mon 11/1/21	Tue 11/2/21	867FF
896	6457	NA	0%	INSTALL REINFORCEMENT	5 days	Fri 11/19/21	Fri 11/26/21	873FF,895
897	6458	NA	0%	DOUBLE UP FORMWORK	1 day	Mon 11/29/21	Tue 11/30/21	883,896
898	6459	NA	0%	INSPECTION	1 day	Mon 11/29/21	Tue 11/30/21	897FF
899	6460	NA	0%	POUR COREWALL	1 day	Mon 11/29/21	Tue 11/30/21	898FF
900	6461	NA	0%	STRIP & CLEANUP	1 day	Tue 11/30/21	Wed 12/1/21	899,893SS
901	<b>612</b>	<b>NA</b>	<b>0%</b>	<b>COLUMNS</b>	<b>12 days</b>	<b>Tue 11/16/21</b>	<b>Thu 12/2/21</b>	
902	613	NA	0%	SET COLUMN REINFORCEMENT	8 days	Tue 11/16/21	Fri 11/26/21	873FF
903	614	NA	0%	FORM COLUMNS	1 day	Fri 11/26/21	Mon 11/29/21	876,902FF
904	615	NA	0%	INSPECTION	1 day	Fri 11/26/21	Mon 11/29/21	903FF
905	616	NA	0%	POUR COLUMNS #1	1 day	Fri 11/26/21	Mon 11/29/21	904FF
906	617	NA	0%	STRIP COLUMNS	1 day	Mon 11/29/21	Tue 11/30/21	905
907	618	NA	0%	FORM COLUMNS	1 day	Mon 11/29/21	Tue 11/30/21	906SS
908	619	NA	0%	INSPECTION	1 day	Mon 11/29/21	Tue 11/30/21	907FF
909	620	NA	0%	POUR COLUMNS #2	1 day	Mon 11/29/21	Tue 11/30/21	908FF
910	621	NA	0%	STRIP COLUMNS	1 day	Tue 11/30/21	Wed 12/1/21	909
911	8576	NA	0%	FORM COLUMNS	1 day	Tue 11/30/21	Wed 12/1/21	909,910FF
912	8575	NA	0%	INSPECTION	1 day	Tue 11/30/21	Wed 12/1/21	911FF
913	8574	NA	0%	POUR COLUMNS #3	1 day	Wed 12/1/21	Wed 12/1/21	912FF
914	8573	NA	0%	STRIP COLUMNS	1 day	Wed 12/1/21	Thu 12/2/21	913
915	<b>622</b>	<b>NA</b>	<b>0%</b>	<b>AREA 2 - HYDE STREET (B1)</b>	<b>13.13 days</b>	<b>Tue 11/2/21</b>	<b>Fri 11/19/21</b>	
916	<b>623</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDED DECK - POUR #2 (7 DAY CYCLE):</b>	<b>13.13 days</b>	<b>Tue 11/2/21</b>	<b>Fri 11/19/21</b>	
917	624	NA	0%	PROSHORE SHORING	3 days	Tue 11/2/21	Fri 11/5/21	867,862
918	625	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Fri 11/5/21	Mon 11/8/21	917
919	626	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Fri 11/5/21	Mon 11/8/21	918FF
920	627	NA	0%	REBAR BOTTOM	2 days	Mon 11/8/21	Wed 11/10/21	919
921	628	NA	0%	MEPS ROUGH IN	1 day	Wed 11/10/21	Thu 11/11/21	920
922	629	NA	0%	REBAR TOP	1 day	Wed 11/10/21	Thu 11/11/21	920
923	630	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Wed 11/10/21	Thu 11/11/21	922FF
924	631	NA	0%	INSPECTION	1 day	Wed 11/10/21	Thu 11/11/21	923FF,921FF
925	239	NA	0%	<b>POUR DECK L3 HYDE</b>	0 days	Thu 11/11/21	Thu 11/11/21	924
926	632	NA	0%	CURE	3 edays	Thu 11/11/21	Sun 11/14/21	925SS
927	633	NA	0%	STRESS L 3 HYDE	1 day	Mon 11/15/21	Mon 11/15/21	926
928	164	NA	0%	STRIP DECK L3 (AREA 2 HYDE ST)	4 days	Tue 11/16/21	Fri 11/19/21	927



University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
929	6463	NA	0%	<b>VERTICAL:</b>	5 days	Mon 11/8/21	Mon 11/15/21	
930	6464	NA	0%	SET REINFORCEMENT	3 days	Mon 11/8/21	Thu 11/11/21	922FF
931	6465	NA	0%	FORM VERTICAL	1 day	Thu 11/11/21	Fri 11/12/21	925,930SS
932	6466	NA	0%	INSPECTION	1 day	Thu 11/11/21	Fri 11/12/21	931FF
933	6467	NA	0%	POUR COLUMNS #1	1 day	Thu 11/11/21	Fri 11/12/21	932FF
934	6468	NA	0%	STRIP COLUMNS	1 day	Fri 11/12/21	Mon 11/15/21	933
935	647	NA	0%	<b>LEVEL 4</b>	17.13 days	Tue 11/30/21	Thu 12/23/21	
936	648	NA	0%	<b>AREA 1 - MCALLISTER STREET (A1/A2)</b>	12.13 days	Tue 11/30/21	Thu 12/16/21	
937	649	NA	0%	<b>SUSPENDED DECK - POUR #1 (9 DAY CYCLE):</b>	12.13 days	Tue 11/30/21	Thu 12/16/21	
938	650	NA	0%	PROSHORE SHORING L4 (4dy )	3 days	Tue 11/30/21	Fri 12/3/21	917,885,928SS,900FF,914FF
939	651	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Thu 12/2/21	Fri 12/3/21	938FF
940	652	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Thu 12/2/21	Fri 12/3/21	939FF
941	653	NA	0%	REBAR BOTTOM	2 days	Fri 12/3/21	Tue 12/7/21	940
942	654	NA	0%	MEPS ROUGH IN	1 day	Mon 12/6/21	Tue 12/7/21	941FF
943	655	NA	0%	REBAR TOP	2 days	Tue 12/7/21	Thu 12/9/21	941
944	656	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Wed 12/8/21	Thu 12/9/21	943FF
945	657	NA	0%	INSPECTION	1 day	Wed 12/8/21	Thu 12/9/21	944FF,942FF
946	658	NA	0%	<b>POUR DECK L4 MCALLISTER</b>	0 days	Thu 12/9/21	Thu 12/9/21	945
947	659	NA	0%	CURE	3 edays	Thu 12/9/21	Sun 12/12/21	946SS
948	660	NA	0%	STRESS	1 day	Mon 12/13/21	Mon 12/13/21	947
949	661	NA	0%	STRIP DECK L 4	3 days	Tue 12/14/21	Thu 12/16/21	948
950	662	NA	0%	<b>COREWALL</b>	6.88 days	Fri 12/3/21	Mon 12/13/21	
951	663	NA	0%	LEADSIDE WALL FORMWORK	1 day	Fri 12/3/21	Fri 12/3/21	938FF
952	664	NA	0%	INSTALL REINFORCEMENT	4 days	Fri 12/3/21	Thu 12/9/21	943FF,951SS
953	665	NA	0%	DOUBLE UP FORMWORK	1 day	Thu 12/9/21	Fri 12/10/21	946,952SS
954	666	NA	0%	INSPECTION	1 day	Thu 12/9/21	Fri 12/10/21	953FF
955	667	NA	0%	POUR COREWALL	1 day	Fri 12/10/21	Fri 12/10/21	954FF
956	668	NA	0%	STRIP & CLEANUP	1 day	Fri 12/10/21	Mon 12/13/21	955
957	669	NA	0%	<b>AREA 2 - HYDE STREET (B1)</b>	14.13 days	Fri 12/3/21	Thu 12/23/21	
958	670	NA	0%	<b>SUSPENDED DECK - POUR #2 (7 DAY CYCLE):</b>	14.13 days	Fri 12/3/21	Thu 12/23/21	
959	671	NA	0%	PROSHORE SHORING LEVEL 4	3 days	Fri 12/3/21	Wed 12/8/21	938
960	672	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Tue 12/7/21	Wed 12/8/21	959FF
961	673	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Tue 12/7/21	Wed 12/8/21	960FF
962	674	NA	0%	REBAR BOTTOM	2 days	Thu 12/9/21	Mon 12/13/21	943,961
963	675	NA	0%	MEPS ROUGH IN	1 day	Fri 12/10/21	Mon 12/13/21	962FF
964	676	NA	0%	REBAR TOP	1 day	Mon 12/13/21	Tue 12/14/21	962
965	677	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Mon 12/13/21	Tue 12/14/21	964FF
966	678	NA	0%	INSPECTION	1 day	Mon 12/13/21	Tue 12/14/21	965FF,963FF
967	679	NA	0%	<b>POUR DECK L4 HYDE</b>	1 day	Wed 12/15/21	Wed 12/15/21	966
968	680	NA	0%	CURE	3 edays	Wed 12/15/21	Sat 12/18/21	967SS
969	681	NA	0%	STRESS	1 day	Mon 12/20/21	Mon 12/20/21	968
970	682	NA	0%	STRIP DECK HYDE	3 days	Tue 12/21/21	Thu 12/23/21	969
971	683	NA	0%	<b>COREWALL</b>	8 days	Tue 12/7/21	Fri 12/17/21	
972	684	NA	0%	LEADSIDE WALL FORMWORK	1 day	Tue 12/7/21	Wed 12/8/21	959FF
973	685	NA	0%	INSTALL REINFORCEMENT	3 days	Thu 12/9/21	Tue 12/14/21	964FF,972
974	686	NA	0%	DOUBLE UP FORMWORK	1 day	Wed 12/15/21	Thu 12/16/21	967,973
975	687	NA	0%	INSPECTION	1 day	Wed 12/15/21	Thu 12/16/21	974FF

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
976	688	NA	0%	POUR COREWALL	1 day	Thu 12/16/21	Thu 12/16/21	975FF
977	689	NA	0%	STRIP & CLEANUP	1 day	Thu 12/16/21	Fri 12/17/21	976
978	<b>690</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 5</b>	<b>19 days</b>	<b>Mon 12/13/21</b>	<b>Thu 1/6/22</b>	
979	<b>691</b>	<b>NA</b>	<b>0%</b>	<b>AREA 1 - MCALLISTER STREET (A1/A2)</b>	<b>13 days</b>	<b>Mon 12/13/21</b>	<b>Wed 12/29/21</b>	
980	<b>692</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDE DECK - POUR #1 (9 DAY CYCLE):</b>	<b>13 days</b>	<b>Mon 12/13/21</b>	<b>Wed 12/29/21</b>	
981	693	NA	0%	PROSHORE SHORING L5	4 days	Mon 12/13/21	Thu 12/16/21	955,959
982	694	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Wed 12/15/21	Thu 12/16/21	981FF
983	695	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Wed 12/15/21	Thu 12/16/21	982FF
984	696	NA	0%	REBAR BOTTOM (2day)	1 day	Fri 12/17/21	Mon 12/20/21	983FS+1 hr
985	697	NA	0%	MEPS ROUGH IN	1 day	Fri 12/17/21	Mon 12/20/21	984FF
986	698	NA	0%	REBAR TOP	2 days	Mon 12/20/21	Wed 12/22/21	984
987	699	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Tue 12/21/21	Wed 12/22/21	986FF
988	700	NA	0%	INSPECTION	1 day	Tue 12/21/21	Wed 12/22/21	987FF,985SS
989	701	NA	0%	<b>POUR DECK L5 MCALLISTER</b>	0 days	Thu 12/23/21	Thu 12/23/21	988FS+1 day
990	702	NA	0%	CURE	3 edays	Thu 12/23/21	Sun 12/26/21	989SS
991	703	NA	0%	STRESS L5 MCALLISTER	1 day	Mon 12/27/21	Mon 12/27/21	990
992	704	NA	0%	STRIP DECK	2 days	Tue 12/28/21	Wed 12/29/21	991
993	<b>705</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL</b>	<b>6.25 days</b>	<b>Wed 12/15/21</b>	<b>Fri 12/24/21</b>	
994	706	NA	0%	LEADSIDE WALL FORMWORK	1 day	Wed 12/15/21	Thu 12/16/21	981FF
995	707	NA	0%	INSTALL REINFORCEMENT	4 days	Thu 12/16/21	Wed 12/22/21	986FF,994SS
996	708	NA	0%	DOUBLE UP FORMWORK	1 day	Wed 12/22/21	Thu 12/23/21	989FF,995SS
997	709	NA	0%	INSPECTION	1 day	Wed 12/22/21	Thu 12/23/21	996FF
998	710	NA	0%	POUR COREWALL	0 days	Thu 12/23/21	Thu 12/23/21	997FF
999	711	NA	0%	STRIP & CLEANUP	1 day	Thu 12/23/21	Fri 12/24/21	998
1000	<b>712</b>	<b>NA</b>	<b>0%</b>	<b>AREA 2 - HYDE STREET (B1)</b>	<b>14.88 days</b>	<b>Fri 12/17/21</b>	<b>Thu 1/6/22</b>	
1001	<b>713</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDE DECK - POUR #2 (7 DAY CYCLE):</b>	<b>14.88 days</b>	<b>Fri 12/17/21</b>	<b>Thu 1/6/22</b>	
1002	714	NA	0%	PROSHORE SHORING (3day)	2 days	Fri 12/17/21	Tue 12/21/21	981FS+1 hr,976
1003	715	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Mon 12/20/21	Tue 12/21/21	1002FF
1004	716	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Mon 12/20/21	Tue 12/21/21	1003FF
1005	717	NA	0%	REBAR BOTTOM	2 days	Wed 12/22/21	Mon 12/27/21	1004,986FS+1 hr
1006	718	NA	0%	MEPS ROUGH IN	1 day	Fri 12/24/21	Mon 12/27/21	1005FF
1007	719	NA	0%	REBAR TOP	1 day	Mon 12/27/21	Tue 12/28/21	1005
1008	720	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Mon 12/27/21	Tue 12/28/21	1007FF
1009	721	NA	0%	INSPECTION	1 day	Mon 12/27/21	Tue 12/28/21	1008FF,1006SS
1010	722	NA	0%	<b>POUR DECK L5 HYDE</b>	0 days	Wed 12/29/21	Wed 12/29/21	1009FS+1 day
1011	723	NA	0%	CURE	3 edays	Wed 12/29/21	Sat 1/1/22	1010SS
1012	724	NA	0%	STRESS L5 HYDE	1 day	Mon 1/3/22	Mon 1/3/22	1011
1013	725	NA	0%	STRIP DECK	3 days	Tue 1/4/22	Thu 1/6/22	1012
1014	<b>726</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL</b>	<b>8.13 days</b>	<b>Mon 12/20/21</b>	<b>Thu 12/30/21</b>	
1015	727	NA	0%	LEADSIDE WALL FORMWORK	1 day	Mon 12/20/21	Tue 12/21/21	1002FF
1016	728	NA	0%	INSTALL REINFORCEMENT	3 days	Thu 12/23/21	Tue 12/28/21	1007FF,1015SS
1017	729	NA	0%	DOUBLE UP FORMWORK	1 day	Tue 12/28/21	Wed 12/29/21	1010FF,1016SS
1018	730	NA	0%	INSPECTION	1 day	Tue 12/28/21	Wed 12/29/21	1017FF
1019	731	NA	0%	POUR COREWALL	0 days	Wed 12/29/21	Wed 12/29/21	1018FF
1020	732	NA	0%	STRIP & CLEANUP	1 day	Wed 12/29/21	Thu 12/30/21	1019
1021	<b>733</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 6</b>	<b>15 days</b>	<b>Fri 12/24/21</b>	<b>Thu 1/13/22</b>	
1022	<b>734</b>	<b>NA</b>	<b>0%</b>	<b>AREA 1 - MCALLISTER STREET (A1/A2)</b>	<b>14 days</b>	<b>Fri 12/24/21</b>	<b>Wed 1/12/22</b>	

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1023	<b>735</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDED DECK - POUR #1 (9 DAY CYCLE):</b>	<b>14 days</b>	<b>Fri 12/24/21</b>	<b>Wed 1/12/22</b>	
1024	736	NA	0%	PROSHORE SHORING L6	4 days	Fri 12/24/21	Wed 12/29/21	998,1002,992FF
1025	737	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Wed 12/29/21	Wed 12/29/21	1024FF
1026	738	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Wed 12/29/21	Wed 12/29/21	1025FF
1027	739	NA	0%	REBAR BOTTOM	2 days	Thu 12/30/21	Fri 12/31/21	1026
1028	740	NA	0%	MEPS ROUGH IN	1 day	Fri 12/31/21	Fri 12/31/21	1027FF
1029	741	NA	0%	REBAR TOP	2 days	Mon 1/3/22	Tue 1/4/22	1027
1030	742	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Tue 1/4/22	Tue 1/4/22	1029FF
1031	743	NA	0%	INSPECTION	1 day	Tue 1/4/22	Tue 1/4/22	1030FF,1028SS
1032	744	NA	0%	<b>POUR DECK L6 MCALLISTER</b>	0 days	Wed 1/5/22	Wed 1/5/22	1031FS+1 day
1033	745	NA	0%	CURE	3 edays	Wed 1/5/22	Sat 1/8/22	1032SS
1034	746	NA	0%	STRESS L 6	1 day	Mon 1/10/22	Mon 1/10/22	1033
1035	747	NA	0%	STRIP DECK L 6	2 days	Tue 1/11/22	Wed 1/12/22	1034
1036	<b>748</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL</b>	<b>7 days</b>	<b>Wed 12/29/21</b>	<b>Thu 1/6/22</b>	
1037	749	NA	0%	LEADSIDE WALL FORMWORK	1 day	Wed 12/29/21	Wed 12/29/21	1024FF
1038	750	NA	0%	INSTALL REINFORCEMENT	4 days	Thu 12/30/21	Tue 1/4/22	1029FF,1037SS
1039	751	NA	0%	DOUBLE UP FORMWORK	1 day	Wed 1/5/22	Wed 1/5/22	1032FF,1038SS
1040	752	NA	0%	INSPECTION	1 day	Wed 1/5/22	Wed 1/5/22	1039FF
1041	753	NA	0%	POUR COREWALL	0 days	Wed 1/5/22	Wed 1/5/22	1040FF
1042	754	NA	0%	STRIP & CLEANUP	1 day	Thu 1/6/22	Thu 1/6/22	1041
1043	<b>755</b>	<b>NA</b>	<b>0%</b>	<b>AREA 2 - HYDE STREET (B1)</b>	<b>10 days</b>	<b>Fri 12/31/21</b>	<b>Thu 1/13/22</b>	
1044	<b>756</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDED DECK - POUR #1 (9 DAY CYCLE):-1</b>	<b>10 days</b>	<b>Fri 12/31/21</b>	<b>Thu 1/13/22</b>	
1045	757	NA	0%	PROSHORE SHORING (3day)	2 days	Fri 12/31/21	Mon 1/3/22	1019,1024FS+1 day
1046	758	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Mon 1/3/22	Mon 1/3/22	1045FF
1047	759	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Mon 1/3/22	Mon 1/3/22	1046FF
1048	760	NA	0%	REBAR BOTTOM	2 days	Tue 1/4/22	Wed 1/5/22	1047
1049	761	NA	0%	MEPS ROUGH IN	1 day	Wed 1/5/22	Wed 1/5/22	1048FF
1050	762	NA	0%	REBAR TOP	1 day	Thu 1/6/22	Thu 1/6/22	1048
1051	763	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Wed 1/5/22	Thu 1/6/22	1050FF
1052	764	NA	0%	INSPECTION	1 day	Wed 1/5/22	Thu 1/6/22	1051FF,1049SS
1053	765	NA	0%	<b>POUR DECK L6 HYDE</b>	1 day	Fri 1/7/22	Fri 1/7/22	1052
1054	766	NA	0%	CURE	3 edays	Fri 1/7/22	Mon 1/10/22	1053SS
1055	767	NA	0%	STRESS	1 day	Mon 1/10/22	Mon 1/10/22	1054
1056	768	NA	0%	STRIP DECK L6 HYDE	3 days	Tue 1/11/22	Thu 1/13/22	1055
1057	<b>769</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL</b>	<b>5.88 days</b>	<b>Mon 1/3/22</b>	<b>Mon 1/10/22</b>	
1058	770	NA	0%	LEADSIDE WALL FORMWORK	1 day	Mon 1/3/22	Mon 1/3/22	1045FF
1059	771	NA	0%	INSTALL REINFORCEMENT	3 days	Mon 1/3/22	Thu 1/6/22	1050FF,1058SS
1060	772	NA	0%	DOUBLE UP FORMWORK	1 day	Thu 1/6/22	Fri 1/7/22	1053FF,1059SS
1061	773	NA	0%	INSPECTION	1 day	Thu 1/6/22	Fri 1/7/22	1060FF
1062	774	NA	0%	POUR COREWALL	1 day	Thu 1/6/22	Fri 1/7/22	1061FF
1063	775	NA	0%	STRIP & CLEANUP	1 day	Fri 1/7/22	Mon 1/10/22	1062
1064	<b>776</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 7</b>	<b>18.13 days</b>	<b>Fri 1/7/22</b>	<b>Wed 2/2/22</b>	
1065	<b>777</b>	<b>NA</b>	<b>0%</b>	<b>AREA 1 - MCALLISTER STREET (A1/A2)</b>	<b>15 days</b>	<b>Fri 1/7/22</b>	<b>Thu 1/27/22</b>	
1066	<b>778</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDED DECK - POUR #1 (9 DAY CYCLE):</b>	<b>15 days</b>	<b>Fri 1/7/22</b>	<b>Thu 1/27/22</b>	
1067	779	NA	0%	PROSHORE SHORING L7	4 days	Fri 1/7/22	Wed 1/12/22	1041,1045,1042,1035FF
1068	780	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Wed 1/12/22	Wed 1/12/22	1067FF
1069	781	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Wed 1/12/22	Wed 1/12/22	1068FF

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1070	782	NA	0%	REBAR BOTTOM	2 days	Thu 1/13/22	Fri 1/14/22	1069
1071	783	NA	0%	MEPS ROUGH IN	1 day	Fri 1/14/22	Fri 1/14/22	1070FF
1072	784	NA	0%	REBAR TOP	2 days	Mon 1/17/22	Tue 1/18/22	1071
1073	785	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Tue 1/18/22	Tue 1/18/22	1072FF
1074	786	NA	0%	INSPECTION	1 day	Tue 1/18/22	Tue 1/18/22	1073FF
1075	787	NA	0%	POUR DECK L7 MCALLISTER	0 days	Wed 1/19/22	Wed 1/19/22	1074FS+1 day
1076	788	NA	0%	CURE	3 edays	Wed 1/19/22	Sat 1/22/22	1075SS
1077	789	NA	0%	STRESS L 7 MCALLISTER	1 day	Mon 1/24/22	Mon 1/24/22	1076
1078	790	NA	0%	STRIP DECK	3 days	Tue 1/25/22	Thu 1/27/22	1077
1079	791	NA	0%	COREWALL	10 days	Fri 1/7/22	Thu 1/20/22	
1080	792	NA	0%	LEADSIDE WALL FORMWORK	1 day	Fri 1/7/22	Fri 1/7/22	1067SS
1081	793	NA	0%	INSTALL REINFORCEMENT	4 days	Thu 1/13/22	Tue 1/18/22	1072FF,1080SS
1082	794	NA	0%	DOUBLE UP FORMWORK	1 day	Wed 1/19/22	Wed 1/19/22	1075FF,1081SS
1083	795	NA	0%	INSPECTION	1 day	Wed 1/19/22	Wed 1/19/22	1082FF
1084	796	NA	0%	POUR COREWALL	1 day	Wed 1/19/22	Wed 1/19/22	1083FF
1085	797	NA	0%	STRIP & CLEANUP	1 day	Thu 1/20/22	Thu 1/20/22	1084
1086	798	NA	0%	AREA 2 - HYDE STREET (B1)	14 days	Thu 1/13/22	Wed 2/2/22	
1087	799	NA	0%	SUSPENDEDECK - POUR #2 (7 DAY CYCLE):	14 days	Thu 1/13/22	Wed 2/2/22	
1088	800	NA	0%	PROSHORE SHORING L 7	3 days	Thu 1/13/22	Tue 1/18/22	1062,1067FS+1 hr
1089	801	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Mon 1/17/22	Tue 1/18/22	1088FF
1090	802	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Mon 1/17/22	Tue 1/18/22	1089FF
1091	803	NA	0%	REBAR BOTTOM	2 days	Tue 1/18/22	Thu 1/20/22	1090
1092	804	NA	0%	MEPS ROUGH IN	1 day	Wed 1/19/22	Thu 1/20/22	1091FF
1093	805	NA	0%	REBAR TOP	1 day	Thu 1/20/22	Fri 1/21/22	1092
1094	806	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Thu 1/20/22	Fri 1/21/22	1093FF
1095	807	NA	0%	INSPECTION	1 day	Thu 1/20/22	Fri 1/21/22	1094FF
1096	808	NA	0%	POUR DECK L7 HYDE	0 days	Mon 1/24/22	Mon 1/24/22	1095FS+1 day
1097	809	NA	0%	CURE	3 edays	Mon 1/24/22	Thu 1/27/22	1096SS
1098	810	NA	0%	STRESS L7 HYDE	1 day	Thu 1/27/22	Fri 1/28/22	1097
1099	811	NA	0%	STRIP DECK	3 days	Fri 1/28/22	Wed 2/2/22	1098
1100	812	NA	0%	COREWALL	8 days	Thu 1/13/22	Tue 1/25/22	
1101	813	NA	0%	LEADSIDE WALL FORMWORK	1 day	Thu 1/13/22	Fri 1/14/22	1088SS
1102	814	NA	0%	INSTALL REINFORCEMENT	3 days	Tue 1/18/22	Fri 1/21/22	1093FF,1101SS
1103	815	NA	0%	DOUBLE UP FORMWORK	0 days	Mon 1/24/22	Mon 1/24/22	1096,1102SS
1104	816	NA	0%	INSPECTION	1 day	Fri 1/21/22	Mon 1/24/22	1103FF
1105	817	NA	0%	POUR COREWALL	1 day	Fri 1/21/22	Mon 1/24/22	1096FF
1106	818	NA	0%	STRIP & CLEANUP	1 day	Mon 1/24/22	Tue 1/25/22	1105
1107	819	NA	0%	LEVEL 8	16.88 days	Thu 1/20/22	Fri 2/11/22	
1108	820	NA	0%	AREA 1 - MCALLISTER STREET (A1/A2)	14 days	Thu 1/20/22	Wed 2/9/22	
1109	821	NA	0%	SUSPENDEDECK - POUR #1 (7 DAY CYCLE):	14 days	Thu 1/20/22	Wed 2/9/22	
1110	822	NA	0%	PROSHORE SHORING L 8	3 days	Thu 1/20/22	Tue 1/25/22	1088FS+1 hr,1084FS+1 hr
1111	823	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Mon 1/24/22	Tue 1/25/22	1110FF
1112	824	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Mon 1/24/22	Tue 1/25/22	1111FF
1113	825	NA	0%	REBAR BOTTOM	2 days	Tue 1/25/22	Thu 1/27/22	1112
1114	826	NA	0%	MEPS ROUGH IN	1 day	Wed 1/26/22	Thu 1/27/22	1113FF
1115	827	NA	0%	REBAR TOP	1 day	Thu 1/27/22	Fri 1/28/22	1113
1116	828	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Thu 1/27/22	Fri 1/28/22	1115FF

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1117	829	NA	0%	INSPECTION	1 day	Thu 1/27/22	Fri 1/28/22	1116FF,1114SS
1118	830	NA	0%	POUR DECK L8 MCALLISTER	0 days	Mon 1/31/22	Mon 1/31/22	1117FS+1 day
1119	831	NA	0%	CURE	3 edays	Mon 1/31/22	Thu 2/3/22	1118SS
1120	832	NA	0%	STRESS L 8	1 day	Thu 2/3/22	Fri 2/4/22	1119
1121	833	NA	0%	STRIP DECK	3 days	Fri 2/4/22	Wed 2/9/22	1120
1122	834	NA	0%	COREWALL	6 days	Mon 1/24/22	Tue 2/1/22	
1123	835	NA	0%	LEADSIDE WALL FORMWORK	1 day	Mon 1/24/22	Tue 1/25/22	1110FF
1124	836	NA	0%	INSTALL REINFORCEMENT	3 days	Tue 1/25/22	Fri 1/28/22	1115FF,1123SS
1125	837	NA	0%	DOUBLE UP FORMWORK	0 days	Mon 1/31/22	Mon 1/31/22	1118,1124SS
1126	838	NA	0%	INSPECTION	1 day	Fri 1/28/22	Mon 1/31/22	1125FF
1127	839	NA	0%	POUR COREWALL	1 day	Fri 1/28/22	Mon 1/31/22	1126FF
1128	840	NA	0%	STRIP & CLEANUP	1 day	Mon 1/31/22	Tue 2/1/22	1127
1129	841	NA	0%	AREA 2 - HYDE STREET (B1)	12.88 days	Wed 1/26/22	Fri 2/11/22	
1130	842	NA	0%	SUSPENDED DECK - POUR #2 (7 DAY CYCLE):	12.88 days	Wed 1/26/22	Fri 2/11/22	
1131	843	NA	0%	PROSHORE SHORING (3 day duration)	2 days	Wed 1/26/22	Fri 1/28/22	1105,1110FS+1 day
1132	844	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Thu 1/27/22	Fri 1/28/22	1131FF
1133	845	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Thu 1/27/22	Fri 1/28/22	1132FF
1134	846	NA	0%	REBAR BOTTOM	2 days	Fri 1/28/22	Tue 2/1/22	1133
1135	847	NA	0%	MEPS ROUGH IN	1 day	Mon 1/31/22	Tue 2/1/22	1134FF
1136	848	NA	0%	REBAR TOP	1 day	Tue 2/1/22	Wed 2/2/22	1134
1137	849	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Tue 2/1/22	Wed 2/2/22	1136FF
1138	850	NA	0%	INSPECTION	1 day	Tue 2/1/22	Wed 2/2/22	1137FF,1135SS
1139	851	NA	0%	POUR DECK L8 HYDE	0 days	Thu 2/3/22	Thu 2/3/22	1138FS+1 day
1140	852	NA	0%	CURE	3 edays	Thu 2/3/22	Sun 2/6/22	1139SS
1141	853	NA	0%	STRESS	1 day	Mon 2/7/22	Mon 2/7/22	1140
1142	854	NA	0%	STRIP DECK	3 days	Tue 2/8/22	Thu 2/10/22	1141
1143	7197	NA	0%	INSTALL ELEVATORS 2,3,4,5 CRASH DECK L8	1 day	Fri 2/11/22	Fri 2/11/22	1142
1144	855	NA	0%	COREWALL	6 days	Thu 1/27/22	Fri 2/4/22	
1145	856	NA	0%	LEADSIDE WALL FORMWORK	1 day	Thu 1/27/22	Fri 1/28/22	1131FF
1146	857	NA	0%	INSTALL REINFORCEMENT	2 days	Mon 1/31/22	Wed 2/2/22	1136FF,1145SS
1147	858	NA	0%	DOUBLE UP FORMWORK	0 days	Thu 2/3/22	Thu 2/3/22	1139,1146SS
1148	859	NA	0%	INSPECTION	1 day	Wed 2/2/22	Thu 2/3/22	1147FF
1149	860	NA	0%	POUR COREWALL	1 day	Wed 2/2/22	Thu 2/3/22	1148FF
1150	861	NA	0%	STRIP & CLEANUP	1 day	Thu 2/3/22	Fri 2/4/22	1149
1151	862	NA	0%	LEVEL 9	19.88 days	Mon 1/31/22	Fri 2/25/22	
1152	863	NA	0%	AREA 1 - MCALLISTER STREET (A1/A2)	17 days	Mon 1/31/22	Wed 2/23/22	
1153	864	NA	0%	SUSPENDED DECK - POUR #1 (9 DAY CYCLE):	17 days	Mon 1/31/22	Wed 2/23/22	
1154	865	NA	0%	PROSHORE SHORING L 9	5 days	Mon 1/31/22	Mon 2/7/22	1127,1131
1155	866	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Fri 2/4/22	Mon 2/7/22	1154FF
1156	867	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Fri 2/4/22	Mon 2/7/22	1155FF
1157	868	NA	0%	REBAR BOTTOM	2 days	Mon 2/7/22	Wed 2/9/22	1156
1158	869	NA	0%	MEPS ROUGH IN	1 day	Tue 2/8/22	Wed 2/9/22	1157FF
1159	870	NA	0%	REBAR TOP	2 days	Wed 2/9/22	Fri 2/11/22	1157
1160	871	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Thu 2/10/22	Fri 2/11/22	1159FF
1161	872	NA	0%	INSPECTION	1 day	Thu 2/10/22	Fri 2/11/22	1160FF,1158SS
1162	873	NA	0%	POUR DECK L9 MCALLISTER	1 day	Mon 2/14/22	Tue 2/15/22	1161FS+1 day
1163	874	NA	0%	CURE	3 edays	Mon 2/14/22	Thu 2/17/22	1162SS

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1164	875	NA	0%	STRESS L9 MCALLISTER	1 day	Thu 2/17/22	Fri 2/18/22	1163
1165	876	NA	0%	STRIP DECK	3 days	Fri 2/18/22	Wed 2/23/22	1164
1166	<b>877</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL</b>	<b>8 days</b>	<b>Fri 2/4/22</b>	<b>Wed 2/16/22</b>	
1167	878	NA	0%	LEADSIDE WALL FORMWORK	1 day	Fri 2/4/22	Mon 2/7/22	1154FF
1168	879	NA	0%	INSTALL REINFORCEMENT	4 days	Mon 2/7/22	Fri 2/11/22	1159FF,1167SS
1169	880	NA	0%	DOUBLE UP FORMWORK	0 days	Tue 2/15/22	Tue 2/15/22	1162,1168SS
1170	881	NA	0%	INSPECTION	1 day	Mon 2/14/22	Tue 2/15/22	1169FF
1171	882	NA	0%	POUR COREWALL	1 day	Mon 2/14/22	Tue 2/15/22	1170FF
1172	883	NA	0%	STRIP & CLEANUP	1 day	Tue 2/15/22	Wed 2/16/22	1171
1173	<b>884</b>	<b>NA</b>	<b>0%</b>	<b>AREA 2 - HYDE STREET (B1)</b>	<b>14.88 days</b>	<b>Mon 2/7/22</b>	<b>Fri 2/25/22</b>	
1174	<b>885</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDED DECK - POUR #2 (7 DAY CYCLE):</b>	<b>14.88 days</b>	<b>Mon 2/7/22</b>	<b>Fri 2/25/22</b>	
1175	886	NA	0%	PROSHORE SHORING	3 days	Mon 2/7/22	Thu 2/10/22	1154,1149
1176	887	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Wed 2/9/22	Thu 2/10/22	1175FF
1177	888	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Wed 2/9/22	Thu 2/10/22	1176FF
1178	889	NA	0%	REBAR BOTTOM	2 days	Fri 2/11/22	Tue 2/15/22	1177,1159
1179	890	NA	0%	MEPS ROUGH IN	1 day	Mon 2/14/22	Tue 2/15/22	1178FF
1180	891	NA	0%	REBAR TOP	1 day	Tue 2/15/22	Wed 2/16/22	1178
1181	892	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Tue 2/15/22	Wed 2/16/22	1180FF
1182	893	NA	0%	INSPECTION	1 day	Tue 2/15/22	Wed 2/16/22	1181FF,1179SS
1183	894	NA	0%	<b>POUR DECK L9 HYDE</b>	0 days	Thu 2/17/22	Thu 2/17/22	1182FS+1 day
1184	895	NA	0%	CURE	3 edays	Thu 2/17/22	Sun 2/20/22	1183SS
1185	896	NA	0%	STRESS L9 HYDE	1 day	Mon 2/21/22	Mon 2/21/22	1184
1186	897	NA	0%	STRIP DECK	3 days	Tue 2/22/22	Thu 2/24/22	1185
1187	7199	NA	0%	INSTALL ELEVATORS 2,3,4,5 CRASH DECK WITH TEMP ROOF L9	1 day	Fri 2/25/22	Fri 2/25/22	1186
1188	<b>898</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL</b>	<b>7 days</b>	<b>Wed 2/9/22</b>	<b>Fri 2/18/22</b>	
1189	899	NA	0%	LEADSIDE WALL FORMWORK	1 day	Wed 2/9/22	Thu 2/10/22	1175FF
1190	900	NA	0%	INSTALL REINFORCEMENT	3 days	Fri 2/11/22	Wed 2/16/22	1180FF,1189SS
1191	901	NA	0%	DOUBLE UP FORMWORK	0 days	Thu 2/17/22	Thu 2/17/22	1183,1190SS
1192	902	NA	0%	INSPECTION	1 day	Wed 2/16/22	Thu 2/17/22	1191FF
1193	903	NA	0%	POUR COREWALL	1 day	Wed 2/16/22	Thu 2/17/22	1192FF
1194	904	NA	0%	STRIP & CLEANUP L9 COREWALL	1 day	Thu 2/17/22	Fri 2/18/22	1193
1195	<b>905</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 10</b>	<b>17.88 days</b>	<b>Tue 2/15/22</b>	<b>Thu 3/10/22</b>	
1196	<b>906</b>	<b>NA</b>	<b>0%</b>	<b>AREA 1 - MCALLISTER STREET (A1/A2)</b>	<b>13 days</b>	<b>Tue 2/15/22</b>	<b>Fri 3/4/22</b>	
1197	<b>907</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDED DECK - POUR #1 (9 DAY CYCLE):</b>	<b>13 days</b>	<b>Tue 2/15/22</b>	<b>Fri 3/4/22</b>	
1198	908	NA	0%	PROSHORE SHORING L 10	4 days	Tue 2/15/22	Mon 2/21/22	1171,1175
1199	909	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Fri 2/18/22	Mon 2/21/22	1198FF
1200	910	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Fri 2/18/22	Mon 2/21/22	1199FF
1201	911	NA	0%	REBAR BOTTOM (2 day duration)	1 day	Tue 2/22/22	Wed 2/23/22	1200FS+1 day
1202	912	NA	0%	MEPS ROUGH IN	1 day	Tue 2/22/22	Wed 2/23/22	1201FF
1203	913	NA	0%	REBAR TOP	1 day	Wed 2/23/22	Thu 2/24/22	1201
1204	914	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Wed 2/23/22	Thu 2/24/22	1203FF
1205	915	NA	0%	INSPECTION	1 day	Wed 2/23/22	Thu 2/24/22	1204FF
1206	916	NA	0%	<b>POUR DECK L10 MCALLISTER</b>	0 days	Fri 2/25/22	Fri 2/25/22	1205FS+1 day
1207	917	NA	0%	CURE	3 edays	Fri 2/25/22	Mon 2/28/22	1206SS
1208	918	NA	0%	STRESS L 10	1 day	Mon 2/28/22	Tue 3/1/22	1207
1209	919	NA	0%	STRIP DECK	3 days	Tue 3/1/22	Fri 3/4/22	1208
1210	<b>920</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL</b>	<b>6 days</b>	<b>Fri 2/18/22</b>	<b>Mon 2/28/22</b>	

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1211	921	NA	0%	LEADSIDE WALL FORMWORK	1 day	Fri 2/18/22	Mon 2/21/22	1198FF
1212	922	NA	0%	INSTALL REINFORCEMENT	4 days	Fri 2/18/22	Thu 2/24/22	1203FF,1211SS
1213	923	NA	0%	DOUBLE UP FORMWORK	0 days	Fri 2/25/22	Fri 2/25/22	1206,1212SS
1214	924	NA	0%	INSPECTION	1 day	Thu 2/24/22	Fri 2/25/22	1213FF
1215	925	NA	0%	POUR COREWALL	1 day	Thu 2/24/22	Fri 2/25/22	1214FF
1216	926	NA	0%	STRIP & CLEANUP	1 day	Fri 2/25/22	Mon 2/28/22	1215
1217	<b>927</b>	<b>NA</b>	<b>0%</b>	<b>AREA 2 - HYDE STREET (B1)</b>	<b>13.88 days</b>	<b>Mon 2/21/22</b>	<b>Thu 3/10/22</b>	
1218	<b>928</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDED DECK - POUR #2 (7 DAY CYCLE):</b>	<b>13.88 days</b>	<b>Mon 2/21/22</b>	<b>Thu 3/10/22</b>	
1219	929	NA	0%	PROSHORE SHORING	3 days	Mon 2/21/22	Thu 2/24/22	1198,1193
1220	930	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Wed 2/23/22	Thu 2/24/22	1219FF
1221	931	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Wed 2/23/22	Thu 2/24/22	1220FF
1222	932	NA	0%	REBAR BOTTOM	2 days	Thu 2/24/22	Mon 2/28/22	1221,1203
1223	933	NA	0%	MEPS ROUGH IN	1 day	Fri 2/25/22	Mon 2/28/22	1222FF
1224	934	NA	0%	REBAR TOP	1 day	Mon 2/28/22	Tue 3/1/22	1222
1225	935	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Mon 2/28/22	Tue 3/1/22	1224FF
1226	936	NA	0%	INSPECTION	1 day	Mon 2/28/22	Tue 3/1/22	1225FF,1223SS
1227	937	NA	0%	<b>POUR DECK L10 HYDE</b>	0 days	Wed 3/2/22	Wed 3/2/22	1226FS+1 day
1228	938	NA	0%	CURE	3 edays	Wed 3/2/22	Sat 3/5/22	1227SS
1229	939	NA	0%	STRESS	1 day	Mon 3/7/22	Mon 3/7/22	1228
1230	940	NA	0%	STRIP DECK	3 days	Tue 3/8/22	Thu 3/10/22	1229
1231	<b>941</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL</b>	<b>6 days</b>	<b>Wed 2/23/22</b>	<b>Thu 3/3/22</b>	
1232	942	NA	0%	LEADSIDE WALL FORMWORK	1 day	Wed 2/23/22	Thu 2/24/22	1219FF
1233	943	NA	0%	INSTALL REINFORCEMENT	3 days	Thu 2/24/22	Tue 3/1/22	1224FF,1232SS
1234	944	NA	0%	DOUBLE UP FORMWORK	0 days	Wed 3/2/22	Wed 3/2/22	1227,1233SS
1235	945	NA	0%	INSPECTION	1 day	Tue 3/1/22	Wed 3/2/22	1234FF
1236	946	NA	0%	POUR COREWALL	1 day	Tue 3/1/22	Wed 3/2/22	1235FF
1237	947	NA	0%	STRIP & CLEANUP L10 CORE WALL	1 day	Wed 3/2/22	Thu 3/3/22	1236
1238	10198	NA	0%	INSTALL ELEVATORS 2,3,4,5 CRASH DECK L10 (WORKING DECK NOT REQUIRED PER KONE DAN MAY)	1 day	Wed 3/2/22	Thu 3/3/22	1237FF
1239	<b>948</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 11</b>	<b>19 days</b>	<b>Fri 2/25/22</b>	<b>Thu 3/24/22</b>	
1240	<b>949</b>	<b>NA</b>	<b>0%</b>	<b>AREA 1 - MCALLISTER STREET (A1/A2)</b>	<b>14.88 days</b>	<b>Fri 2/25/22</b>	<b>Thu 3/17/22</b>	
1241	<b>950</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDED DECK - POUR #1 (9 DAY CYCLE):</b>	<b>14.88 days</b>	<b>Fri 2/25/22</b>	<b>Thu 3/17/22</b>	
1242	951	NA	0%	PROSHORE SHORING L 11	4 days	Fri 2/25/22	Thu 3/3/22	1215,1219
1243	952	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Wed 3/2/22	Thu 3/3/22	1242FF
1244	953	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Wed 3/2/22	Thu 3/3/22	1243FF
1245	954	NA	0%	REBAR BOTTOM	2 days	Thu 3/3/22	Mon 3/7/22	1244
1246	955	NA	0%	MEPS ROUGH IN	1 day	Fri 3/4/22	Mon 3/7/22	1245FF
1247	956	NA	0%	REBAR TOP	2 days	Mon 3/7/22	Wed 3/9/22	1246
1248	957	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Tue 3/8/22	Wed 3/9/22	1247FF
1249	958	NA	0%	INSPECTION	1 day	Tue 3/8/22	Wed 3/9/22	1248FF
1250	959	NA	0%	<b>POUR DECK L11 MCALLISTER</b>	0 days	Thu 3/10/22	Thu 3/10/22	1249FS+1 day
1251	960	NA	0%	CURE	3 edays	Thu 3/10/22	Sun 3/13/22	1250SS
1252	961	NA	0%	STRESS L 11 MCALLISTER	1 day	Mon 3/14/22	Mon 3/14/22	1251
1253	962	NA	0%	STRIP DECK	3 days	Tue 3/15/22	Thu 3/17/22	1252
1254	<b>963</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL</b>	<b>7 days</b>	<b>Wed 3/2/22</b>	<b>Fri 3/11/22</b>	
1255	964	NA	0%	LEADSIDE WALL FORMWORK	1 day	Wed 3/2/22	Thu 3/3/22	1242FF
1256	965	NA	0%	INSTALL REINFORCEMENT	4 days	Thu 3/3/22	Wed 3/9/22	1247FF,1255SS



University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1257	966	NA	0%	DOUBLE UP FORMWORK	0 days	Thu 3/10/22	Thu 3/10/22	1250,1256SS
1258	967	NA	0%	INSPECTION	1 day	Wed 3/9/22	Thu 3/10/22	1257FF
1259	968	NA	0%	POUR COREWALL	1 day	Wed 3/9/22	Thu 3/10/22	1258FF
1260	969	NA	0%	STRIP & CLEANUP	1 day	Thu 3/10/22	Fri 3/11/22	1259
1261	<b>970</b>	<b>NA</b>	<b>0%</b>	<b>AREA 2 - HYDE STREET (B1)</b>	<b>15 days</b>	<b>Thu 3/3/22</b>	<b>Thu 3/24/22</b>	
1262	<b>971</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDED DECK - POUR #2 (7 DAY CYCLE):</b>	<b>15 days</b>	<b>Thu 3/3/22</b>	<b>Thu 3/24/22</b>	
1263	972	NA	0%	PROSHORE SHORING	3 days	Thu 3/3/22	Tue 3/8/22	1236,1242
1264	973	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Mon 3/7/22	Tue 3/8/22	1263FF
1265	974	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Mon 3/7/22	Tue 3/8/22	1264FF
1266	975	NA	0%	REBAR BOTTOM	2 days	Wed 3/9/22	Fri 3/11/22	1265,1247
1267	976	NA	0%	MEPS ROUGH IN	1 day	Thu 3/10/22	Fri 3/11/22	1266FF
1268	977	NA	0%	REBAR TOP	1 day	Fri 3/11/22	Mon 3/14/22	1267
1269	978	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Fri 3/11/22	Mon 3/14/22	1268FF
1270	979	NA	0%	INSPECTION	1 day	Fri 3/11/22	Mon 3/14/22	1269FF
1271	980	NA	0%	<b>POUR DECK L11 HYDE</b>	0 days	Tue 3/15/22	Tue 3/15/22	1270FS+1 day
1272	981	NA	0%	CURE	3 edays	Tue 3/15/22	Fri 3/18/22	1271SS
1273	982	NA	0%	STRESS L11 HYDE	1 day	Fri 3/18/22	Mon 3/21/22	1272
1274	983	NA	0%	STRIP DECK	3 days	Mon 3/21/22	Thu 3/24/22	1273
1275	<b>984</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL</b>	<b>8 days</b>	<b>Mon 3/7/22</b>	<b>Thu 3/17/22</b>	
1276	985	NA	0%	LEADSIDE WALL FORMWORK	1 day	Mon 3/7/22	Tue 3/8/22	1263FF
1277	986	NA	0%	INSTALL REINFORCEMENT	3 days	Wed 3/9/22	Mon 3/14/22	1268FF,1276SS
1278	987	NA	0%	DOUBLE UP FORMWORK	0 days	Tue 3/15/22	Tue 3/15/22	1271,1277SS
1279	988	NA	0%	INSPECTION	1 day	Mon 3/14/22	Tue 3/15/22	1278FF
1280	989	NA	0%	POUR COREWALL	1 day	Mon 3/14/22	Tue 3/15/22	1279FF
1281	990	NA	0%	STRIP & CLEANUP L 11 CORE WALL	1 day	Tue 3/15/22	Wed 3/16/22	1280
1282	10469	NA	0%	INSTALL ELEVATORS 2,3,4,5 CRASH DECK L11 (WORKING DECK NOT REQUI	1 day	Wed 3/16/22	Thu 3/17/22	1281
1283	<b>991</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 12</b>	<b>19 days</b>	<b>Thu 3/10/22</b>	<b>Wed 4/6/22</b>	
1284	<b>992</b>	<b>NA</b>	<b>0%</b>	<b>AREA 1 - MCALLISTER STREET (A1/A2)</b>	<b>15.88 days</b>	<b>Thu 3/10/22</b>	<b>Thu 3/31/22</b>	
1285	<b>993</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDED DECK - POUR #1 (9 DAY CYCLE):</b>	<b>15.88 days</b>	<b>Thu 3/10/22</b>	<b>Thu 3/31/22</b>	
1286	994	NA	0%	PROSHORE SHORING L 12	4 days	Thu 3/10/22	Wed 3/16/22	1259,1263
1287	995	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Tue 3/15/22	Wed 3/16/22	1286FF
1288	996	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Tue 3/15/22	Wed 3/16/22	1287FF
1289	997	NA	0%	REBAR BOTTOM	2 days	Wed 3/16/22	Fri 3/18/22	1288
1290	998	NA	0%	MEPS ROUGH IN	1 day	Thu 3/17/22	Fri 3/18/22	1289FF
1291	999	NA	0%	REBAR TOP	2 days	Fri 3/18/22	Tue 3/22/22	1289
1292	1000	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Mon 3/21/22	Tue 3/22/22	1291FF
1293	1001	NA	0%	INSPECTION	1 day	Mon 3/21/22	Tue 3/22/22	1292FF,1290SS
1294	1002	NA	0%	<b>POUR DECK L12 McAllister ST</b>	0 days	Wed 3/23/22	Wed 3/23/22	1293FS+1 day
1295	1003	NA	0%	CURE	3 edays	Wed 3/23/22	Sat 3/26/22	1294SS
1296	1004	NA	0%	STRESS L 12	1 day	Mon 3/28/22	Mon 3/28/22	1295
1297	1005	NA	0%	STRIP DECK	3 days	Tue 3/29/22	Thu 3/31/22	1296
1298	<b>1006</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL</b>	<b>7 days</b>	<b>Tue 3/15/22</b>	<b>Thu 3/24/22</b>	
1299	1007	NA	0%	LEADSIDE WALL FORMWORK	1 day	Tue 3/15/22	Wed 3/16/22	1286FF
1300	1008	NA	0%	INSTALL REINFORCEMENT	4 days	Wed 3/16/22	Tue 3/22/22	1291FF,1299SS
1301	1009	NA	0%	DOUBLE UP FORMWORK	0 days	Wed 3/23/22	Wed 3/23/22	1294,1300SS
1302	1010	NA	0%	INSPECTION	1 day	Tue 3/22/22	Wed 3/23/22	1301FF
1303	1011	NA	0%	POUR COREWALL	1 day	Tue 3/22/22	Wed 3/23/22	1302FF



University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1304	1012	NA	0%	STRIP & CLEANUP	1 day	Wed 3/23/22	Thu 3/24/22	1303
1305	<b>1013</b>	<b>NA</b>	<b>0%</b>	<b>AREA 2 - HYDE STREET (B1)</b>	<b>15 days</b>	<b>Wed 3/16/22</b>	<b>Wed 4/6/22</b>	
1306	<b>1014</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDED DECK - POUR #2 (7 DAY CYCLE):</b>	<b>15 days</b>	<b>Wed 3/16/22</b>	<b>Wed 4/6/22</b>	
1307	1015	NA	0%	PROSHORE SHORING	3 days	Wed 3/16/22	Mon 3/21/22	1280,1286
1308	1016	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Fri 3/18/22	Mon 3/21/22	1307FF
1309	1017	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Fri 3/18/22	Mon 3/21/22	1308FF
1310	1018	NA	0%	REBAR BOTTOM	2 days	Tue 3/22/22	Thu 3/24/22	1309,1291
1311	1019	NA	0%	MEPS ROUGH IN	1 day	Wed 3/23/22	Thu 3/24/22	1310FF
1312	1020	NA	0%	REBAR TOP	1 day	Thu 3/24/22	Fri 3/25/22	1310
1313	1021	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Thu 3/24/22	Fri 3/25/22	1312FF
1314	1022	NA	0%	INSPECTION	1 day	Thu 3/24/22	Fri 3/25/22	1313FF,1311SS
1315	1023	NA	0%	<b>POUR DECK L12 Hyde ST</b>	0 days	Mon 3/28/22	Mon 3/28/22	1314FS+1 day
1316	1024	NA	0%	CURE	3 edays	Mon 3/28/22	Thu 3/31/22	1315SS
1317	1025	NA	0%	STRESS	1 day	Thu 3/31/22	Fri 4/1/22	1316
1318	1026	NA	0%	STRIP DECK	3 days	Fri 4/1/22	Wed 4/6/22	1317
1319	<b>1027</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL</b>	<b>7 days</b>	<b>Fri 3/18/22</b>	<b>Tue 3/29/22</b>	
1320	1028	NA	0%	LEADSIDE WALL FORMWORK	1 day	Fri 3/18/22	Mon 3/21/22	1307FF
1321	1029	NA	0%	INSTALL REINFORCEMENT	3 days	Tue 3/22/22	Fri 3/25/22	1312FF,1320SS
1322	1030	NA	0%	DOUBLE UP FORMWORK	0 days	Mon 3/28/22	Mon 3/28/22	1315,1321SS
1323	1031	NA	0%	INSPECTION	1 day	Fri 3/25/22	Mon 3/28/22	1322FF
1324	1032	NA	0%	POUR COREWALL	1 day	Fri 3/25/22	Mon 3/28/22	1323FF
1325	1033	NA	0%	STRIP & CLEANUP L 12 CORE WALL	1 day	Mon 3/28/22	Tue 3/29/22	1324
1326	<b>1034</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 13</b>	<b>17 days</b>	<b>Wed 3/23/22</b>	<b>Fri 4/15/22</b>	
1327	<b>1035</b>	<b>NA</b>	<b>0%</b>	<b>AREA 1 - MCALLISTER STREET (A1/A2)</b>	<b>16 days</b>	<b>Wed 3/23/22</b>	<b>Thu 4/14/22</b>	
1328	<b>1036</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDED DECK - POUR #1 (9 DAYC CYCLE):</b>	<b>16 days</b>	<b>Wed 3/23/22</b>	<b>Thu 4/14/22</b>	
1329	1037	NA	0%	PROSHORE SHORING L 13	4 days	Wed 3/23/22	Tue 3/29/22	1303,1307
1330	1038	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Mon 3/28/22	Tue 3/29/22	1329FF
1331	1039	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Mon 3/28/22	Tue 3/29/22	1330FF
1332	1040	NA	0%	REBAR BOTTOM	2 days	Tue 3/29/22	Thu 3/31/22	1331
1333	1041	NA	0%	MEPS ROUGH IN	1 day	Wed 3/30/22	Thu 3/31/22	1332FF
1334	1042	NA	0%	REBAR TOP	2 days	Thu 3/31/22	Mon 4/4/22	1332
1335	1043	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Fri 4/1/22	Mon 4/4/22	1334FF
1336	1044	NA	0%	INSPECTION	1 day	Fri 4/1/22	Mon 4/4/22	1335FF,1333SS
1337	1045	NA	0%	<b>POUR DECK L13 MCALLISTER</b>	0 days	Tue 4/5/22	Tue 4/5/22	1336FS+1 day
1338	1046	NA	0%	CURE	3 edays	Tue 4/5/22	Fri 4/8/22	1337SS
1339	1047	NA	0%	STRESS L 13 MCALLISTER	1 day	Fri 4/8/22	Mon 4/11/22	1338
1340	1048	NA	0%	STRIP DECK	3 days	Mon 4/11/22	Thu 4/14/22	1339
1341	<b>1049</b>	<b>NA</b>	<b>0%</b>	<b>COREWALL</b>	<b>7 days</b>	<b>Mon 3/28/22</b>	<b>Wed 4/6/22</b>	
1342	1050	NA	0%	LEADSIDE WALL FORMWORK	1 day	Mon 3/28/22	Tue 3/29/22	1329FF
1343	1051	NA	0%	INSTALL REINFORCEMENT	4 days	Tue 3/29/22	Mon 4/4/22	1334FF,1342SS
1344	1052	NA	0%	DOUBLE UP FORMWORK	0 days	Tue 4/5/22	Tue 4/5/22	1337,1343SS
1345	1053	NA	0%	INSPECTION	1 day	Mon 4/4/22	Tue 4/5/22	1344FF
1346	1054	NA	0%	POUR COREWALL	1 day	Mon 4/4/22	Tue 4/5/22	1345FF
1347	1055	NA	0%	STRIP & CLEANUP	1 day	Tue 4/5/22	Wed 4/6/22	1346
1348	<b>1056</b>	<b>NA</b>	<b>0%</b>	<b>AREA 2 - HYDE STREET (B1)</b>	<b>13 days</b>	<b>Tue 3/29/22</b>	<b>Fri 4/15/22</b>	
1349	<b>1057</b>	<b>NA</b>	<b>0%</b>	<b>SUSPENDED DECK - POUR #2 (7 DAY CYCLE):</b>	<b>13 days</b>	<b>Tue 3/29/22</b>	<b>Fri 4/15/22</b>	
1350	1058	NA	0%	PROSHORE SHORING	3 days	Tue 3/29/22	Fri 4/1/22	1329,1324

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1351	1059	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Thu 3/31/22	Fri 4/1/22	1350FF
1352	1060	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Thu 3/31/22	Fri 4/1/22	1351FF
1353	1061	NA	0%	REBAR BOTTOM	2 days	Mon 4/4/22	Wed 4/6/22	1352,1334
1354	1062	NA	0%	MEPS ROUGH IN	1 day	Tue 4/5/22	Wed 4/6/22	1353FF
1355	1063	NA	0%	REBAR TOP	1 day	Wed 4/6/22	Thu 4/7/22	1353
1356	1064	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Wed 4/6/22	Thu 4/7/22	1355FF
1357	1065	NA	0%	INSPECTION	1 day	Wed 4/6/22	Thu 4/7/22	1356FF,1354SS
1358	1066	NA	0%	POUR DECK L13 HYDE	0 days	Fri 4/8/22	Fri 4/8/22	1357FS+1 day
1359	1067	NA	0%	CURE	3 edays	Fri 4/8/22	Mon 4/11/22	1358SS
1360	1068	NA	0%	STRESS L13 HYDE	1 day	Mon 4/11/22	Tue 4/12/22	1359
1361	1069	NA	0%	STRIP DECK	3 days	Tue 4/12/22	Fri 4/15/22	1360
1362	1070	NA	0%	COREWALL	7 days	Thu 3/31/22	Mon 4/11/22	
1363	1071	NA	0%	LEADSIDE WALL FORMWORK	1 day	Thu 3/31/22	Fri 4/1/22	1350FF
1364	1072	NA	0%	INSTALL REINFORCEMENT	3 days	Mon 4/4/22	Thu 4/7/22	1355FF,1363SS
1365	1073	NA	0%	DOUBLE UP FORMWORK	0 days	Fri 4/8/22	Fri 4/8/22	1358,1364SS
1366	1074	NA	0%	INSPECTION	1 day	Thu 4/7/22	Fri 4/8/22	1365FF
1367	1075	NA	0%	POUR COREWALL	1 day	Thu 4/7/22	Fri 4/8/22	1366FF
1368	1076	NA	0%	STRIP & CLEANUP	1 day	Fri 4/8/22	Mon 4/11/22	1367
1369	1077	NA	0%	LEVEL 14	17.88 days	Tue 4/5/22	Thu 4/28/22	
1370	1078	NA	0%	AREA 1 - MCALLISTER STREET (A1/A2)	13 days	Tue 4/5/22	Fri 4/22/22	
1371	1079	NA	0%	SUSPENDED DECK - POUR #1 (7 DAY CYCLE):	13 days	Tue 4/5/22	Fri 4/22/22	
1372	1080	NA	0%	PROSHORE SHORING L 14	3 days	Tue 4/5/22	Fri 4/8/22	1350,1346
1373	1081	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Thu 4/7/22	Fri 4/8/22	1372FF
1374	1082	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Thu 4/7/22	Fri 4/8/22	1373FF
1375	1083	NA	0%	REBAR BOTTOM	2 days	Fri 4/8/22	Tue 4/12/22	1374
1376	1084	NA	0%	MEPS ROUGH IN	1 day	Mon 4/11/22	Tue 4/12/22	1375FF
1377	1085	NA	0%	REBAR TOP	1 day	Tue 4/12/22	Wed 4/13/22	1376
1378	1086	NA	0%	INSTALL DOWELS	1 day	Wed 4/13/22	Thu 4/14/22	1377
1379	1087	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Wed 4/13/22	Thu 4/14/22	1378FF
1380	1088	NA	0%	INSPECTION	1 day	Wed 4/13/22	Thu 4/14/22	1379FF
1381	1089	NA	0%	POUR DECK L14 MCALLISTER	0 days	Fri 4/15/22	Fri 4/15/22	1380FS+1 day
1382	1090	NA	0%	CURE	3 edays	Fri 4/15/22	Mon 4/18/22	1381SS
1383	1091	NA	0%	STRESS L 14 MCALLISTER	1 day	Mon 4/18/22	Tue 4/19/22	1382
1384	1092	NA	0%	STRIP DECK	3 days	Tue 4/19/22	Fri 4/22/22	1383
1385	1093	NA	0%	COREWALL	7 days	Thu 4/7/22	Mon 4/18/22	
1386	1094	NA	0%	LEADSIDE WALL FORMWORK	1 day	Thu 4/7/22	Fri 4/8/22	1372FF
1387	1095	NA	0%	INSTALL REINFORCEMENT	3 days	Fri 4/8/22	Wed 4/13/22	1377FF,1386SS
1388	1096	NA	0%	DOUBLE UP FORMWORK	0 days	Fri 4/15/22	Fri 4/15/22	1381,1387SS
1389	1097	NA	0%	INSPECTION	1 day	Thu 4/14/22	Fri 4/15/22	1388FF
1390	1098	NA	0%	POUR COREWALL	1 day	Thu 4/14/22	Fri 4/15/22	1389FF
1391	1099	NA	0%	STRIP & CLEANUP	1 day	Fri 4/15/22	Mon 4/18/22	1390
1392	1100	NA	0%	AREA 2 - HYDE STREET (B1)	14.88 days	Fri 4/8/22	Thu 4/28/22	
1393	1101	NA	0%	SUSPENDED DECK - POUR #2 (7 DAY CYCLE):	14.88 days	Fri 4/8/22	Thu 4/28/22	
1394	1102	NA	0%	PROSHORE SHORING	3 days	Fri 4/8/22	Wed 4/13/22	1367,1372
1395	1103	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Tue 4/12/22	Wed 4/13/22	1394FF
1396	1104	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Tue 4/12/22	Wed 4/13/22	1395FF
1397	1105	NA	0%	REBAR BOTTOM	2 days	Wed 4/13/22	Fri 4/15/22	1396,1377

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1398	1106	NA	0%	MEPS ROUGH IN	1 day	Thu 4/14/22	Fri 4/15/22	1397FF
1399	1107	NA	0%	REBAR TOP	1 day	Fri 4/15/22	Mon 4/18/22	1398
1400	1108	NA	0%	INSTALL DOWELS	1 day	Mon 4/18/22	Tue 4/19/22	1399
1401	1109	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Mon 4/18/22	Tue 4/19/22	1400FF
1402	1110	NA	0%	INSPECTION	1 day	Mon 4/18/22	Tue 4/19/22	1401FF
1403	1111	NA	0%	POUR DECK L14 HYDE	0 days	Wed 4/20/22	Wed 4/20/22	1402FS+1 day
1404	1112	NA	0%	CURE	3 edays	Wed 4/20/22	Sat 4/23/22	1403SS
1405	1113	NA	0%	STRESS L14 HYDE	1 day	Mon 4/25/22	Mon 4/25/22	1404
1406	1114	NA	0%	STRIP DECK	3 days	Tue 4/26/22	Thu 4/28/22	1405
1407	1115	NA	0%	COREWALL	7 days	Tue 4/12/22	Thu 4/21/22	
1408	1116	NA	0%	LEADSIDE WALL FORMWORK	1 day	Tue 4/12/22	Wed 4/13/22	1394FF
1409	1117	NA	0%	INSTALL REINFORCEMENT	3 days	Wed 4/13/22	Mon 4/18/22	1399FF,1408SS
1410	1118	NA	0%	DOUBLE UP FORMWORK	0 days	Wed 4/20/22	Wed 4/20/22	1403,1409SS
1411	1119	NA	0%	INSPECTION	1 day	Tue 4/19/22	Wed 4/20/22	1410FF
1412	1120	NA	0%	POUR COREWALL	1 day	Tue 4/19/22	Wed 4/20/22	1411FF
1413	1121	NA	0%	STRIP & CLEANUP	1 day	Wed 4/20/22	Thu 4/21/22	1412
1414	1122	NA	0%	LEVEL 15 ROOF	20 days	Fri 4/15/22	Fri 5/13/22	
1415	1123	NA	0%	AREA 1 - MCALLISTER STREET (A1/A2)	17 days	Fri 4/15/22	Tue 5/10/22	
1416	1124	NA	0%	SUSPENDED DECK - POUR #1 (8 DAY CYCLE):	14.88 days	Fri 4/15/22	Thu 5/5/22	
1417	1125	NA	0%	PROSHORE SHORING L15/ROOF	3 days	Fri 4/15/22	Wed 4/20/22	1390,1394
1418	1126	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Tue 4/19/22	Wed 4/20/22	1417FF
1419	1127	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Tue 4/19/22	Wed 4/20/22	1418FF
1420	1128	NA	0%	REBAR BOTTOM	2 days	Wed 4/20/22	Fri 4/22/22	1419
1421	1129	NA	0%	MEPS ROUGH IN	1 day	Thu 4/21/22	Fri 4/22/22	1420FF
1422	1130	NA	0%	REBAR TOP	1 day	Fri 4/22/22	Mon 4/25/22	1421
1423	1131	NA	0%	INSTALL DOWELS	1 day	Mon 4/25/22	Tue 4/26/22	1422
1424	1132	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Tue 4/26/22	Wed 4/27/22	1423
1425	1133	NA	0%	INSPECTION	1 day	Tue 4/26/22	Wed 4/27/22	1424FF
1426	243	NA	0%	POUR DECK L15 MCALLISTER	0 days	Thu 4/28/22	Thu 4/28/22	1425FS+1 day
1427	1134	NA	0%	CURE	3 edays	Thu 4/28/22	Sun 5/1/22	1426SS
1428	1135	NA	0%	STRESS L 15 MCALLISTER	1 day	Mon 5/2/22	Mon 5/2/22	1427
1429	247	NA	0%	STRIP DECK L15 (ROOF MCALLISTER ST)	3 days	Tue 5/3/22	Thu 5/5/22	1428
1430	6470	NA	0%	CURBS & PADS:	8 days	Thu 4/28/22	Tue 5/10/22	
1431	6471	NA	0%	LEADSIDE FORMWORK	2 days	Thu 4/28/22	Mon 5/2/22	1426
1432	6472	NA	0%	INSTALL REINFORCEMENT	2 days	Mon 5/2/22	Wed 5/4/22	1431
1433	6473	NA	0%	DOUBLE UP FORMWORK	2 days	Wed 5/4/22	Fri 5/6/22	1432
1434	6474	NA	0%	INSPECTION	1 day	Thu 5/5/22	Fri 5/6/22	1433FF
1435	6475	NA	0%	POUR PADS & CURBS AREA 1 - MCALLISTER STREET (A1/A2)	1 day	Fri 5/6/22	Mon 5/9/22	1434
1436	6476	NA	0%	STRIP & CLEANUP AREA 1 - MCALLISTER STREET (A1/A2)	1 day	Mon 5/9/22	Tue 5/10/22	1435
1437	1142	NA	0%	AREA 2 - HYDE STREET (B1)	17 days	Wed 4/20/22	Fri 5/13/22	
1438	1143	NA	0%	SUSPENDED DECK - POUR #2 (8 DAY CYCLE):	16 days	Wed 4/20/22	Thu 5/12/22	
1439	1144	NA	0%	PROSHORE SHORING	3 days	Wed 4/20/22	Mon 4/25/22	1412,1417
1440	1145	NA	0%	HANDRAILS, BLOCKOUTS & EDGEFORMS	1 day	Fri 4/22/22	Mon 4/25/22	1439FF
1441	1146	NA	0%	MEPS LAYOUT, INSERT & CAN	1 day	Fri 4/22/22	Mon 4/25/22	1440FF
1442	1147	NA	0%	REBAR BOTTOM	2 days	Mon 4/25/22	Wed 4/27/22	1441
1443	1148	NA	0%	MEPS ROUGH IN	1 day	Tue 4/26/22	Wed 4/27/22	1442FF
1444	1149	NA	0%	REBAR TOP	1 day	Wed 4/27/22	Thu 4/28/22	1443

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1445	1150	NA	0%	INSTALL DOWELS	1 day	Thu 4/28/22	Fri 4/29/22	1444
1446	1151	NA	0%	EMBEDS, TEMPLATES & DEPRESSIONS	1 day	Fri 4/29/22	Mon 5/2/22	1445
1447	1152	NA	0%	INSPECTION	1 day	Fri 4/29/22	Mon 5/2/22	1446FF
1448	242	NA	0%	POUR DECK L15 HYDE	0 days	Tue 5/3/22	Tue 5/3/22	1447FS+1 day
1449	1153	NA	0%	CURE	3 edays	Tue 5/3/22	Fri 5/6/22	1448SS
1450	1154	NA	0%	STRESS	1 day	Fri 5/6/22	Mon 5/9/22	1449
1451	245	NA	0%	STRIP DECK L15 HYDE	3 days	Mon 5/9/22	Thu 5/12/22	1450
1452	6478	NA	0%	<b>CURBS &amp; PADS:</b>	<b>8 days</b>	<b>Tue 5/3/22</b>	<b>Fri 5/13/22</b>	
1453	6479	NA	0%	LEADSIDE FORMWORK	2 days	Tue 5/3/22	Thu 5/5/22	1448
1454	6480	NA	0%	INSTALL REINFORCEMENT	2 days	Thu 5/5/22	Mon 5/9/22	1453
1455	6481	NA	0%	DOUBLE UP FORMWORK	2 days	Mon 5/9/22	Wed 5/11/22	1454
1456	6482	NA	0%	INSPECTION	1 day	Tue 5/10/22	Wed 5/11/22	1455FF
1457	6483	NA	0%	POUR COREWALL/CURBS & PADS AREA 2 - HYDE STREET (B1)	1 day	Wed 5/11/22	Thu 5/12/22	1456
1458	6484	NA	0%	STRIP & CLEANUP AREA 2 - HYDE STREET (B1)	1 day	Thu 5/12/22	Fri 5/13/22	1457
1459	9227	NA	0%	<b>SUBCONTRACTORS MATERIAL DELIVERY LOG (LOWER LEVEL DELIVERY CARTS W/ WHEELS REQUIRED BY SUBCONTRACTOR MATERIALS REMAIN ON CARTS)</b>	<b>235 days</b>	<b>Mon 6/28/21</b>	<b>Tue 6/7/22</b>	
1460	9229	NA	0%	<b>Electrical Equipment</b>	<b>20 days</b>	<b>Mon 8/16/21</b>	<b>Sat 9/11/21</b>	
1461	10169	NA	0%	Electrical Switch Gear (Crane Hoisted to Lower levels Tarp Protection as Required)	1 day	Mon 8/16/21	Mon 8/16/21	554
1462	9230	NA	0%	Electrical (30-40ps Cabinets/Switch Gear L 1 ( Crane Hoist Tarp Protection as Required)	1 eday	Fri 9/10/21	Sat 9/11/21	694
1463	9231	NA	0%	<b>Fire Pumps</b>	<b>1 day</b>	<b>Mon 8/16/21</b>	<b>Mon 8/16/21</b>	
1464	9232	NA	0%	Fire Pump/CONTROLLER (6AM) Tarp Protection Required	1 day	Mon 8/16/21	Mon 8/16/21	554
1465	9234	NA	0%	<b>Domestic Water Room</b>	<b>1 day</b>	<b>Mon 8/16/21</b>	<b>Mon 8/16/21</b>	
1466	9235	NA	0%	Heavy Equipment/Cistern Tarp Protection Required	1 day	Mon 8/16/21	Mon 8/16/21	554
1467	9277	NA	0%	<b>Storm/Waste/Vent</b>	<b>235 days</b>	<b>Mon 6/28/21</b>	<b>Tue 6/7/22</b>	
1468	9279	NA	0%	<b>LOWER LEVEL Storm/Waste/Vent</b>	<b>36 days</b>	<b>Mon 6/28/21</b>	<b>Mon 8/16/21</b>	
1469	9634	NA	0%	MAT 1	1 day	Mon 6/28/21	Mon 6/28/21	489
1470	9637	NA	0%	MAT 2	1 day	Mon 7/26/21	Mon 7/26/21	505
1471	9636	NA	0%	MAT 3	1 day	Mon 8/2/21	Mon 8/2/21	539
1472	9635	NA	0%	MAT 4	1 day	Mon 8/16/21	Mon 8/16/21	554
1473	9281	NA	0%	<b>L2 Storm/Waste/Vent</b>	<b>0 days</b>	<b>Thu 3/3/22</b>	<b>Thu 3/3/22</b>	
1474	9641	NA	0%	SOUTH	0 days	Thu 3/3/22	Thu 3/3/22	2090SS
1475	9640	NA	0%	NORTH	0 days	Thu 3/3/22	Thu 3/3/22	2090SS
1476	9282	NA	0%	<b>L3 Storm/Waste/Vent</b>	<b>5 days</b>	<b>Fri 12/24/21</b>	<b>Fri 12/31/21</b>	
1477	9643	NA	0%	SOUTH	0 days	Fri 12/24/21	Fri 12/24/21	2142SS
1478	9642	NA	0%	NORTH	0 days	Fri 12/31/21	Fri 12/31/21	2147SS
1479	9283	NA	0%	<b>L4 Storm/Waste/Vent</b>	<b>5 days</b>	<b>Fri 1/7/22</b>	<b>Fri 1/14/22</b>	
1480	9645	NA	0%	SOUTH	0 days	Fri 1/7/22	Fri 1/7/22	2225SS
1481	9644	NA	0%	NORTH	0 days	Fri 1/14/22	Fri 1/14/22	2230SS
1482	9284	NA	0%	<b>L5 Storm/Waste/Vent</b>	<b>5 days</b>	<b>Tue 1/25/22</b>	<b>Tue 2/1/22</b>	
1483	9647	NA	0%	SOUTH	0 days	Tue 1/25/22	Tue 1/25/22	2308SS
1484	9646	NA	0%	NORTH	0 days	Tue 2/1/22	Tue 2/1/22	2313SS
1485	9285	NA	0%	<b>L6 Storm/Waste/Vent</b>	<b>5 days</b>	<b>Tue 2/8/22</b>	<b>Tue 2/15/22</b>	
1486	9649	NA	0%	SOUTH	0 days	Tue 2/8/22	Tue 2/8/22	2391SS
1487	9648	NA	0%	NORTH	0 days	Tue 2/15/22	Tue 2/15/22	2396SS
1488	9286	NA	0%	<b>L7 Storm/Waste/Vent</b>	<b>5 days</b>	<b>Tue 2/22/22</b>	<b>Tue 3/1/22</b>	
1489	9651	NA	0%	SOUTH	0 days	Tue 2/22/22	Tue 2/22/22	2474SS
1490	9650	NA	0%	NORTH	0 days	Tue 3/1/22	Tue 3/1/22	2479SS

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1491	<b>9287</b>	<b>NA</b>	<b>0%</b>	<b>L8 Storm/Waste/Vent</b>	<b>5 days</b>	<b>Tue 3/8/22</b>	<b>Tue 3/15/22</b>	
1492	9653	NA	0%	SOUTH	0 days	Tue 3/8/22	Tue 3/8/22	2557SS
1493	9652	NA	0%	NORTH	0 days	Tue 3/15/22	Tue 3/15/22	2562SS
1494	<b>9288</b>	<b>NA</b>	<b>0%</b>	<b>L9 Storm/Waste/Vent</b>	<b>5 days</b>	<b>Tue 3/22/22</b>	<b>Tue 3/29/22</b>	
1495	9655	NA	0%	SOUTH	0 days	Tue 3/22/22	Tue 3/22/22	2640SS
1496	9654	NA	0%	NORTH	0 days	Tue 3/29/22	Tue 3/29/22	2645SS
1497	<b>9289</b>	<b>NA</b>	<b>0%</b>	<b>L10 Storm/Waste/Vent</b>	<b>5 days</b>	<b>Tue 4/5/22</b>	<b>Tue 4/12/22</b>	
1498	9657	NA	0%	SOUTH	0 days	Tue 4/5/22	Tue 4/5/22	2723SS
1499	9656	NA	0%	NORTH	0 days	Tue 4/12/22	Tue 4/12/22	2728SS
1500	<b>9290</b>	<b>NA</b>	<b>0%</b>	<b>L11 Storm/Waste/Vent</b>	<b>5 days</b>	<b>Tue 4/19/22</b>	<b>Tue 4/26/22</b>	
1501	9659	NA	0%	SOUTH	0 days	Tue 4/19/22	Tue 4/19/22	2806SS
1502	9658	NA	0%	NORTH	0 days	Tue 4/26/22	Tue 4/26/22	2811SS
1503	<b>9291</b>	<b>NA</b>	<b>0%</b>	<b>L12 Storm/Waste/Vent</b>	<b>5 days</b>	<b>Tue 5/3/22</b>	<b>Tue 5/10/22</b>	
1504	9661	NA	0%	SOUTH	0 days	Tue 5/3/22	Tue 5/3/22	2889SS
1505	9660	NA	0%	NORTH	0 days	Tue 5/10/22	Tue 5/10/22	2894SS
1506	<b>9292</b>	<b>NA</b>	<b>0%</b>	<b>L13 Storm/Waste/Vent</b>	<b>5 days</b>	<b>Tue 5/17/22</b>	<b>Tue 5/24/22</b>	
1507	9663	NA	0%	SOUTH	0 days	Tue 5/17/22	Tue 5/17/22	2972SS
1508	9662	NA	0%	NORTH	0 days	Tue 5/24/22	Tue 5/24/22	2977SS
1509	<b>9293</b>	<b>NA</b>	<b>0%</b>	<b>L14 Storm/Waste/Vent</b>	<b>5 days</b>	<b>Tue 5/31/22</b>	<b>Tue 6/7/22</b>	
1510	9665	NA	0%	SOUTH	0 days	Tue 5/31/22	Tue 5/31/22	3055SS
1511	9664	NA	0%	NORTH	0 days	Tue 6/7/22	Tue 6/7/22	3060SS
1512	<b>9319</b>	<b>NA</b>	<b>0%</b>	<b>Waters/Gas/Condensers/H.P.Risers</b>	<b>35.88 days</b>	<b>Mon 6/28/21</b>	<b>Mon 8/16/21</b>	
1513	<b>9321</b>	<b>NA</b>	<b>0%</b>	<b>LOWER LEVEL Waters/Gas/Condensers/H.P.Risers</b>	<b>35.88 days</b>	<b>Mon 6/28/21</b>	<b>Mon 8/16/21</b>	
1514	9757	NA	0%	MAT 1	1 day	Mon 6/28/21	Mon 6/28/21	489
1515	9758	NA	0%	MAT 2	1 day	Mon 7/26/21	Mon 7/26/21	505
1516	9759	NA	0%	MAT 3	1 day	Mon 8/2/21	Mon 8/2/21	539
1517	9760	NA	0%	MAT 4	1 day	Mon 8/16/21	Mon 8/16/21	554
1518	<b>9361</b>	<b>NA</b>	<b>0%</b>	<b>Fire Sprinkler MAINS/DISTRIBUTION</b>	<b>36 days</b>	<b>Mon 6/28/21</b>	<b>Mon 8/16/21</b>	
1519	<b>9628</b>	<b>NA</b>	<b>0%</b>	<b>LOWER LEVEL (ON CARTS)</b>	<b>36 days</b>	<b>Mon 6/28/21</b>	<b>Mon 8/16/21</b>	
1520	9912	NA	0%	MAT 1	1 day	Mon 6/28/21	Mon 6/28/21	489
1521	9913	NA	0%	MAT 2	1 day	Mon 7/26/21	Mon 7/26/21	505
1522	9914	NA	0%	MAT 3	1 day	Mon 8/2/21	Mon 8/2/21	539
1523	9915	NA	0%	MAT 4	1 day	Mon 8/16/21	Mon 8/16/21	554
1524	<b>9441</b>	<b>NA</b>	<b>0%</b>	<b>HVAC LARGE EQUIPMENT</b>	<b>36 days</b>	<b>Mon 6/28/21</b>	<b>Mon 8/16/21</b>	
1525	<b>9921</b>	<b>NA</b>	<b>0%</b>	<b>LOWER LEVEL (ON CARTS)</b>	<b>36 days</b>	<b>Mon 6/28/21</b>	<b>Mon 8/16/21</b>	
1526	9922	NA	0%	MAT 1	1 day	Mon 6/28/21	Mon 6/28/21	489
1527	9923	NA	0%	MAT 2	1 day	Mon 7/26/21	Mon 7/26/21	505
1528	9924	NA	0%	MAT 3	1 day	Mon 8/2/21	Mon 8/2/21	539
1529	9925	NA	0%	MAT 4	1 day	Mon 8/16/21	Mon 8/16/21	554
1530	<b>9625</b>	<b>NA</b>	<b>0%</b>	<b>Elevator Rails/Cab's</b>	<b>10 days</b>	<b>Thu 3/3/22</b>	<b>Thu 3/17/22</b>	
1531	9626	NA	0%	KONE Deliver Material onsite	10 days	Thu 3/3/22	Thu 3/17/22	3673FF
1532	<b>8665</b>	<b>NA</b>	<b>0%</b>	<b>STAIRS</b>	<b>238.13 days</b>	<b>Mon 7/26/21</b>	<b>Thu 6/23/22</b>	
1533	<b>8666</b>	<b>NA</b>	<b>0%</b>	<b>STAIR DELIVERY LOG (STAIR PACKAGES ON CARTS WITH WHEELS PROVIDED BY S</b>	<b>181.13 days</b>	<b>Mon 7/26/21</b>	<b>Mon 4/18/22</b>	
1534	<b>8727</b>	<b>NA</b>	<b>0%</b>	<b>MCALLISTER ST (STAIR #1 &amp; Stair # 2)</b>	<b>166.13 days</b>	<b>Mon 8/16/21</b>	<b>Mon 4/18/22</b>	
1535	8668	NA	0%	LOWER LEVEL TO 1	1 day	Mon 8/16/21	Mon 8/16/21	554
1536	8669	NA	0%	1 to 2	1 day	Mon 9/13/21	Mon 9/13/21	694
1537	8670	NA	0%	2 to 3	1 day	Tue 10/19/21	Tue 10/19/21	802

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1538	8671	NA	0%	3 to 4	1 day	Mon 11/29/21	Mon 11/29/21	876
1539	8672	NA	0%	4 to 5	1 day	Fri 12/10/21	Fri 12/10/21	946
1540	8673	NA	0%	5 to 6	1 day	Thu 12/23/21	Mon 12/27/21	989
1541	8674	NA	0%	6 to 7	1 day	Thu 1/6/22	Thu 1/6/22	1032
1542	8675	NA	0%	7 to 8	1 day	Thu 1/20/22	Thu 1/20/22	1075
1543	8676	NA	0%	8 to 9	1 day	Mon 1/31/22	Tue 2/1/22	1118
1544	8677	NA	0%	9 to 10	1 day	Mon 2/7/22	Tue 2/8/22	1154
1545	8678	NA	0%	10 to 11	1 day	Fri 2/25/22	Mon 2/28/22	1206
1546	8679	NA	0%	11 to 12	1 day	Thu 3/10/22	Fri 3/11/22	1250
1547	8680	NA	0%	12 to 13	1 day	Wed 3/23/22	Thu 3/24/22	1294
1548	8681	NA	0%	13 to 14	1 day	Tue 4/5/22	Wed 4/6/22	1337
1549	8682	NA	0%	14 to 15	1 day	Fri 4/15/22	Mon 4/18/22	1381
1550	<b>8730</b>	<b>NA</b>	<b>0%</b>	<b>HYDE ST (STAIR # 3)</b>	<b>181.13 days</b>	<b>Mon 7/26/21</b>	<b>Mon 4/18/22</b>	
1551	8731	NA	0%	LOWER LEVEL TO 1	1 day	Mon 7/26/21	Mon 7/26/21	505
1552	8732	NA	0%	1 to 2	1 day	Wed 9/22/21	Wed 9/22/21	729
1553	8733	NA	0%	2 to 3	1 day	Mon 11/1/21	Mon 11/1/21	851
1554	8734	NA	0%	3 to 4	1 day	Fri 11/12/21	Fri 11/12/21	925
1555	8735	NA	0%	4 to 5	1 day	Thu 12/16/21	Thu 12/16/21	967
1556	8736	NA	0%	5 to 6	1 day	Wed 12/29/21	Thu 12/30/21	1010
1557	8737	NA	0%	6 to 7	1 day	Mon 1/10/22	Mon 1/10/22	1053
1558	8738	NA	0%	7 to 8	1 day	Mon 1/24/22	Tue 1/25/22	1096
1559	8739	NA	0%	8 to 9	1 day	Thu 2/3/22	Fri 2/4/22	1139
1560	8740	NA	0%	9 to 10	1 day	Thu 2/17/22	Fri 2/18/22	1183
1561	8741	NA	0%	10 to 11	1 day	Wed 3/2/22	Thu 3/3/22	1227
1562	8742	NA	0%	11 to 12	1 day	Tue 3/15/22	Wed 3/16/22	1271
1563	8743	NA	0%	12 to 13	1 day	Mon 3/28/22	Tue 3/29/22	1315
1564	8744	NA	0%	13 to 14	1 day	Fri 4/8/22	Mon 4/11/22	1358
1565	8745	NA	0%	14 to 15	1 day	Fri 4/15/22	Mon 4/18/22	1381
1566	<b>8636</b>	<b>NA</b>	<b>0%</b>	<b>STAIR INSTALLATION</b>	<b>103.13 days</b>	<b>Mon 12/13/21</b>	<b>Wed 5/11/22</b>	
1567	<b>8746</b>	<b>NA</b>	<b>0%</b>	<b>MCALLISTER ST (STAIR #1 &amp; Stair # 2)</b>	<b>100.13 days</b>	<b>Mon 12/13/21</b>	<b>Fri 5/6/22</b>	
1568	8723	NA	0%	Install Stair - LOWER TO 1	2 days	Mon 12/13/21	Tue 12/14/21	946FS+1 day
1569	8637	NA	0%	Install Stair - 1 to 2	1 day	Wed 12/15/21	Wed 12/15/21	1568
1570	8639	NA	0%	Install Stair - 2 to 3	1 day	Mon 12/27/21	Tue 12/28/21	1569,989FS+1 day
1571	8641	NA	0%	Install Stair - 3 to 4	1 day	Fri 1/7/22	Fri 1/7/22	1570,1032FS+1 day
1572	8643	NA	0%	Install Stair - 4 to 5	1 day	Fri 1/21/22	Fri 1/21/22	1571,1075FS+1 day
1573	8645	NA	0%	Install Stair - 5 to 6	1 day	Tue 2/1/22	Wed 2/2/22	1572,1118FS+1 day
1574	8647	NA	0%	Install Stair - 6 to 7	1 day	Wed 2/16/22	Thu 2/17/22	1573,1162FS+1 day
1575	8649	NA	0%	Install Stair - 7 to 8	1 day	Mon 2/28/22	Tue 3/1/22	1574,1206FS+1 day
1576	8651	NA	0%	Install Stair - 8 to 9	1 day	Fri 3/11/22	Mon 3/14/22	1575,1250FS+1 day
1577	8653	NA	0%	Install Stair - 9 to 10	1 day	Thu 3/24/22	Fri 3/25/22	1576,1294FS+1 day
1578	8655	NA	0%	Install Stair - 10 to 11	1 day	Wed 4/6/22	Thu 4/7/22	1577,1337FS+1 day
1579	8657	NA	0%	Install Stair - 11 to 12	1 day	Mon 4/18/22	Tue 4/19/22	1578,1381FS+1 day
1580	8659	NA	0%	Install Stair - 12 to 13	1 day	Fri 4/29/22	Mon 5/2/22	1579,1426FS+1 day
1581	8661	NA	0%	Install Stair - 13 to 14	1 day	Tue 5/3/22	Wed 5/4/22	1580FS+1 day
1582	8663	NA	0%	Install Stair - 14 to 15	1 day	Thu 5/5/22	Fri 5/6/22	1581FS+1 day
1583	<b>8749</b>	<b>NA</b>	<b>0%</b>	<b>HYDE ST (STAIR # 3)</b>	<b>99.13 days</b>	<b>Fri 12/17/21</b>	<b>Wed 5/11/22</b>	
1584	8750	NA	0%	Install Stair - LOWER TO 1	2 days	Fri 12/17/21	Mon 12/20/21	967FS+1 day

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1585	8752	NA	0%	Install Stair - 1 to 2	1 day	Wed 12/22/21	Wed 12/22/21	1584FS+1 day
1586	8754	NA	0%	Install Stair - 2 to 3	1 day	Thu 12/30/21	Mon 1/3/22	1585,1010FS+1 day
1587	8756	NA	0%	Install Stair - 3 to 4	1 day	Tue 1/11/22	Tue 1/11/22	1586,1053FS+1 day
1588	8758	NA	0%	Install Stair - 4 to 5	1 day	Tue 1/25/22	Wed 1/26/22	1587,1096FS+1 day
1589	8760	NA	0%	Install Stair - 5 to 6	1 day	Fri 2/4/22	Mon 2/7/22	1588,1139FS+1 day
1590	8762	NA	0%	Install Stair - 6 to 7	1 day	Fri 2/18/22	Mon 2/21/22	1589,1183FS+1 day
1591	8764	NA	0%	Install Stair - 7 to 8	1 day	Thu 3/3/22	Fri 3/4/22	1590,1227FS+1 day
1592	8766	NA	0%	Install Stair - 8 to 9	1 day	Wed 3/16/22	Thu 3/17/22	1591,1271FS+1 day
1593	8768	NA	0%	Install Stair - 9 to 10	1 day	Tue 3/29/22	Wed 3/30/22	1592,1315FS+1 day
1594	8770	NA	0%	Install Stair - 10 to 11	1 day	Mon 4/11/22	Tue 4/12/22	1593,1358FS+1 day
1595	8772	NA	0%	Install Stair - 11 to 12	1 day	Thu 4/21/22	Fri 4/22/22	1594,1403FS+1 day
1596	8774	NA	0%	Install Stair - 12 to 13	1 day	Wed 5/4/22	Thu 5/5/22	1595,1448FS+1 day
1597	8776	NA	0%	Install Stair - 13 to 14	1 day	Fri 5/6/22	Mon 5/9/22	1596FS+1 day
1598	8778	NA	0%	Install Stair - 14 to 15	1 day	Tue 5/10/22	Wed 5/11/22	1597FS+1 day
1599	<b>8685</b>	<b>NA</b>	<b>0%</b>	<b>STAIRS WALLS/DOOR FRAMES/DOORS &amp; HARDWARE</b>	<b>108.25 days</b>	<b>Fri 1/21/22</b>	<b>Thu 6/23/22</b>	
1600	<b>8780</b>	<b>NA</b>	<b>0%</b>	<b>MCALLISTER ST &amp; HYDE ST (STAIR #1,#2,#3)</b>	<b>108.25 days</b>	<b>Fri 1/21/22</b>	<b>Thu 6/23/22</b>	
1601	<b>8686</b>	<b>NA</b>	<b>0%</b>	<b>Levels LOWER TO 5</b>	<b>34 days</b>	<b>Fri 1/21/22</b>	<b>Thu 3/10/22</b>	
1602	8687	NA	0%	Install Walls	6 days	Fri 1/21/22	Mon 1/31/22	1572
1603	8688	NA	0%	Install Door Frames	3 days	Thu 1/27/22	Tue 2/1/22	1602FS-2 days
1604	8690	NA	0%	MEPS Rough-in	6 days	Mon 1/31/22	Tue 2/8/22	1602
1605	8691	NA	0%	Inspection	1 day	Tue 2/8/22	Wed 2/9/22	1604
1606	8692	NA	0%	Insulate Walls	3 days	Wed 2/9/22	Mon 2/14/22	1605
1607	8693	NA	0%	Drywall LOWER - L5 MCALLISTER ST & HYDE ST STAIR SHAFTS	5 days	Mon 2/14/22	Mon 2/21/22	1606
1608	8694	NA	0%	Tape	5 days	Mon 2/21/22	Mon 2/28/22	1607
1609	8695	NA	0%	Install Doors& Hardware	3 days	Mon 2/28/22	Thu 3/3/22	1608
1610	8696	NA	0%	MEPS Trim	5 days	Thu 3/3/22	Thu 3/10/22	1609
1611	<b>8697</b>	<b>NA</b>	<b>0%</b>	<b>Levels 6 - 11</b>	<b>34 days</b>	<b>Thu 4/7/22</b>	<b>Wed 5/25/22</b>	
1612	8698	NA	0%	Install Walls	6 days	Thu 4/7/22	Fri 4/15/22	1602,1578
1613	8699	NA	0%	Install Door Frames	3 days	Wed 4/13/22	Mon 4/18/22	1612FS-2 days
1614	8700	NA	0%	MEPS Rough-in	6 days	Fri 4/15/22	Mon 4/25/22	1612
1615	8701	NA	0%	Inspection	1 day	Mon 4/25/22	Tue 4/26/22	1614
1616	8702	NA	0%	Insulate Walls	3 days	Tue 4/26/22	Fri 4/29/22	1615
1617	8703	NA	0%	Drywall	5 days	Fri 4/29/22	Fri 5/6/22	1616
1618	8704	NA	0%	Tape	5 days	Fri 5/6/22	Fri 5/13/22	1617
1619	8705	NA	0%	Install Doors& Hardware	3 days	Fri 5/13/22	Wed 5/18/22	1618
1620	8706	NA	0%	MEPS Trim	5 days	Wed 5/18/22	Wed 5/25/22	1619
1621	<b>8707</b>	<b>NA</b>	<b>0%</b>	<b>Levels 12 - 15</b>	<b>34 days</b>	<b>Fri 5/6/22</b>	<b>Thu 6/23/22</b>	
1622	8708	NA	0%	Install Walls	6 days	Fri 5/6/22	Mon 5/16/22	1582
1623	8709	NA	0%	Install Door Frames	3 days	Thu 5/12/22	Tue 5/17/22	1622FS-2 days
1624	8710	NA	0%	MEPS Rough-in	6 days	Mon 5/16/22	Tue 5/24/22	1622
1625	8711	NA	0%	Inspection	1 day	Tue 5/24/22	Wed 5/25/22	1624
1626	8712	NA	0%	Insulate Walls	3 days	Wed 5/25/22	Mon 5/30/22	1625
1627	8713	NA	0%	Drywall	5 days	Mon 5/30/22	Mon 6/6/22	1626
1628	8714	NA	0%	Tape	5 days	Mon 6/6/22	Mon 6/13/22	1627
1629	8715	NA	0%	Install Doors& Hardware	3 days	Mon 6/13/22	Thu 6/16/22	1628
1630	8716	NA	0%	MEPS Trim	5 days	Thu 6/16/22	Thu 6/23/22	1629
1631	<b>8717</b>	<b>NA</b>	<b>0%</b>	<b>STAIRS WALL MOUNTED HAND RAILS</b>	<b>80.25 days</b>	<b>Mon 2/28/22</b>	<b>Tue 6/21/22</b>	

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1632	<b>8815</b>	<b>NA</b>	<b>0%</b>	<b>MCALLISTER ST &amp; HYDE ST (STAIR #1,#2,#3)</b>	<b>80.25 days</b>	<b>Mon 2/28/22</b>	<b>Tue 6/21/22</b>	
1633	8725	NA	0%	Install Hand Rails LOWER - 1	1 day	Mon 2/28/22	Tue 3/1/22	1608
1634	8718	NA	0%	Install Hand Rails 1 - 5	6 days	Tue 3/1/22	Wed 3/9/22	1633
1635	8719	NA	0%	Install Hand Rails 6 - 11	6 days	Fri 5/13/22	Mon 5/23/22	1618
1636	8720	NA	0%	Install Hand Rails 12 - 15	6 days	Mon 6/13/22	Tue 6/21/22	1628
1637	<b>1161</b>	<b>NA</b>	<b>0%</b>	<b>STRUCTURAL STEEL &amp; STAIRS</b>	<b>214 days</b>	<b>Wed 9/15/21</b>	<b>Tue 7/26/22</b>	
1638	1162	NA	0%	STRUCTURE COMPLETE	0 days	Thu 5/26/22	Thu 5/26/22	1660,471
1639	<b>1164</b>	<b>NA</b>	<b>0%</b>	<b>STRUCTURAL STEEL</b>	<b>44 days</b>	<b>Wed 9/15/21</b>	<b>Tue 11/16/21</b>	
1640	1165	NA	0%	MOBILIZE STRUCTURAL STEEL	0 days	Wed 9/15/21	Wed 9/15/21	710
1641	594	NA	0%	PODIUM STEEL COMPLETE	0 days	Tue 11/9/21	Tue 11/9/21	1655
1642	1167	NA	0%	SET LEVEL 2, A1 TG2	1 day	Wed 9/22/21	Wed 9/22/21	1645
1643	1169	NA	0%	SET GG LEVEL TG2'S	2 days	Tue 9/28/21	Wed 9/29/21	757,1642
1644	561	NA	0%	SET, BOLT, WELD GG LEVEL TRUSS FRAMES	5 days	Thu 9/30/21	Wed 10/6/21	1643
1645	1168	NA	0%	MOVE IN 1, ASSEMBLE CRANE	3 days	Fri 9/17/21	Tue 9/21/21	1648
1646	529	NA	0%	WELD GIRDER BEAM	2 days	Thu 9/23/21	Fri 9/24/21	1642
1647	1171	NA	0%	DISMANTLE, MOVE OUT CRANE	3 days	Fri 10/1/21	Tue 10/5/21	1644SF+32 hrs
1648	1170	NA	0%	IMPLEMENT TRAFFIC CONTROL PLAN	1 day	Thu 9/16/21	Thu 9/16/21	1640
1649	1172	NA	0%	RE-ESTABLISH TYPICAL TRAFFIC CONTROL PLAN	1 day	Wed 10/6/21	Wed 10/6/21	1647
1650	1173	NA	0%	MOVE IN 2, ASSEMBLE CRANE	3 days	Tue 10/19/21	Thu 10/21/21	1652,802
1651	1175	NA	0%	DISMANTLE, MOVE OUT CRANE	3 days	Wed 11/10/21	Mon 11/15/21	1641,1655SF+32 hrs
1652	1174	NA	0%	IMPLEMENT TRAFFIC CONTROL PLAN	1 day	Thu 10/7/21	Thu 10/7/21	1649
1653	601	NA	0%	RE-ESTABLISH TYPICAL TRAFFIC CONTROL PLAN	1 day	Tue 11/16/21	Tue 11/16/21	1651
1654	591	NA	0%	SET LEVEL 3, A1 TG2'S	5 days	Wed 10/27/21	Tue 11/2/21	835,839,1650
1655	1166	NA	0%	SET, BOLT, WELD A1 W36X150 BEAMS, A2 W24X55	5 days	Wed 11/3/21	Tue 11/9/21	1654,1656
1656	1176	NA	0%	SET LEVEL 3 TG3'S	1 day	Wed 10/27/21	Wed 10/27/21	835,839
1657	<b>1177</b>	<b>NA</b>	<b>0%</b>	<b>MISC IRON</b>	<b>145.88 days</b>	<b>Tue 12/21/21</b>	<b>Tue 7/12/22</b>	
1658	1178	NA	0%	STAIR 3 STEEL FRAME - L3 TO ROOF	140 days	Tue 12/21/21	Tue 7/12/22	1429FF,970SS
1659	1179	NA	0%	INSTALL SUPPORT COLUMNS - L3 TO L13	110 days	Mon 12/27/21	Thu 6/2/22	970,1340FF
1660	1163	NA	0%	LEVEL 15 ROOF STEEL	10 days	Thu 5/12/22	Thu 5/26/22	1451
1661	<b>1180</b>	<b>NA</b>	<b>0%</b>	<b>PODIUM STAIRS</b>	<b>17.88 days</b>	<b>Mon 11/8/21</b>	<b>Thu 12/2/21</b>	
1662	1181	NA	0%	MOBILIZE STAIRS	0 days	Mon 11/8/21	Mon 11/8/21	805,854
1663	1182	NA	0%	INSTALL AUDITORIUM STAIR	5 days	Wed 11/17/21	Tue 11/23/21	1665
1664	1184	NA	0%	INSTALL GRAND STAIR	5 days	Wed 11/24/21	Thu 12/2/21	1663
1665	1183	NA	0%	INSTALL CIRCULATION STAIR	5 days	Tue 11/9/21	Tue 11/16/21	1662
1666	<b>1185</b>	<b>NA</b>	<b>0%</b>	<b>TOWER STAIRS</b>	<b>167.88 days</b>	<b>Fri 12/3/21</b>	<b>Tue 7/26/22</b>	
1667	1186	NA	0%	INSTALL EXIT STAIR 1	150 days	Fri 12/3/21	Fri 7/8/22	1664,805,1429FF
1668	1187	NA	0%	INSTALL EXIT STAIR 2	155 days	Fri 12/10/21	Fri 7/22/22	1667SF+1280 hrs
1669	1188	NA	0%	INSTALL EXIT STAIR 3	150 days	Tue 12/21/21	Tue 7/26/22	1667SF+1240 hrs,1658FF+80 h
1670	<b>1189</b>	<b>NA</b>	<b>0%</b>	<b>MEPS SYSTEMS</b>	<b>461 days</b>	<b>Fri 1/15/21</b>	<b>Tue 11/15/22</b>	
1671	<b>1190</b>	<b>NA</b>	<b>0%</b>	<b>WET UTILITIES (STOMER/SEWER &amp; WATER)</b>	<b>149.88 days</b>	<b>Thu 6/24/21</b>	<b>Wed 1/19/22</b>	
1672	<b>1191</b>	<b>NA</b>	<b>0%</b>	<b>STORM &amp; SEWER</b>	<b>10.88 days</b>	<b>Thu 6/24/21</b>	<b>Thu 7/8/21</b>	
1673	1192	NA	0%	SET UP TRAFFIC CONTROL - HYDE	1 day	Thu 6/24/21	Thu 6/24/21	379
1674	1193	NA	0%	EXCAVATE, PREP, INSPECT TRENCHES	2 days	Fri 6/25/21	Mon 6/28/21	1673
1675	1194	NA	0%	INSTALL, CONNECT, INSPECT LATERALS	2 days	Tue 6/29/21	Wed 6/30/21	1674
1676	1195	NA	0%	FORM, INSPECT POUR MANHOLE BASE	1 day	Tue 6/29/21	Tue 6/29/21	1674
1677	1196	NA	0%	INSTALL MANHOLE, CONNECT LATERALS, INSPECT	2 days	Thu 7/1/21	Fri 7/2/21	1676,1675
1678	1197	NA	0%	BACKFILL TRENCH	2 days	Tue 7/6/21	Wed 7/7/21	1677



University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1679	1198	NA	0%	REMOVE TRAFFIC CONTROL - HYDE	1 day	Thu 7/8/21	Thu 7/8/21	1678
1680	1199	NA	0%	SET UP TRAFFIC CONTROL - MCALLISTER	1 day	Mon 6/28/21	Mon 6/28/21	1673FS+8 hrs
1681	1200	NA	0%	EXCAVATE, PREP, INSPECT TRENCHES	1 day	Thu 7/1/21	Thu 7/1/21	1680,380
1682	1201	NA	0%	INSTALL, CONNECT, INSPECT LATERALS	1 day	Fri 7/2/21	Fri 7/2/21	1681
1683	1202	NA	0%	FORM, INSPECT POUR MANHOLE BASE	1 day	Fri 7/2/21	Fri 7/2/21	1681
1684	1203	NA	0%	INSTALL MANHOLE, CONNECT LATERALS, INSPECT	1 day	Tue 7/6/21	Tue 7/6/21	1682,1683
1685	1204	NA	0%	BACKFILL TRENCH	1 day	Wed 7/7/21	Wed 7/7/21	1684
1686	1205	NA	0%	<b>WATER</b>	<b>143.88 days</b>	<b>Fri 7/2/21</b>	<b>Wed 1/19/22</b>	
1687	2154	NA	0%	<b>Domestic Waters/Fire Water</b>	<b>62.88 days</b>	<b>Mon 9/20/21</b>	<b>Wed 12/15/21</b>	
1688	2153	NA	0%	<i>MEPS Finish Trim/Back Flow Preventers Fire Pump Rm./ Domestic Water Pum</i>	1 day	Mon 9/20/21	Mon 9/20/21	696
1689	2152	NA	0%	Notified Water Quality Division BF are ready for inspection	1 day	Tue 9/21/21	Tue 9/21/21	1688
1690	1206	NA	0%	Emailed/CALL WATER QUALITY DIVISION Ready for Inspec	1 day	Wed 9/22/21	Wed 9/22/21	1689,381
1691	2155	NA	0%	60 DAY WAIT PERIOD PRIOR TO INSTALL WATER METER'S	60 days	Wed 9/22/21	Wed 12/15/21	1690
1692	1207	NA	0%	INSTALL, INSPECT LINE, VALVE, METER BOX	2 days	Thu 12/16/21	Fri 12/17/21	1691
1693	1208	NA	0%	WET TAP BY SFPUC	2 days	Mon 12/20/21	Tue 12/21/21	1692
1694	1209	NA	0%	BACKFILL TRENCH	1 day	Wed 12/22/21	Wed 12/22/21	1693
1695	1210	NA	0%	REMOVE TRAFFIC CONTROL - MCALLISTER	1 day	Wed 1/19/22	Wed 1/19/22	1679,1704
1696	1212	NA	0%	POTHOLE FOR RELOCATED FIRE HYDRANT	1 day	Fri 7/2/21	Fri 7/2/21	1681
1697	1213	NA	0%	EXCAVATE, PREP TRENCH - FIRE SERVICE	1 day	Thu 12/23/21	Thu 12/23/21	1694
1698	1214	NA	0%	INSTALL, INSPECT LINES, VALVES	4 days	Mon 12/27/21	Thu 12/30/21	1697
1699	1215	NA	0%	WET TAPS BY SFPUC	2 days	Mon 1/3/22	Tue 1/4/22	1698
1700	1216	NA	0%	BACKFILL TRENCH	1 day	Wed 1/5/22	Wed 1/5/22	1699
1701	1217	NA	0%	EXCAVATE, PREP TRENCH - FIRE SERVICE	1 day	Thu 1/6/22	Thu 1/6/22	1700,1696
1702	1218	NA	0%	INSTALL, INSPECT LINES, VALVES	4 days	Fri 1/7/22	Wed 1/12/22	1701
1703	1219	NA	0%	WET TAPS BY SFPUC	2 days	Thu 1/13/22	Fri 1/14/22	1702
1704	1211	NA	0%	BACKFILL TRENCH	1 day	Tue 1/18/22	Tue 1/18/22	1703
1705	1220	NA	0%	<b>DRY UTILITIES (ELEC/DATA &amp; GAS)</b>	<b>357.88 days</b>	<b>Fri 1/15/21</b>	<b>Thu 6/2/22</b>	
1706	1221	NA	0%	<b>GAS</b>	<b>6.88 days</b>	<b>Wed 5/25/22</b>	<b>Thu 6/2/22</b>	
1707	1222	NA	0%	EXCAVATE, PREP TRENCH - GAS SERVICE	1 day	Wed 5/25/22	Wed 5/25/22	3564,3565
1708	1223	NA	0%	INSTALL, INSPECT LINE, VALVE	2 days	Thu 5/26/22	Fri 5/27/22	1707
1709	1224	NA	0%	WET TAP BY PG&E	2 days	Tue 5/31/22	Wed 6/1/22	1708
1710	1225	NA	0%	BACKFILL TRENCH	1 day	Thu 6/2/22	Thu 6/2/22	1709
1711	1226	NA	0%	<b>ELECTRICAL, DATA</b>	<b>8.88 days</b>	<b>Fri 1/15/21</b>	<b>Thu 1/28/21</b>	
1712	1227	NA	0%	TEMP ELECTRICAL SERVICE TO SITE BY OTHER	10 days	Fri 1/15/21	Thu 1/28/21	418FS-10 days
1713	1229	NA	0%	<b>MEPS SYSTEMS</b>	<b>296.88 days</b>	<b>Mon 9/27/21</b>	<b>Tue 11/15/22</b>	
1714	1230	NA	0%	ENERGIZE MSB	0 days	Fri 9/23/22	Fri 9/23/22	1754
1715	58	NA	0%	MOBILIZE MEPF ROUGH	0 days	Tue 11/9/21	Tue 11/9/21	1665SS
1716	1232	NA	0%	MOBILIZE FIRE SPRINKLER	0 days	Tue 11/9/21	Tue 11/9/21	1715
1717	1233	NA	0%	MOBILIZE HVAC	0 days	Mon 12/13/21	Mon 12/13/21	1734
1718	1235	NA	0%	PERMANENT POWER -TOWER/PODIUM	0 days	Fri 9/30/22	Fri 9/30/22	1714,1750
1719	134	NA	0%	PERMANENT POWER - TOWER	0 days	Thu 9/1/22	Thu 9/1/22	1752
1720	1238	NA	0%	GAS SERVICE TO PODIUM	0 days	Fri 10/7/22	Fri 10/7/22	1727
1721	1240	NA	0%	GAS SERVICE TO TOWER	0 days	Fri 10/7/22	Fri 10/7/22	1727
1722	1247	NA	0%	<b>PLUMBING</b>	<b>90.13 days</b>	<b>Fri 6/3/22</b>	<b>Fri 10/7/22</b>	
1723	1286	NA	0%	<b>GAS &amp; FUEL OIL</b>	<b>90.13 days</b>	<b>Fri 6/3/22</b>	<b>Fri 10/7/22</b>	
1724	1289	NA	0%	INSTALL GAS MANIFOLD	5 days	Fri 6/3/22	Thu 6/9/22	1710
1725	1293	NA	0%	INSTALL GAS/FUEL OIL TO ROOF	0 days	Fri 7/22/22	Fri 7/22/22	1724,1668,3062FF

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1726	1291	NA	0%	TEST, INSPECT GAS DISTRIBUTION	5 days	Fri 9/23/22	Fri 9/30/22	1725,3641FF
1727	1239	NA	0%	ISSUE PINK TAG	5 days	Fri 9/30/22	Fri 10/7/22	1710,1726
1728	<b>1308</b>	<b>NA</b>	<b>0%</b>	<b>FIRE SPRINKLER</b>	<b>82.88 days</b>	<b>Mon 9/27/21</b>	<b>Wed 1/19/22</b>	
1729	<b>1309</b>	<b>NA</b>	<b>0%</b>	<b>FIRE PUMP</b>	<b>9.88 days</b>	<b>Mon 9/27/21</b>	<b>Fri 10/8/21</b>	
1730	1310	NA	0%	INSTALL PUMPS & CONTROLS	5 days	Mon 9/27/21	Fri 10/1/21	3431
1731	1312	NA	0%	ENERGIZE PUMPS & CONTROLS	5 days	Mon 10/4/21	Fri 10/8/21	1730
1732	<b>1313</b>	<b>NA</b>	<b>0%</b>	<b>PODIUM FIRE SPRINKLERS</b>	<b>51.88 days</b>	<b>Tue 11/9/21</b>	<b>Wed 1/19/22</b>	
1733	1314	NA	0%	INSTALL FIRE RISERS & STANDPIPES	12 days	Tue 11/9/21	Mon 11/29/21	1716
1734	1234	NA	0%	FIRE SPRINKLER DISTRIBUTION	10 days	Tue 11/30/21	Mon 12/13/21	1733
1735	1315	NA	0%	INSTALL FIRE RISERS & STANDPIPES	12 days	Tue 11/30/21	Wed 12/15/21	1733
1736	1316	NA	0%	FIRE SPRINKLER DISTRIBUTION	10 days	Thu 12/16/21	Thu 12/30/21	1735,1734
1737	1317	NA	0%	INSTALL FIRE RISERS & STANDPIPES	12 days	Thu 12/16/21	Tue 1/4/22	1735
1738	1318	NA	0%	FIRE SPRINKLER DISTRIBUTION	10 days	Wed 1/5/22	Wed 1/19/22	1736,1737
1739	<b>1334</b>	<b>NA</b>	<b>0%</b>	<b>MECHANICAL</b>	<b>83.88 days</b>	<b>Tue 12/14/21</b>	<b>Fri 4/8/22</b>	
1740	<b>1335</b>	<b>NA</b>	<b>0%</b>	<b>PODIUM HVAC</b>	<b>83.88 days</b>	<b>Tue 12/14/21</b>	<b>Fri 4/8/22</b>	
1741	1336	NA	0%	PODIUM DUCT, DAMPERS, CONTROLS	20 days	Tue 12/14/21	Wed 1/12/22	1717
1742	1337	NA	0%	COMPLETE PODIUM MECHANICAL EQUIPMENT	20 days	Mon 3/14/22	Fri 4/8/22	1743
1743	1338	NA	0%	PODIUM DUCT, DAMPERS, CONTROLS	20 days	Fri 2/11/22	Fri 3/11/22	1744
1744	1339	NA	0%	PODIUM DUCT, DAMPERS, CONTROLS	20 days	Thu 1/13/22	Thu 2/10/22	1741
1745	<b>1349</b>	<b>NA</b>	<b>0%</b>	<b>ELECTRICAL</b>	<b>107.88 days</b>	<b>Fri 6/17/22</b>	<b>Tue 11/15/22</b>	
1746	<b>1350</b>	<b>NA</b>	<b>0%</b>	<b>PERMANENT POWER</b>	<b>92.88 days</b>	<b>Fri 6/17/22</b>	<b>Tue 10/25/22</b>	
1747	<b>1351</b>	<b>NA</b>	<b>0%</b>	<b>MAIN SERVICE BOARD</b>	<b>82.88 days</b>	<b>Fri 6/17/22</b>	<b>Tue 10/11/22</b>	
1748	1353	NA	0%	MOUNT INSTALL SATELITE XFORMERS, PANELS	80 days	Fri 6/17/22	Tue 10/11/22	1915
1749	1355	NA	0%	GREEN TAG INSPECTION - TOWER/PODIUM	5 days	Fri 8/26/22	Thu 9/1/22	1753,1748SS+160 hrs,51,3425
1750	1236	NA	0%	SERVICE PROVIDER SCHEDULE, COMPLETE SERVICE	20 days	Fri 9/2/22	Fri 9/30/22	1749
1751	76	NA	0%	GREEN TAG INSPECTION - TOWER	5 days	Fri 8/19/22	Thu 8/25/22	3424,51,3425
1752	1237	NA	0%	SERVICE PROVIDER SCHEDULE, COMPLETE SERVICE	5 days	Fri 8/26/22	Thu 9/1/22	1751
1753	1356	NA	0%	GREEN TAG INSPECTION - SERVICED MAIN	5 days	Fri 8/19/22	Thu 8/25/22	1712,3450,3455,51,3425
1754	1231	NA	0%	SERVICE PROVIDER SCHEDULE COMPLETE SERVICE	20 days	Fri 8/26/22	Fri 9/23/22	1753
1755	<b>1363</b>	<b>NA</b>	<b>0%</b>	<b>PODIUM DISTRIBUTION</b>	<b>87.88 days</b>	<b>Fri 6/24/22</b>	<b>Tue 10/25/22</b>	
1756	1364	NA	0%	DISTRIBUTION & PANEL TO RETAIL SHELL	5 days	Wed 10/12/22	Tue 10/18/22	1748
1757	1365	NA	0%	DISTRIBUTION & PANEL TO FOOD SERVICE SHELL	5 days	Wed 10/19/22	Tue 10/25/22	1756
1758	1366	NA	0%	BUS DUCT TO - LEVEL 1	5 days	Mon 7/11/22	Fri 7/15/22	1761
1759	1368	NA	0%	BUS DUCT TO - LEVEL 2	3 days	Mon 7/18/22	Wed 7/20/22	1758
1760	1369	NA	0%	INSTALL SATELITE XFORMERS, PANELS - LEVEL 1	5 days	Fri 6/24/22	Thu 6/30/22	1918
1761	1367	NA	0%	INSTALL SATELITE XFORMERS, PANELS - LEVEL 2	5 days	Fri 7/1/22	Fri 7/8/22	1760
1762	<b>1414</b>	<b>NA</b>	<b>0%</b>	<b>LIFE SAFETY</b>	<b>98.88 days</b>	<b>Thu 6/30/22</b>	<b>Tue 11/15/22</b>	
1763	1415	NA	0%	INSTALL FIRE CONTROL PANEL	5 days	Thu 6/30/22	Thu 7/7/22	2037
1764	1417	NA	0%	INSTALL, TERMINATE RELAYS	20 days	Fri 7/8/22	Thu 8/4/22	1763
1765	1418	NA	0%	ENERGIZE, PROGRAM FIRE CONTROL PANEL	30 days	Mon 10/3/22	Tue 11/15/22	1764,1718
1766	<b>1419</b>	<b>NA</b>	<b>0%</b>	<b>INTERIOR CONSTRUCTION</b>	<b>306 days</b>	<b>Fri 12/3/21</b>	<b>Thu 2/23/23</b>	
1767	<b>1435</b>	<b>NA</b>	<b>0%</b>	<b>PODIUM INTERIOR CONSTRUCTION</b>	<b>134 days</b>	<b>Fri 12/3/21</b>	<b>Thu 6/9/22</b>	
1768	<b>1436</b>	<b>NA</b>	<b>0%</b>	<b>BASEMENT BUILD OUT</b>	<b>134 days</b>	<b>Fri 12/3/21</b>	<b>Thu 6/9/22</b>	
1769	<b>1437</b>	<b>NA</b>	<b>0%</b>	<b>B.O.H., MACHINE ROOM, FCC</b>	<b>29 days</b>	<b>Fri 12/3/21</b>	<b>Thu 1/13/22</b>	
1770	7424	NA	0%	LAYOUT, FRAME WALLS, DOOR FRAMES	5 days	Fri 12/3/21	Fri 12/10/21	938,878
1771	7425	NA	0%	INSTALL MEPS ROUGH	5 days	Fri 12/10/21	Fri 12/17/21	1770
1772	2166	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Mon 12/20/21	Mon 12/20/21	1771

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1773	60	NA	0%	DRYWALL/INSULATE LOWER LEVEL	5 days	Tue 12/21/21	Tue 12/28/21	1772
1774	7414	NA	0%	TAPE	10 days	Tue 12/28/21	Tue 1/11/22	1773
1775	2200	NA	0%	PRIME& First Coat PAINT WALLS, SOFFITS	5 days	Wed 12/29/21	Wed 1/5/22	1773
1776	1405	NA	0%	MEPS Trim	5 days	Thu 1/6/22	Wed 1/12/22	1775
1777	1443	NA	0%	INSTALL DOORS & HARDWARE	5 days	Wed 12/29/21	Wed 1/5/22	1773
1778	2169	NA	0%	LOCK DOORS	1 day	Thu 1/13/22	Thu 1/13/22	1777,1776
1779	7212	NA	0%	ELEVATOR MACHINE ROOM WATER TIGHT/POWERED/LOCKED DOORS ALL	0 days	Thu 1/13/22	Thu 1/13/22	1778
1780	<b>1449</b>	<b>NA</b>	<b>0%</b>	<b>LAUNDRY, BIKE STORAGE, STAFF BREAKROOM</b>	<b>54.88 days</b>	<b>Mon 12/6/21</b>	<b>Fri 2/18/22</b>	
1781	1450	NA	0%	LAYOUT, FRAME WALLS, DOOR FRAMES	5 days	Mon 12/6/21	Fri 12/10/21	1770SS
1782	1452	NA	0%	INSTALL MEPS ROUGH	5 days	Mon 12/13/21	Fri 12/17/21	1781
1783	2167	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Mon 12/20/21	Mon 12/20/21	1782
1784	1454	NA	0%	DRYWALL/INSULATE/TAPE	10 days	Tue 12/21/21	Wed 1/5/22	1783
1785	1459	NA	0%	SKIM CEILINGS	5 days	Tue 12/21/21	Tue 12/28/21	1784SS
1786	1456	NA	0%	PRIME& First Coat PAINT WALLS, SOFFITS	5 days	Wed 12/29/21	Wed 1/5/22	1785
1787	1455	NA	0%	MEPS Trim	5 days	Thu 1/6/22	Wed 1/12/22	1786
1788	1457	NA	0%	INSTALL DOORS & HARDWARE	5 days	Thu 1/6/22	Wed 1/12/22	1784
1789	1458	NA	0%	INSTALL LAUNDRY COUNTER	5 days	Thu 1/13/22	Thu 1/20/22	1788
1790	1460	NA	0%	INSTALL FLOORING	5 days	Fri 1/21/22	Thu 1/27/22	1789
1791	2179	NA	0%	LOCK DOORS	1 day	Fri 1/28/22	Fri 1/28/22	1790
1792	2180	NA	0%	BG Pre-Punch List	1 day	Fri 1/28/22	Fri 1/28/22	1791SS
1793	2181	NA	0%	Subcontractor Complete Pre-Punch List	2 days	Mon 1/31/22	Tue 2/1/22	1792
1794	2182	NA	0%	Rough Cleaning	2 days	Wed 2/2/22	Thu 2/3/22	1793
1795	2183	NA	0%	Owners Punch	1 day	Fri 2/4/22	Fri 2/4/22	1794
1796	2184	NA	0%	Subcontractor Complete Owner Punch	2 days	Mon 2/7/22	Tue 2/8/22	1795
1797	2185	NA	0%	Paint 2nd Coat Finish	5 days	Wed 2/9/22	Tue 2/15/22	1796
1798	2186	NA	0%	Final Cleaning	2 days	Wed 2/16/22	Thu 2/17/22	1797
1799	2187	NA	0%	Owner Acceptance LAUNDRY, BIKE STORAGE, STAFF BREAKROOM	1 day	Fri 2/18/22	Fri 2/18/22	1798
1800	<b>1491</b>	<b>NA</b>	<b>0%</b>	<b>FITNESS CENTER</b>	<b>55.13 days</b>	<b>Tue 12/14/21</b>	<b>Tue 3/1/22</b>	
1801	1492	NA	0%	LAYOUT, FRAME WALLS, DOOR FRAMES	5 days	Tue 12/14/21	Mon 12/20/21	1781SF+40 hrs,1734
1802	1493	NA	0%	INSTALL MEPS ROUGH	5 days	Tue 12/21/21	Tue 12/28/21	1801
1803	2188	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Wed 12/29/21	Wed 12/29/21	1802
1804	1494	NA	0%	DRYWALL/INSULATE/TAPE	10 days	Thu 12/30/21	Thu 1/13/22	1803
1805	1499	NA	0%	SKIM CEILINGS	5 days	Thu 12/30/21	Thu 1/6/22	1804SS
1806	1496	NA	0%	PRIME& First Coat PAINT WALLS, SOFFITS	5 days	Fri 1/7/22	Thu 1/13/22	1805
1807	1495	NA	0%	MEPS Trim	5 days	Tue 2/22/22	Tue 3/1/22	1806,1202SS
1808	1497	NA	0%	INSTALL DOORS & HARDWARE	5 days	Fri 1/14/22	Fri 1/21/22	1804
1809	1498	NA	0%	INSTALL MIRRORS, LOCKERS	5 days	Fri 1/14/22	Fri 1/21/22	1806
1810	1500	NA	0%	INSTALL FLOORING	5 days	Mon 1/24/22	Fri 1/28/22	1809
1811	2190	NA	0%	LOCK DOORS	1 day	Mon 1/31/22	Mon 1/31/22	1810
1812	2191	NA	0%	BG Pre-Punch List	1 day	Mon 1/31/22	Mon 1/31/22	1811SS
1813	2192	NA	0%	Subcontractor Complete Pre-Punch List	2 days	Tue 2/1/22	Wed 2/2/22	1812
1814	2193	NA	0%	Rough Cleaning	2 days	Thu 2/3/22	Fri 2/4/22	1813
1815	2194	NA	0%	Owners Punch	1 day	Mon 2/7/22	Mon 2/7/22	1814
1816	2195	NA	0%	Subcontractor Complete Owner Punch	2 days	Tue 2/8/22	Wed 2/9/22	1815
1817	2196	NA	0%	Paint 2nd Coat Finish	5 days	Thu 2/10/22	Wed 2/16/22	1816
1818	2197	NA	0%	Final Cleaning	2 days	Thu 2/17/22	Fri 2/18/22	1817
1819	2198	NA	0%	Owner Acceptance FITNESS CENTER	1 day	Tue 2/22/22	Tue 2/22/22	1818

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1820	<b>1504</b>	<b>NA</b>	<b>0%</b>	<b>SCHOLARLY PUBS</b>	<b>65.88 days</b>	<b>Tue 12/14/21</b>	<b>Tue 3/15/22</b>	
1821	1505	NA	0%	LAYOUT, FRAME WALLS, DOOR FRAMES	5 days	Tue 12/14/21	Mon 12/20/21	1801SS
1822	1506	NA	0%	INSTALL MEPS ROUGH	5 days	Tue 12/21/21	Tue 12/28/21	1821
1823	2199	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Wed 12/29/21	Wed 12/29/21	1822
1824	1509	NA	0%	DRYWALL/INSULATE/TAPE	10 days	Thu 12/30/21	Thu 1/13/22	1823
1825	1515	NA	0%	SKIM CEILINGS	5 days	Thu 12/30/21	Thu 1/6/22	1824SS
1826	1512	NA	0%	PRIME& First Coat PAINT WALLS, SOFFITS	5 days	Mon 2/7/22	Fri 2/11/22	1825,1831
1827	1510	NA	0%	MEPS Trim	5 days	Mon 2/14/22	Fri 2/18/22	1826
1828	1513	NA	0%	INSTALL DOORS & HARDWARE	5 days	Fri 1/14/22	Fri 1/21/22	1824
1829	1514	NA	0%	INSTALL CABINetry	5 days	Mon 1/24/22	Fri 1/28/22	1828
1830	1524	NA	0%	INSTALL FIRE SHUTTER	5 days	Mon 1/31/22	Fri 2/4/22	1829
1831	2202	NA	0%	INSTALL INTERIOR GLAZING	5 days	Mon 1/31/22	Fri 2/4/22	1829
1832	2203	NA	0%	INSTALL ACOUSTIC CELING	5 days	Mon 2/7/22	Fri 2/11/22	1831
1833	1516	NA	0%	INSTALL FLOORING	5 days	Mon 2/14/22	Fri 2/18/22	1830,1832
1834	2205	NA	0%	LOCK DOORS	1 day	Tue 2/22/22	Tue 2/22/22	1833
1835	2206	NA	0%	BG Pre-Punch List	1 day	Tue 2/22/22	Tue 2/22/22	1834SS
1836	2207	NA	0%	Subcontractor Complete Pre-Punch List	2 days	Wed 2/23/22	Thu 2/24/22	1835
1837	2208	NA	0%	Rough Cleaning	2 days	Fri 2/25/22	Mon 2/28/22	1836
1838	2209	NA	0%	Owners Punch	1 day	Tue 3/1/22	Tue 3/1/22	1837
1839	2210	NA	0%	Subcontractor Complete Owner Punch	2 days	Wed 3/2/22	Thu 3/3/22	1838
1840	2211	NA	0%	Paint 2nd Coat Finish	5 days	Fri 3/4/22	Thu 3/10/22	1839
1841	2212	NA	0%	Final Cleaning	2 days	Fri 3/11/22	Mon 3/14/22	1840
1842	2213	NA	0%	Owner Acceptance SCHOLARLY PUBS	1 day	Tue 3/15/22	Tue 3/15/22	1841
1843	<b>1525</b>	<b>NA</b>	<b>0%</b>	<b>WATER CLOSETS &amp; SHOWERS</b>	<b>70.88 days</b>	<b>Tue 12/14/21</b>	<b>Tue 3/22/22</b>	
1844	1526	NA	0%	LAYOUT, FRAME WALLS/SOFFITS, DOOR FRAMES	5 days	Tue 12/14/21	Mon 12/20/21	1801FF
1845	1527	NA	0%	INSTALL MEPS ROUGH	5 days	Tue 12/21/21	Tue 12/28/21	1844
1846	1529	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Wed 12/29/21	Wed 12/29/21	1845
1847	2214	NA	0%	DRYWALL/INSULATE/TAPE	10 days	Thu 12/30/21	Thu 1/13/22	1846
1848	2215	NA	0%	PRIME& First Coat PAINT WALLS, SOFFITS	5 days	Fri 1/14/22	Fri 1/21/22	1847
1849	1530	NA	0%	MEPS Trim	5 days	Mon 1/24/22	Fri 1/28/22	1848
1850	1532	NA	0%	INSTALL DOORS & HARDWARE	5 days	Fri 1/14/22	Fri 1/21/22	1847
1851	1533	NA	0%	INSTALL CABINetry	5 days	Mon 1/31/22	Fri 2/4/22	1849
1852	1535	NA	0%	INSTALL TILE	10 days	Mon 2/7/22	Fri 2/18/22	1851
1853	1534	NA	0%	INSTALL BATH ACCESSORIES & PARTITIONS	5 days	Tue 2/22/22	Mon 2/28/22	1852
1854	2217	NA	0%	LOCK DOORS	1 day	Tue 3/1/22	Tue 3/1/22	1833,1853
1855	2218	NA	0%	BG Pre-Punch List	1 day	Tue 3/1/22	Tue 3/1/22	1854SS
1856	2219	NA	0%	Subcontractor Complete Pre-Punch List	2 days	Wed 3/2/22	Thu 3/3/22	1855
1857	2220	NA	0%	Rough Cleaning	2 days	Fri 3/4/22	Mon 3/7/22	1856
1858	2221	NA	0%	Owners Punch	1 day	Tue 3/8/22	Tue 3/8/22	1857
1859	2222	NA	0%	Subcontractor Complete Owner Punch	2 days	Wed 3/9/22	Thu 3/10/22	1858
1860	2223	NA	0%	Paint 2nd Coat Finish	5 days	Fri 3/11/22	Thu 3/17/22	1859
1861	2224	NA	0%	Final Cleaning	2 days	Fri 3/18/22	Mon 3/21/22	1860
1862	2225	NA	0%	Owner Acceptance WATER CLOSETS & SHOWERS	1 day	Tue 3/22/22	Tue 3/22/22	1861
1863	<b>1540</b>	<b>NA</b>	<b>0%</b>	<b>AUDITORIUM, PRE-FUNCTION, PANTRY</b>	<b>122.88 days</b>	<b>Tue 12/21/21</b>	<b>Thu 6/9/22</b>	
1864	1541	NA	0%	LAYOUT, FRAME WALLS, DOOR FRAMES	10 days	Tue 12/21/21	Wed 1/5/22	1821
1865	1542	NA	0%	INSTALL MEPS ROUGH/OVERHEAD	10 days	Thu 1/6/22	Thu 1/20/22	1864
1866	2226	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Fri 1/21/22	Fri 1/21/22	1865

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1867	1545	NA	0%	DRYWALL/INSULATE/TAPE	15 days	Mon 1/24/22	Fri 2/11/22	1866
1868	2227	NA	0%	PRIME& First Coat PAINT WALLS, SOFFITS	5 days	Mon 2/14/22	Fri 2/18/22	1867
1869	1558	NA	0%	INSTALL ACOUSTIC CELING	10 days	Tue 2/22/22	Mon 3/7/22	1868
1870	2230	NA	0%	MEPS ROUGH IN ACOUSTIC CEILING	10 days	Tue 3/8/22	Mon 3/21/22	1869
1871	2229	NA	0%	ACOUSTIC CEILING INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILING)	1 day	Tue 3/22/22	Tue 3/22/22	1870
1872	1546	NA	0%	MEPS Trim	10 days	Wed 3/23/22	Tue 4/5/22	1871
1873	1551	NA	0%	TERRAZZO FLOOR	15 days	Wed 4/6/22	Tue 4/26/22	1869,1872
1874	1548	NA	0%	INSTALL DOORS & HARDWARE	5 days	Wed 4/27/22	Tue 5/3/22	1867,1873
1875	1549	NA	0%	INSTALL CABINETRY	5 days	Wed 5/4/22	Tue 5/10/22	1872,1874
1876	1550	NA	0%	INSTALL FLOORING	5 days	Wed 5/11/22	Tue 5/17/22	1875,1873
1877	2232	NA	0%	LOCK DOORS	1 day	Wed 5/18/22	Wed 5/18/22	1833,1853,1876
1878	2233	NA	0%	BG Pre-Punch List	1 day	Wed 5/18/22	Wed 5/18/22	187755
1879	2234	NA	0%	Subcontractor Complete Pre-Punch List	2 days	Thu 5/19/22	Fri 5/20/22	1878
1880	2235	NA	0%	Rough Cleaning	2 days	Mon 5/23/22	Tue 5/24/22	1879
1881	2236	NA	0%	Owners Punch	1 day	Wed 5/25/22	Wed 5/25/22	1880
1882	2237	NA	0%	Subcontractor Complete Owner Punch	2 days	Thu 5/26/22	Fri 5/27/22	1881
1883	2238	NA	0%	Paint 2nd Coat Finish	5 days	Tue 5/31/22	Mon 6/6/22	1882
1884	2239	NA	0%	Final Cleaning	2 days	Tue 6/7/22	Wed 6/8/22	1883
1885	2240	NA	0%	Owner Acceptance AUDITORIUM, PRE-FUNCTION, PANTRY	1 day	Thu 6/9/22	Thu 6/9/22	1884
1886	10422	NA	0%	LOWER LEVEL OWNER ACCEPTANCE	1 day	Wed 6/8/22	Thu 6/9/22	1799FF,1819FF,1842FF,1862FF
1887	<b>1817</b>	<b>NA</b>	<b>0%</b>	<b>INTERIOR CONSTRUCTION ION</b>	<b>306 days</b>	<b>Fri 12/24/21</b>	<b>Thu 2/23/23</b>	
1888	<b>1882</b>	<b>NA</b>	<b>0%</b>	<b>MOCK UP UNIT</b>	<b>20 days</b>	<b>Tue 5/10/22</b>	<b>Tue 6/7/22</b>	
1889	<b>8167</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 3</b>	<b>20 days</b>	<b>Tue 5/10/22</b>	<b>Tue 6/7/22</b>	
1890	1891	NA	0%	DRYWALL & TAPE	0 days	Tue 5/10/22	Tue 5/10/22	2189FF
1891	1892	NA	0%	PRIME PAINT UNITS, DRYWALL TOUCHUP	2 days	Wed 5/11/22	Thu 5/12/22	1890
1892	1893	NA	0%	INSTALL CABINETS & FINISH CARPENTRY	2 days	Fri 5/13/22	Mon 5/16/22	1891
1893	10420	NA	0%	INSTALL COUNTER TOPS/BACKSPLASHES	2 days	Tue 5/17/22	Wed 5/18/22	1892
1894	1894	NA	0%	INSTALL PLUMBING FIXTURES & TRIM	1 day	Thu 5/19/22	Thu 5/19/22	1892,1893
1895	1895	NA	0%	INSTALL ELECTRICAL FIXTURES & TRIM	2 days	Thu 5/19/22	Fri 5/20/22	1891,1893
1896	1896	NA	0%	INSTALL FLOORING	1 day	Fri 5/20/22	Fri 5/20/22	1894
1897	1897	NA	0%	INSTALL APPLIANCES	1 day	Mon 5/23/22	Mon 5/23/22	1896
1898	10421	NA	0%	Install Bathroom Accessories/Mirrors/Tube/Shower Enclosures/Closet Inse	1 day	Mon 5/23/22	Mon 5/23/22	1896
1899	10482	NA	0%	<b>MOCK UP UNIT COMPLETE</b>	1 day	Mon 5/23/22	Tue 5/24/22	1898
1900	<b>10416</b>	<b>NA</b>	<b>0%</b>	<b>PUNCH/CLEANING &amp; UNIT ACCEPTANCE</b>	<b>10.88 days</b>	<b>Tue 5/24/22</b>	<b>Tue 6/7/22</b>	
1901	10417	NA	0%	BG Pre-Punch List	1 day	Tue 5/24/22	Tue 5/24/22	1898
1902	10418	NA	0%	Subcontractor Complete	1 day	Wed 5/25/22	Wed 5/25/22	1901
1903	10411	NA	0%	Rough Cleaning	1 day	Thu 5/26/22	Thu 5/26/22	1902
1904	10412	NA	0%	Owners Punch/Consultents	1 day	Fri 5/27/22	Fri 5/27/22	1903
1905	10413	NA	0%	Subcontractor Complete Owner/Consultent Punch	2 days	Tue 5/31/22	Wed 6/1/22	1904
1906	10414	NA	0%	Paint 2nd Coat Finish	2 days	Thu 6/2/22	Fri 6/3/22	1905
1907	10410	NA	0%	Final Cleaning	1 day	Mon 6/6/22	Mon 6/6/22	1906
1908	10409	NA	0%	Mock Up Unit Acceptance	1 day	Tue 6/7/22	Tue 6/7/22	1907
1909	<b>1899</b>	<b>NA</b>	<b>0%</b>	<b>RESIDENTIAL/MEPS VERTICAL/UNITS/ CORRIDORS</b>	<b>292 days</b>	<b>Fri 12/24/21</b>	<b>Thu 2/23/23</b>	
1910	<b>1560</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 1 (ADDITIONAL SUBCONTRACTOR CREWS ON LEVEL 1)</b>	<b>240.88 days</b>	<b>Tue 1/18/22</b>	<b>Tue 12/20/22</b>	
1911	<b>1561</b>	<b>NA</b>	<b>0%</b>	<b>BACK OF HOUSE, LOADING DOCK, EXITS</b>	<b>43.88 days</b>	<b>Wed 5/18/22</b>	<b>Mon 7/18/22</b>	
1912	1562	NA	0%	LAYOUT, FRAME WALLS, DOOR FRAMES	5 days	Wed 5/18/22	Tue 5/24/22	981,1864,3463,3563,3564
1913	1563	NA	0%	INSTALL MEPS/DAS ROUGH	5 days	Wed 5/25/22	Wed 6/1/22	1912

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1914	2241	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Thu 6/2/22	Thu 6/2/22	1913
1915	1564	NA	0%	DRYWALL/INSULATE/TAPE LEVEL 1	10 days	Fri 6/3/22	Thu 6/16/22	1914
1916	2242	NA	0%	PRIME& First Coat PAINT WALLS, SOFFITS	5 days	Fri 6/17/22	Thu 6/23/22	1915
1917	1407	NA	0%	MEPS Trim	5 days	Fri 6/24/22	Thu 6/30/22	1916
1918	1370	NA	0%	INSTALL DOORS & HARDWARE	5 days	Fri 6/17/22	Thu 6/23/22	1915
1919	2244	NA	0%	LOCK DOORS	1 day	Fri 6/24/22	Fri 6/24/22	1918
1920	2245	NA	0%	BG Pre-Punch List	1 day	Fri 6/24/22	Fri 6/24/22	1919SS
1921	2246	NA	0%	Subcontractor Complete Pre-Punch List	2 days	Mon 6/27/22	Tue 6/28/22	1920
1922	2247	NA	0%	Rough Cleaning	2 days	Wed 6/29/22	Thu 6/30/22	1921
1923	2248	NA	0%	Owners Punch	1 day	Fri 7/1/22	Fri 7/1/22	1922
1924	2249	NA	0%	Subcontractor Complete Owner Punch	2 days	Tue 7/5/22	Wed 7/6/22	1923
1925	2250	NA	0%	Paint 2nd Coat Finish	5 days	Thu 7/7/22	Wed 7/13/22	1924
1926	2251	NA	0%	Final Cleaning	2 days	Thu 7/14/22	Fri 7/15/22	1925
1927	2252	NA	0%	Owner Acceptance BACK OF HOUSE, LOADING DOCK, EXITS	1 day	Mon 7/18/22	Mon 7/18/22	1926
1928	1565	NA	0%	<b>RESTROOMS, MOTHERS ROOM, CIRCULATION</b>	<b>68.88 days</b>	<b>Wed 5/25/22</b>	<b>Mon 8/29/22</b>	
1929	1566	NA	0%	LAYOUT, FRAME WALLS/SOFFITS, DOOR FRAMES	5 days	Wed 5/25/22	Wed 6/1/22	1912,1736
1930	1567	NA	0%	INSTALL MEPS/DAS ROUGH	5 days	Thu 6/2/22	Wed 6/8/22	1929
1931	2253	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Thu 6/9/22	Thu 6/9/22	1930
1932	1569	NA	0%	DRYWALL/INSULATE/TAPE	10 days	Fri 6/10/22	Thu 6/23/22	1931
1933	2254	NA	0%	PRIME& First Coat PAINT WALLS, SOFFITS	5 days	Thu 6/23/22	Thu 6/30/22	1932
1934	1570	NA	0%	MEPS Trim	5 days	Fri 7/1/22	Fri 7/8/22	1933
1935	1572	NA	0%	INSTALL DOORS & HARDWARE	5 days	Fri 6/24/22	Thu 6/30/22	1932
1936	1573	NA	0%	INSTALL CABINETS	5 days	Mon 7/11/22	Fri 7/15/22	1935,1934
1937	1575	NA	0%	INSTALL TILE	10 days	Mon 7/18/22	Fri 7/29/22	1936
1938	1574	NA	0%	INSTALL BATH ACCESSORIES & PARTITIONS	5 days	Mon 8/1/22	Fri 8/5/22	1937
1939	2256	NA	0%	LOCK DOORS	1 day	Mon 8/8/22	Mon 8/8/22	1938,1935
1940	2257	NA	0%	BG Pre-Punch List	1 day	Mon 8/8/22	Mon 8/8/22	1939SS
1941	2258	NA	0%	Subcontractor Complete Pre-Punch List	2 days	Tue 8/9/22	Wed 8/10/22	1940
1942	2259	NA	0%	Rough Cleaning	2 days	Thu 8/11/22	Fri 8/12/22	1941
1943	2260	NA	0%	Owners Punch	1 day	Mon 8/15/22	Mon 8/15/22	1942
1944	2261	NA	0%	Subcontractor Complete Owner Punch	2 days	Tue 8/16/22	Wed 8/17/22	1943
1945	2262	NA	0%	Paint 2nd Coat Finish	5 days	Thu 8/18/22	Wed 8/24/22	1944
1946	2263	NA	0%	Final Cleaning	2 days	Thu 8/25/22	Fri 8/26/22	1945
1947	2264	NA	0%	Owner Acceptance RESTROOMS, MOTHERS ROOM, CIRCULATION	1 day	Mon 8/29/22	Mon 8/29/22	1946
1948	1580	NA	0%	<b>COURTROOMS</b>	<b>143.88 days</b>	<b>Thu 6/2/22</b>	<b>Tue 12/20/22</b>	
1949	1581	NA	0%	<b>BAXTER COURTROOM, CIRCULATION, WAITING</b>	<b>121.88 days</b>	<b>Thu 6/2/22</b>	<b>Fri 11/18/22</b>	
1950	1582	NA	0%	LAYOUT, FRAME WALLS, DOOR FRAMES	5 days	Thu 6/2/22	Wed 6/8/22	1929
1951	1583	NA	0%	INSTALL MEPS/DAS ROUGH	5 days	Thu 6/9/22	Wed 6/15/22	1950
1952	2265	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Thu 6/16/22	Thu 6/16/22	1951
1953	1586	NA	0%	DRYWALL/INSULATE/TAPE	10 days	Fri 6/17/22	Thu 6/30/22	1951,1952
1954	2266	NA	0%	PRIME& First Coat PAINT WALLS, SOFFITS	5 days	Fri 7/1/22	Fri 7/8/22	1953
1955	2267	NA	0%	INSTALL ACOUSTIC CEILING FRAMING	10 days	Mon 7/11/22	Fri 7/22/22	1954,1951
1956	2270	NA	0%	MEPS ROUGHIN ACOUSTIC CEILING	10 days	Mon 7/25/22	Fri 8/5/22	1955
1957	2272	NA	0%	INSPECTION MEPS ACOUSTIC CEILING	1 day	Mon 8/8/22	Mon 8/8/22	1956
1958	2271	NA	0%	INSTALL ACOUSTIC CEILING PANELS	10 days	Tue 8/9/22	Mon 8/22/22	1957
1959	1591	NA	0%	INSTALL BUILTUP FLOOR, FRAME BENCH, JURY BOX, ET AL	10 days	Tue 8/23/22	Tue 9/6/22	1954,1955,1956,1958
1960	1588	NA	0%	FINISH CARPENTRY, INSTALL DOORS & HARDWARE	10 days	Wed 9/7/22	Tue 9/20/22	1959

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
1961	1589	NA	0%	WOOD PANELING, STONE CLADDING	20 days	Wed 9/21/22	Wed 10/19/22	1960
1962	1590	NA	0%	INSTALL FLOORING & PROTECTION (FLOORING/PANELING SEQUENCE	5 days	Thu 10/20/22	Wed 10/26/22	1961
1963	2273	NA	0%	LOCK DOORS	1 day	Thu 10/27/22	Thu 10/27/22	1962
1964	2274	NA	0%	BG Pre-Punch List	1 day	Thu 10/27/22	Thu 10/27/22	1963SS
1965	2275	NA	0%	Subcontractor Complete Pre-Punch List	2 days	Fri 10/28/22	Mon 10/31/22	1964
1966	2276	NA	0%	Rough Cleaning	2 days	Tue 11/1/22	Wed 11/2/22	1965
1967	2277	NA	0%	Owners Punch	1 day	Thu 11/3/22	Thu 11/3/22	1966
1968	2278	NA	0%	Subcontractor Complete Owner Punch	2 days	Fri 11/4/22	Mon 11/7/22	1967
1969	2279	NA	0%	Paint 2nd Coat Finish	5 days	Tue 11/8/22	Tue 11/15/22	1968
1970	2280	NA	0%	Final Cleaning	2 days	Wed 11/16/22	Thu 11/17/22	1969
1971	2281	NA	0%	Owner Acceptance BAXTER COURTROOM, CIRCULATION, WAITING	1 day	Fri 11/18/22	Fri 11/18/22	1970
1972	<b>1598</b>	<b>NA</b>	<b>0%</b>	<b>SPECTER COURTROOM, CIRCULATION</b>	<b>138.88 days</b>	<b>Thu 6/9/22</b>	<b>Tue 12/20/22</b>	
1973	2283	NA	0%	LAYOUT, FRAME WALLS, DOOR FRAMES	5 days	Thu 6/9/22	Wed 6/15/22	1950
1974	2284	NA	0%	INSTALL MEPS/DAS ROUGH	5 days	Thu 6/16/22	Wed 6/22/22	1973
1975	2285	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Thu 6/23/22	Thu 6/23/22	1974
1976	2286	NA	0%	DRYWALL/INSULATE/TAPE	10 days	Fri 6/24/22	Fri 7/8/22	1974,1975
1977	2287	NA	0%	PRIME& First Coat PAINT WALLS, SOFFITS	5 days	Mon 7/11/22	Fri 7/15/22	1976
1978	2288	NA	0%	INSTALL ACOUSTIC CEILING FRAMING	10 days	Mon 7/25/22	Fri 8/5/22	1974,1977,1955
1979	2289	NA	0%	MEPS ROUGHIN ACOUSTIC CEILING	10 days	Mon 8/8/22	Fri 8/19/22	1978,1956
1980	2290	NA	0%	INSPECTION MEPS ACOUSTIC CEILING	1 day	Mon 8/22/22	Mon 8/22/22	1979,1957
1981	2291	NA	0%	INSTALL ACOUSTIC CEILING PANELS	10 days	Tue 8/23/22	Tue 9/6/22	1980,1958
1982	2292	NA	0%	INSTALL BUILTUP FLOOR, FRAME BENCH, JURY BOX, ET AL	10 days	Wed 9/7/22	Tue 9/20/22	1977,1978,1979,1981,1959
1983	2293	NA	0%	FINISH CARPENTRY, INSTALL DOORS & HARDWARE	10 days	Wed 9/21/22	Tue 10/4/22	1982,1960
1984	2294	NA	0%	WOOD PANELING, STONE CLADDING	20 days	Thu 10/20/22	Thu 11/17/22	1983,1961
1985	2295	NA	0%	INSTALL FLOORING & PROTECTION (FLOORING/PANELING SEQUENCE	5 days	Fri 11/18/22	Mon 11/28/22	1984
1986	2296	NA	0%	LOCK DOORS	1 day	Tue 11/29/22	Tue 11/29/22	1985
1987	2297	NA	0%	BG Pre-Punch List	1 day	Tue 11/29/22	Tue 11/29/22	1986SS
1988	2298	NA	0%	Subcontractor Complete Pre-Punch List	2 days	Wed 11/30/22	Thu 12/1/22	1987
1989	2299	NA	0%	Rough Cleaning	2 days	Fri 12/2/22	Mon 12/5/22	1988
1990	2300	NA	0%	Owners Punch	1 day	Tue 12/6/22	Tue 12/6/22	1989
1991	2301	NA	0%	Subcontractor Complete Owner Punch	2 days	Wed 12/7/22	Thu 12/8/22	1990
1992	2302	NA	0%	Paint 2nd Coat Finish	5 days	Fri 12/9/22	Thu 12/15/22	1991
1993	2303	NA	0%	Final Cleaning	2 days	Fri 12/16/22	Mon 12/19/22	1992
1994	2304	NA	0%	Owner Acceptance SPECTER COURTROOM, CIRCULATION	1 day	Tue 12/20/22	Tue 12/20/22	1993
1995	<b>1625</b>	<b>NA</b>	<b>0%</b>	<b>ENTRY LOBBY</b>	<b>199.88 days</b>	<b>Wed 1/19/22</b>	<b>Tue 10/25/22</b>	
1996	<b>1626</b>	<b>NA</b>	<b>0%</b>	<b>KITCHEN, CAFE</b>	<b>88.88 days</b>	<b>Thu 6/16/22</b>	<b>Tue 10/18/22</b>	
1997	1627	NA	0%	LAYOUT, FRAME WALLS/SOFFITS, DOOR FRAMES	5 days	Thu 6/16/22	Wed 6/22/22	1973
1998	1628	NA	0%	INSTALL MEPS/DAS ROUGH	5 days	Thu 6/30/22	Thu 7/7/22	1997,2009SF+80 hrs
1999	10155	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Thu 7/7/22	Fri 7/8/22	1998
2000	1630	NA	0%	DRYWALL, TAPE	10 days	Mon 7/11/22	Fri 7/22/22	1998,1999
2001	1631	NA	0%	ELECTRIC TRIM, LIGHTS	5 days	Mon 8/8/22	Fri 8/12/22	2005
2002	1633	NA	0%	INSTALL DOORS & HARDWARE	5 days	Mon 8/15/22	Fri 8/19/22	2001
2003	1634	NA	0%	INSTALL CABINERY	5 days	Mon 8/22/22	Fri 8/26/22	2002
2004	1635	NA	0%	INSTALL WOOD PANELING	5 days	Mon 8/29/22	Fri 9/2/22	2003
2005	1632	NA	0%	PRIME PAINT WALLS, SOFFITS	5 days	Mon 8/1/22	Fri 8/5/22	2011
2006	1637	NA	0%	DRYWALL TOUCH UP, FINAL PAINT	5 days	Tue 9/6/22	Mon 9/12/22	2010,2004
2007	1639	NA	0%	PRE-PUNCH	20 days	Tue 9/13/22	Tue 10/11/22	2006

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2008	1640	NA	0%	FINAL CLEANUP	5 days	Wed 10/12/22	Tue 10/18/22	2007
2009	1629	NA	0%	ROUGH PLUMBING, TEST & INSPECT	10 days	Thu 6/23/22	Thu 7/7/22	1997
2010	1638	NA	0%	PLUMBNG FIXTURES & TRIM	5 days	Mon 8/29/22	Fri 9/2/22	2003
2011	1636	NA	0%	INSTALL TILE	5 days	Mon 7/25/22	Fri 7/29/22	2000
2012	<b>1641</b>	<b>NA</b>	<b>0%</b>	<b>GRAND STAIR &amp; LOBBY</b>	<b>199.88 days</b>	<b>Wed 1/19/22</b>	<b>Tue 10/25/22</b>	
2013	1642	NA	0%	LAYOUT, FRAME WALLS, DOOR FRAMES	5 days	Wed 1/19/22	Tue 1/25/22	3571
2014	1645	NA	0%	FIRE SPRINKLER DROPS	10 days	Wed 2/2/22	Tue 2/15/22	2021SF+80 hrs,2022,2013
2015	1648	NA	0%	DRYWALL, TAPE SOFFIT	10 days	Wed 2/16/22	Wed 3/2/22	2014
2016	1649	NA	0%	ELECTRIC TRIM	5 days	Thu 5/12/22	Wed 5/18/22	2027,2018,2027SF+120 hrs
2017	1652	NA	0%	INSTALL FLOORING, WALK AWAY MATS	5 days	Thu 5/12/22	Wed 5/18/22	2027
2018	1651	NA	0%	WOOD PANELING, PAINT WALLS	10 days	Thu 4/14/22	Wed 4/27/22	2028
2019	1654	NA	0%	PRE-PUNCH	20 days	Thu 5/19/22	Thu 6/16/22	2017,2029,2030,2016
2020	1429	NA	0%	FINAL CLEANUP	5 days	Wed 10/19/22	Tue 10/25/22	2019,2008
2021	1646	NA	0%	ROUGH ELECTRIC, TEST & INSPECT	10 days	Wed 1/26/22	Tue 2/8/22	2013
2022	1647	NA	0%	PRE-ROCK ENTRY WALLS	5 days	Wed 1/26/22	Tue 2/1/22	2013SF+80 hrs
2023	1658	NA	0%	FRAME HIGH SOFFIT	5 days	Wed 2/2/22	Tue 2/8/22	2022
2024	1659	NA	0%	INSTALL CEILING LIGHTING	10 days	Wed 2/9/22	Wed 2/23/22	2023
2025	1660	NA	0%	INSTALL ACOUSTIC CELING; PAINT SOFFIT	10 days	Thu 3/3/22	Wed 3/16/22	2015,2026,2024
2026	1661	NA	0%	COMPLETE CEILING HVAC	10 days	Wed 2/9/22	Wed 2/23/22	2023
2027	1650	NA	0%	INSTALL TBD FINISHES	10 days	Thu 4/28/22	Wed 5/11/22	2028,2018
2028	1653	NA	0%	DRYWALL, REVEALS, FINISH	20 days	Thu 3/17/22	Wed 4/13/22	2025
2029	1655	NA	0%	INSTALL METAL RAILS	5 days	Thu 4/14/22	Wed 4/20/22	2028
2030	1656	NA	0%	INSTALL GLASS RAILS	5 days	Thu 4/14/22	Wed 4/20/22	2028
2031	<b>1676</b>	<b>NA</b>	<b>0%</b>	<b>FIRE CONTROL CENTER</b>	<b>112 days</b>	<b>Mon 1/24/22</b>	<b>Wed 6/29/22</b>	
2032	1677	NA	0%	LAYOUT, FRAME WALLS, DOOR FRAMES	5 days	Wed 5/18/22	Tue 5/24/22	1912SF+40 hrs
2033	10156	NA	0%	INSTALL MEPS/DAS ROUGH	5 days	Mon 1/24/22	Mon 1/31/22	2032
2034	1678	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	5 days	Wed 5/25/22	Wed 6/1/22	2032,2033
2035	1679	NA	0%	DRYWALL, TAPE, PAINT WALLS	10 days	Thu 6/2/22	Wed 6/15/22	2034
2036	1680	NA	0%	ELECTRIC TRIM, LIGHTS	5 days	Thu 6/16/22	Wed 6/22/22	2035
2037	1416	NA	0%	INSTALL DOORS & HARDWARE	5 days	Thu 6/23/22	Wed 6/29/22	2036
2038	<b>1683</b>	<b>NA</b>	<b>0%</b>	<b>MAIL ROOM, CIRCULATION</b>	<b>65.88 days</b>	<b>Tue 1/18/22</b>	<b>Tue 4/19/22</b>	
2039	1684	NA	0%	LAYOUT, FRAME WALLS, DOOR FRAMES	5 days	Tue 1/18/22	Mon 1/24/22	3463
2040	1685	NA	0%	INSTALL MEPS/DAS ROUGH	5 days	Tue 1/25/22	Mon 1/31/22	2039
2041	10157	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	5 days	Mon 1/31/22	Mon 2/7/22	2040
2042	1686	NA	0%	DRYWALL, TAPE, PAINT WALLS	10 days	Tue 2/8/22	Tue 2/22/22	2041
2043	1687	NA	0%	ELECTRIC TRIM, LIGHTS	5 days	Wed 2/23/22	Tue 3/1/22	2042
2044	1688	NA	0%	INSTALL DOORS & HARDWARE	5 days	Wed 3/2/22	Tue 3/8/22	2043
2045	1689	NA	0%	INSTALL FLOORING	5 days	Wed 3/9/22	Tue 3/15/22	2044
2046	1690	NA	0%	PRE-PUNCH	20 days	Wed 3/16/22	Tue 4/12/22	2045
2047	1691	NA	0%	FINAL CLEANUP	5 days	Wed 4/13/22	Tue 4/19/22	2046
2048	<b>1692</b>	<b>NA</b>	<b>0%</b>	<b>OFFICES/SECURITY</b>	<b>80.88 days</b>	<b>Tue 1/18/22</b>	<b>Tue 5/10/22</b>	
2049	1693	NA	0%	LAYOUT, FRAME WALLS, DOOR FRAMES	5 days	Tue 1/18/22	Mon 1/24/22	2039SF+40 hrs
2050	10159	NA	0%	INSTALL MEPS/DAS ROUGH	5 days	Mon 1/24/22	Mon 1/31/22	2049
2051	10158	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	5 days	Mon 1/31/22	Mon 2/7/22	2050
2052	1694	NA	0%	DRYWALL, TAPE WALLS	10 days	Tue 2/8/22	Tue 2/22/22	2051
2053	1696	NA	0%	ELECTRIC TRIM, LIGHTS	5 days	Wed 3/9/22	Tue 3/15/22	2052,2060
2054	1698	NA	0%	INSTALL DOORS & HARDWARE	5 days	Wed 2/23/22	Tue 3/1/22	2052



University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2055	1699	NA	0%	PREROCK, FIRETAPE	5 days	Tue 1/25/22	Mon 1/31/22	2049
2056	1700	NA	0%	INSTALL ACOUSTIC CELING GRID	5 days	Tue 2/1/22	Mon 2/7/22	2055
2057	1701	NA	0%	CELING/ WALL ELEC, HVAC, FIRE SPRINKLER	5 days	Tue 2/8/22	Mon 2/14/22	2056
2058	1695	NA	0%	INSPECTONS	5 days	Tue 2/15/22	Tue 2/22/22	2057
2059	1702	NA	0%	INSTALL CEILING PANELS	5 days	Wed 2/23/22	Tue 3/1/22	2052
2060	1697	NA	0%	PAINT & FINISH	5 days	Wed 3/2/22	Tue 3/8/22	2054,2059
2061	1703	NA	0%	INSTALL FLOORING	5 days	Wed 3/16/22	Tue 3/22/22	2053
2062	1704	NA	0%	PRE-PUNCH	20 days	Wed 3/23/22	Tue 4/19/22	2061
2063	1432	NA	0%	FINAL CLEANUP	5 days	Wed 5/4/22	Tue 5/10/22	2079FF,2062,2047FF
2064	<b>1706</b>	<b>NA</b>	<b>0%</b>	<b>TOUCHDOWN</b>	<b>80.88 days</b>	<b>Tue 1/18/22</b>	<b>Tue 5/10/22</b>	
2065	1707	NA	0%	LAYOUT, FRAME WALLS, DOOR FRAMES	5 days	Tue 1/18/22	Mon 1/24/22	2049SF+40 hrs
2066	10161	NA	0%	INSTALL MEPS/DAS ROUGH	5 days	Mon 1/24/22	Mon 1/31/22	2065
2067	10160	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	5 days	Mon 1/31/22	Mon 2/7/22	2066
2068	1708	NA	0%	DRYWALL, TAPE WALLS	10 days	Wed 2/23/22	Tue 3/8/22	2074,2067
2069	1710	NA	0%	ELECTRIC TRIM, LIGHTS	5 days	Wed 3/23/22	Tue 3/29/22	2076,2068
2070	1712	NA	0%	INSTALL DOORS & HARDWARE	5 days	Wed 3/9/22	Tue 3/15/22	2068
2071	1713	NA	0%	PREROCK, FIRETAPE	5 days	Tue 1/25/22	Mon 1/31/22	2065
2072	1714	NA	0%	INSTALL ACOUSTIC CELING GRID	5 days	Tue 2/1/22	Mon 2/7/22	2071
2073	1715	NA	0%	CELING/ WALL ELEC, HVAC, FIRE SPRINKLER	5 days	Tue 2/8/22	Mon 2/14/22	2072
2074	1709	NA	0%	INSPECTONS	5 days	Tue 2/15/22	Tue 2/22/22	2073
2075	1716	NA	0%	INSTALL CEILING PANELS	5 days	Wed 3/9/22	Tue 3/15/22	2068
2076	1711	NA	0%	PAINT & FINISH	5 days	Wed 3/16/22	Tue 3/22/22	2070,2075
2077	1717	NA	0%	INSTALL FLOORING	5 days	Wed 3/30/22	Tue 4/5/22	2069
2078	1718	NA	0%	PRE-PUNCH	20 days	Wed 4/6/22	Tue 5/3/22	2077
2079	1705	NA	0%	FINAL CLEANUP	5 days	Wed 5/4/22	Tue 5/10/22	2078
2080	10423	NA	0%	LEVEL 1 OWNER ACCEPTANCE	1 day	Tue 10/25/22	Wed 10/26/22	1996,2031,2012,2038,2048,20
2081	<b>8078</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 2 MEPS DISTRIBUTION LEVEL (ADDITIONAL SUBCONTRACTOR CREW)</b>	<b>221 days</b>	<b>Thu 12/30/21</b>	<b>Tue 11/15/22</b>	
2082	8160	NA	0%	Re-Shores have been Removed/Dry Finish/ Prep Ceilings	3 days	Thu 12/30/21	Mon 1/3/22	1024,991
2083	8159	NA	0%	Spray Concrete Ceiling Bonding Agent	2 days	Tue 1/4/22	Wed 1/5/22	2082
2084	8158	NA	0%	Layout Walls Install Top Tracks	10 days	Thu 1/6/22	Wed 1/19/22	2083
2085	8157	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	10 days	Thu 1/6/22	Wed 1/19/22	2084FF
2086	<b>8079</b>	<b>NA</b>	<b>0%</b>	<b>MEPS VERTICAL</b>	<b>75 days</b>	<b>Thu 1/20/22</b>	<b>Wed 5/4/22</b>	
2087	8081	NA	0%	Fire Sprinkler Risers	5 days	Thu 1/20/22	Wed 1/26/22	2084
2088	8162	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	15 days	Thu 1/20/22	Wed 2/9/22	2084
2089	8156	NA	0%	Fire Sprinkler Distribution	15 days	Thu 2/10/22	Wed 3/2/22	2084,2088
2090	8083	NA	0%	Storm/Waste/Vent	15 days	Thu 3/3/22	Wed 3/23/22	2089
2091	8084	NA	0%	Duct Riser/HORIZONTALS	15 days	Thu 3/24/22	Wed 4/13/22	2090
2092	8085	NA	0%	Water/Gas/Fuel	15 days	Thu 4/14/22	Wed 5/4/22	2091
2093	8086	NA	0%	Heat Pump Risers	10 days	Thu 4/14/22	Wed 4/27/22	2091
2094	<b>8107</b>	<b>NA</b>	<b>0%</b>	<b>Rough-In</b>	<b>95 days</b>	<b>Mon 1/31/22</b>	<b>Wed 6/15/22</b>	
2095	8108	NA	0%	L2 Window Walls/Precast Panels Complete	0 days	Mon 1/31/22	Mon 1/31/22	3469
2096	8109	NA	0%	Party & Corridor Walls/Duct Shafts/Electrical Rm L2	10 days	Thu 5/5/22	Wed 5/18/22	2095,2086
2097	8110	NA	0%	Top Down	5 days	Thu 5/12/22	Wed 5/18/22	2096FF
2098	8113	NA	0%	Frame Ceilings	10 days	Wed 5/18/22	Wed 6/1/22	2097
2099	8114	NA	0%	Rough-In MEPS/DAS, Walls,CEILINGS (COMPLETE ELECRICAL PANELS & B	10 days	Tue 5/31/22	Tue 6/14/22	2098FS-1 day
2100	8115	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Wed 6/15/22	Wed 6/15/22	2099

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2101	8116	NA	0%	Build Group Quality Control Inspection (Consultant's/Client/Arch if Required) Subcontractor's Distributes One Collilated Complete List To	1 day	Thu 6/9/22	Fri 6/10/22	2099FS-3 days
2102	8117	NA	0%	Subcontractors Complete Build Group's Quality Control Inspection	1 day	Mon 6/13/22	Mon 6/13/22	2101
2103	8118	NA	0%	Build Group Back-Check Subcontractors Completion	1 day	Mon 6/13/22	Tue 6/14/22	2102
2104	<b>8119</b>	<b>NA</b>	<b>0%</b>	<b>Rock and Tape</b>	<b>25 days</b>	<b>Tue 6/14/22</b>	<b>Tue 7/19/22</b>	
2105	8120	NA	0%	Insulate Walls	5 days	Wed 6/15/22	Tue 6/21/22	2100SF,2103
2106	8121	NA	0%	Drywall Delivery After MEPS Rough IN	1 day	Tue 6/14/22	Tue 6/14/22	2099FF
2107	8122	NA	0%	Door Frames	5 days	Wed 6/15/22	Tue 6/21/22	2099FF,2106
2108	8123	NA	0%	Hang Drywall L2	10 days	Wed 6/22/22	Wed 7/6/22	2100,2103,2107,2181
2109	8124	NA	0%	Tape & Drywall Touch Up (Walls/Ceilings & Corridors)	10 days	Wed 7/6/22	Tue 7/19/22	2108FS-1 day
2110	<b>8125</b>	<b>NA</b>	<b>0%</b>	<b>Finishes</b>	<b>59 days</b>	<b>Tue 7/19/22</b>	<b>Tue 10/11/22</b>	
2111	8126	NA	0%	Prime Paint/1ST COAT PAINT	10 days	Tue 7/19/22	Mon 8/1/22	2109FS-1 day
2112	8127	NA	0%	Install Interior Door Frames/Sliders	10 days	Tue 8/2/22	Mon 8/15/22	2111
2113	8128	NA	0%	Install Unit Entry Doors- Glazing/Hardware	10 days	Tue 8/2/22	Mon 8/15/22	2112SS
2114	8129	NA	0%	Install WP Redgard at Restroom Walls & Floors	5 days	Tue 8/2/22	Mon 8/8/22	2111
2115	8134	NA	0%	Install Tile flooring/Base	10 days	Fri 8/26/22	Fri 9/9/22	2118
2116	8164	NA	0%	MEPS Trim Restroom	5 days	Fri 9/9/22	Fri 9/16/22	2115
2117	8163	NA	0%	Install Toilet Partitions	1 day	Fri 9/16/22	Mon 9/19/22	2116
2118	8131	NA	0%	Install Cabinets/Trim/Linen Closets	10 days	Mon 8/15/22	Fri 8/26/22	2112FS-1 day
2119	8132	NA	0%	Install Stone Countertops/Back Splashes	10 days	Mon 8/15/22	Fri 8/26/22	2118FF
2120	8133	NA	0%	Install Stone Backsplash at Kitchen Counters	10 days	Mon 8/15/22	Fri 8/26/22	2119FF
2121	8135	NA	0%	Install Stone Entry Threshold & Protection	10 days	Fri 8/12/22	Fri 8/26/22	2119FF,2120FF
2122	8138	NA	0%	Install Unit Flooring & Base	10 days	Fri 8/26/22	Fri 9/9/22	2121
2123	8139	NA	0%	Install Window Blinds	10 days	Fri 9/9/22	Fri 9/23/22	2122
2124	8140	NA	0%	Appliances	10 days	Fri 9/9/22	Fri 9/23/22	2122
2125	8141	NA	0%	Install Finish Appliance Panels	10 days	Fri 9/9/22	Fri 9/23/22	2124FF
2126	8144	NA	0%	Install MEPS Trim	10 days	Fri 9/23/22	Fri 10/7/22	2124
2127	8146	NA	0%	LOCK DOORS	1 day	Tue 10/11/22	Tue 10/11/22	2126
2128	<b>8147</b>	<b>NA</b>	<b>0%</b>	<b>PUNCH/CLEANING &amp; UNIT ACCEPTANCE</b>	<b>26 days</b>	<b>Tue 10/11/22</b>	<b>Tue 11/15/22</b>	
2129	8148	NA	0%	BG Pre-Punch List	1 day	Tue 10/11/22	Tue 10/11/22	2127SS
2130	8149	NA	0%	Subcontractor Complete Pre-Punch List L3 NORTH	3 days	Wed 10/12/22	Fri 10/14/22	2129
2131	8150	NA	0%	Rough Cleaning	3 days	Mon 10/17/22	Wed 10/19/22	2130
2132	8151	NA	0%	Owners Punch	1 day	Thu 10/20/22	Thu 10/20/22	2131
2133	8152	NA	0%	Subcontractor Complete Owner Punch	2 days	Fri 10/21/22	Mon 10/24/22	2132
2134	8153	NA	0%	Paint 2nd Coat Finish	10 days	Tue 10/25/22	Mon 11/7/22	2133
2135	8154	NA	0%	Final Cleaning	5 days	Tue 11/8/22	Mon 11/14/22	2134
2136	8155	NA	0%	Unit Acceptance Level 2	1 day	Tue 11/15/22	Tue 11/15/22	2135
2137	<b>2416</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 3</b>	<b>188 days</b>	<b>Fri 12/24/21</b>	<b>Thu 9/22/22</b>	
2138	<b>7722</b>	<b>NA</b>	<b>0%</b>	<b>MEPS VERTICAL</b>	<b>20 days</b>	<b>Fri 12/24/21</b>	<b>Thu 1/20/22</b>	
2139	7723	NA	0%	PROSHORE SHORING L6	0 days	Fri 12/24/21	Fri 12/24/21	1024SS
2140	7717	NA	0%	Fire Sprinkler Risers	10 days	Fri 12/24/21	Thu 1/6/22	2139
2141	<b>7724</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Fri 12/24/21</b>	<b>Thu 1/13/22</b>	
2142	7727	NA	0%	Storm/Waste/Vent	5 days	Fri 12/24/21	Thu 12/30/21	2139
2143	7728	NA	0%	Duct Riser	5 days	Fri 12/31/21	Thu 1/6/22	2142
2144	7726	NA	0%	Water/Gas/Fuel	5 days	Fri 1/7/22	Thu 1/13/22	2143
2145	7729	NA	0%	Heat Pump Risers	5 days	Fri 1/7/22	Thu 1/13/22	2143
2146	<b>7725</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Fri 12/31/21</b>	<b>Thu 1/20/22</b>	

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2147	7719	NA	0%	Storm/Waste/Vent	5 days	Fri 12/31/21	Thu 1/6/22	2142
2148	7715	NA	0%	Duct Riser	5 days	Fri 1/7/22	Thu 1/13/22	2143
2149	7720	NA	0%	Water/Gas/Fuel	5 days	Fri 1/14/22	Thu 1/20/22	2148,2144
2150	7730	NA	0%	Heat Pump Risers	5 days	Fri 1/14/22	Thu 1/20/22	2147,2145
2151	<b>7797</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT/SPRINKLERS-ELECTRICAL DISTRIBUTION/SHAFTS</b>	<b>30 days</b>	<b>Tue 1/11/22</b>	<b>Mon 2/21/22</b>	
2152	7567	NA	0%	Re-Shores have been Removed/Dry Finish/ Prep Ceilings	3 days	Tue 1/11/22	Thu 1/13/22	1034,1067SS
2153	7568	NA	0%	Spray Concrete Ceiling Bonding Agent	2 days	Fri 1/21/22	Mon 1/24/22	2152,2146,2141
2154	<b>7731</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Tue 1/25/22</b>	<b>Mon 2/14/22</b>	
2155	7734	NA	0%	Layout Walls Install Top Tracks	5 days	Tue 1/25/22	Mon 1/31/22	2153
2156	7735	NA	0%	Layout MEPS Wall/Ceiling/Acess Panel Openings	5 days	Tue 1/25/22	Mon 1/31/22	2155FF
2157	7732	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Tue 2/1/22	Mon 2/7/22	2143,2155
2158	9802	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Tue 2/8/22	Tue 2/8/22	2157
2159	9801	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Tue 2/8/22	Tue 2/8/22	2158FF
2160	9803	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Tue 2/8/22	Tue 2/8/22	2159FF,2158FF
2161	7733	NA	0%	Fire Sprinkler Distribution	5 days	Tue 2/8/22	Mon 2/14/22	2157
2162	7569	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Tue 2/8/22	Mon 2/14/22	2153,2161SS
2163	<b>7737</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Tue 2/1/22</b>	<b>Mon 2/21/22</b>	
2164	7736	NA	0%	Layout Walls Install Top Tracks	5 days	Tue 2/1/22	Mon 2/7/22	2155
2165	7570	NA	0%	Layout MEPS Wall/Ceiling/Acess Panel Openings	5 days	Tue 2/1/22	Mon 2/7/22	2164FF
2166	7571	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Tue 2/8/22	Mon 2/14/22	2148,2164
2167	9806	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Tue 2/15/22	Tue 2/15/22	2166
2168	9807	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Tue 2/15/22	Tue 2/15/22	2167FF
2169	9808	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Tue 2/15/22	Tue 2/15/22	2167FF,2168FF
2170	7718	NA	0%	Fire Sprinkler Distribution	5 days	Tue 2/15/22	Mon 2/21/22	2166
2171	7716	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Tue 2/15/22	Mon 2/21/22	2162,2155,2170SS
2172	<b>2419</b>	<b>NA</b>	<b>0%</b>	<b>Rough-In</b>	<b>39 days</b>	<b>Mon 2/14/22</b>	<b>Mon 4/11/22</b>	
2173	2420	NA	0%	L3 Window Walls/Precast Panels Complete	0 days	Mon 2/14/22	Mon 2/14/22	3475FF
2174	9804	NA	0%	Insulate Shafts with Moisture Barrier Insulation	2 days	Wed 2/16/22	Fri 2/18/22	2160,2175SF-1 day,2169
2175	2421	NA	0%	Party & Corridor Walls L3	10 days	Tue 2/22/22	Mon 3/7/22	2173,2152,2153,2164,2165,21
2176	2422	NA	0%	Top Down & Tub Walls	5 days	Tue 3/1/22	Mon 3/7/22	2175FF
2177	2423	NA	0%	Install Tubs & Fill Test	10 days	Fri 3/4/22	Thu 3/17/22	2176FS-2 days
2178	2424	NA	0%	HVAC Rigid Distribution @ Corridors/Kitchens/Soffits	10 days	Thu 3/3/22	Thu 3/17/22	2176FS-2 days
2179	2425	NA	0%	Frame Ceilings	10 days	Tue 3/15/22	Tue 3/29/22	2176,2177FS-2 days,2178FS-2
2180	2426	NA	0%	Rough-In MEPS/DAS, Walls,CEILINGS (COMPLETE ELECTRICAL PANELS & B	10 days	Fri 3/25/22	Fri 4/8/22	2179FS-2 days
2181	2427	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Mon 4/11/22	Mon 4/11/22	2180
2182	2428	NA	0%	Build Group Quality Control Inspection (Consultant's/Client/Arch if Required) Subcontractor's Distributes One Collilated Complete List To	1 day	Tue 4/5/22	Wed 4/6/22	2180FS-3 days
2183	2429	NA	0%	Subcontractors Complete Build Group's Quality Control Inspection	1 day	Thu 4/7/22	Thu 4/7/22	2182
2184	2430	NA	0%	Build Group Back-Check Subcontractors Completion	1 day	Thu 4/7/22	Fri 4/8/22	2183
2185	<b>2431</b>	<b>NA</b>	<b>0%</b>	<b>Rock and Tape</b>	<b>33 days</b>	<b>Fri 4/8/22</b>	<b>Tue 5/24/22</b>	
2186	2432	NA	0%	Insulate Walls	5 days	Mon 4/11/22	Fri 4/15/22	2181SF,2184
2187	2433	NA	0%	Drywall Delivery After MEPS Rough IN	1 day	Fri 4/8/22	Fri 4/8/22	2180FF
2188	2434	NA	0%	Door Frames	5 days	Mon 4/11/22	Fri 4/15/22	2180FF,2187
2189	2435	NA	0%	Hang Drywall L3 (AFTER L4 INSPECTIONS)	10 days	Wed 4/27/22	Tue 5/10/22	2184,2188,2181,2264FS+1 day
2190	2436	NA	0%	Tape & Drywall Touch Up (Walls/Ceilings & Corridors)	10 days	Wed 5/11/22	Tue 5/24/22	2189
2191	<b>2437</b>	<b>NA</b>	<b>0%</b>	<b>Finishes</b>	<b>65 days</b>	<b>Tue 5/24/22</b>	<b>Wed 8/24/22</b>	
2192	2438	NA	0%	Prime Paint/1ST COAT PAINT	10 days	Tue 5/24/22	Tue 6/7/22	2190FS-1 day

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2193	2439	NA	0%	Install Interior Door Frames	10 days	Tue 6/7/22	Mon 6/20/22	2192FS-1 day
2194	2440	NA	0%	Install Unit Entry Doors/Hardware	10 days	Tue 6/7/22	Mon 6/20/22	2193SS
2195	2441	NA	0%	Install WP Redgard at Tube/Shower Walls & Floors	5 days	Wed 6/8/22	Tue 6/14/22	2192
2196	2442	NA	0%	Flood Test Shower Pans	2 days	Wed 6/15/22	Thu 6/16/22	2195
2197	2443	NA	0%	Install Cabinets/Trim/Linen Closets	10 days	Fri 6/17/22	Thu 6/30/22	2193FS-2 days
2198	2444	NA	0%	Install Kitchen Stone Countertops	10 days	Thu 6/30/22	Thu 7/14/22	2197FS-1 day
2199	2445	NA	0%	Install Stone Backsplash at Kitchen Counters	10 days	Thu 6/30/22	Thu 7/14/22	2198FF
2200	2446	NA	0%	Install Tile/Vinyl flooring/Base	10 days	Thu 6/30/22	Thu 7/14/22	2196,2197
2201	2447	NA	0%	Install Stone Entry Threshold & Protection	10 days	Thu 6/30/22	Thu 7/14/22	2198FF,2199FF
2202	2448	NA	0%	Install Vanities/Medicine Cabinets	5 days	Tue 7/12/22	Tue 7/19/22	2200FS-2 days
2203	2449	NA	0%	Install Vanity Countertops	5 days	Fri 7/15/22	Fri 7/22/22	2202FS-2 days
2204	2450	NA	0%	Install Unit Flooring & Base	10 days	Tue 7/19/22	Tue 8/2/22	2201,2202
2205	2451	NA	0%	Install Window Blinds	10 days	Tue 8/2/22	Tue 8/16/22	2204
2206	2452	NA	0%	Appliances/Dish-Washer/Refrigerator/Microwave	5 days	Tue 8/2/22	Tue 8/9/22	2204
2207	2456	NA	0%	Install Bathroom Accessories/Mirrors/Tube/Shower Enclosures/Closet Lin	10 days	Tue 8/2/22	Tue 8/16/22	2204,2200
2208	2455	NA	0%	Install MEPS Trim	10 days	Tue 8/9/22	Tue 8/23/22	2203,2206
2209	2457	NA	0%	Tube Mending	1 day	Tue 8/16/22	Wed 8/17/22	2207
2210	2458	NA	0%	LOCK DOORS	0 days	Wed 8/24/22	Wed 8/24/22	2208FS+1 day
2211	<b>5822</b>	<b>NA</b>	<b>0%</b>	<b>PUNCH/CLEANING &amp; UNIT ACCEPTANCE</b>	<b>21 days</b>	<b>Wed 8/24/22</b>	<b>Thu 9/22/22</b>	
2212	2459	NA	0%	BG Pre-Punch List	0 days	Wed 8/24/22	Wed 8/24/22	2207,2209FF,2210SS
2213	2460	NA	0%	Subcontractor Complete Pre-Punch List L3	2 days	Thu 8/25/22	Fri 8/26/22	2212
2214	2461	NA	0%	Rough Cleaning	2 days	Fri 8/26/22	Tue 8/30/22	2213
2215	2462	NA	0%	Owners Punch LEVEL 3	1 day	Tue 8/30/22	Wed 8/31/22	2214
2216	2463	NA	0%	Subcontractor Complete Owner Punch	2 days	Wed 8/31/22	Fri 9/2/22	2215
2217	2464	NA	0%	Paint 2nd Coat Finish	10 days	Fri 9/2/22	Fri 9/16/22	2216
2218	2465	NA	0%	Final Cleaning	3 days	Fri 9/16/22	Wed 9/21/22	2217
2219	2466	NA	0%	Unit Acceptance L3	1 day	Wed 9/21/22	Thu 9/22/22	2218
2220	<b>3106</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 4</b>	<b>190 days</b>	<b>Fri 1/7/22</b>	<b>Thu 10/6/22</b>	
2221	<b>7741</b>	<b>NA</b>	<b>0%</b>	<b>MEPS VERTICAL</b>	<b>24 days</b>	<b>Fri 1/7/22</b>	<b>Wed 2/9/22</b>	
2222	7742	NA	0%	PROSHORE SHORING L7	0 days	Fri 1/7/22	Fri 1/7/22	1067SS
2223	7743	NA	0%	Fire Sprinkler Risers	10 days	Thu 1/27/22	Wed 2/9/22	2222,2140,2087
2224	<b>7744</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Fri 1/7/22</b>	<b>Thu 1/27/22</b>	
2225	7745	NA	0%	Storm/Waste/Vent	5 days	Fri 1/7/22	Thu 1/13/22	2222,2147
2226	7748	NA	0%	Duct Riser	5 days	Fri 1/14/22	Thu 1/20/22	2148,2225
2227	7746	NA	0%	Water/Gas/Fuel	5 days	Fri 1/21/22	Thu 1/27/22	2149
2228	7747	NA	0%	Heat Pump Risers	5 days	Fri 1/21/22	Thu 1/27/22	2150
2229	<b>7749</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Fri 1/14/22</b>	<b>Thu 2/3/22</b>	
2230	7750	NA	0%	Storm/Waste/Vent	5 days	Fri 1/14/22	Thu 1/20/22	2225
2231	7753	NA	0%	Duct Riser	5 days	Fri 1/21/22	Thu 1/27/22	2226,2230
2232	7751	NA	0%	Water/Gas/Fuel	5 days	Fri 1/28/22	Thu 2/3/22	2227
2233	7752	NA	0%	Heat Pump Risers	5 days	Fri 1/28/22	Thu 2/3/22	2228
2234	<b>7798</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT/SPRINKLERS-ELECTRICAL DISTRIBUTION/SHAFTS</b>	<b>29.88 days</b>	<b>Tue 1/25/22</b>	<b>Mon 3/7/22</b>	
2235	7754	NA	0%	Re-Shores have been Removed/Dry Finish/ Prep Ceilings	3 days	Tue 1/25/22	Fri 1/28/22	1077,1110
2236	7755	NA	0%	Spray Concrete Ceiling Bonding Agent	2 days	Fri 2/4/22	Mon 2/7/22	2224,2229,2235
2237	<b>7756</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Tue 2/8/22</b>	<b>Mon 2/28/22</b>	
2238	7757	NA	0%	Layout Walls Install Top Tracks	5 days	Tue 2/8/22	Mon 2/14/22	2236
2239	7758	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Tue 2/8/22	Mon 2/14/22	2238FF

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2240	7760	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Tue 2/15/22	Mon 2/21/22	2226,2238
2241	9810	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Tue 2/22/22	Tue 2/22/22	2240
2242	9811	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Tue 2/22/22	Tue 2/22/22	2241FF
2243	9812	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Tue 2/22/22	Tue 2/22/22	2241FF,2242FF
2244	7759	NA	0%	Fire Sprinkler Distribution	5 days	Tue 2/22/22	Mon 2/28/22	2239,2240
2245	7761	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Tue 2/22/22	Mon 2/28/22	2236,2244FF
2246	<b>7762</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Tue 2/15/22</b>	<b>Mon 3/7/22</b>	
2247	7763	NA	0%	Layout Walls Install Top Tracks	5 days	Tue 2/15/22	Mon 2/21/22	2238
2248	7764	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Tue 2/15/22	Mon 2/21/22	2247FF
2249	7766	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Tue 2/22/22	Mon 2/28/22	2231,2247,2248
2250	9815	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Tue 3/1/22	Tue 3/1/22	2249
2251	9816	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Tue 3/1/22	Tue 3/1/22	2250FF
2252	9817	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Tue 3/1/22	Tue 3/1/22	2250FF,2251FF
2253	7765	NA	0%	Fire Sprinkler Distribution	5 days	Tue 3/1/22	Mon 3/7/22	2249
2254	7767	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Tue 3/1/22	Mon 3/7/22	2238,2245,2253SS
2255	<b>4648</b>	<b>NA</b>	<b>0%</b>	<b>Rough-In</b>	<b>39 days</b>	<b>Tue 3/1/22</b>	<b>Mon 4/25/22</b>	
2256	4649	NA	0%	L4 Window Walls/Precast Panels Complete	0 days	Tue 3/1/22	Tue 3/1/22	3481FF
2257	9818	NA	0%	Insulate Shafts with Moisture Barrier Insulation	2 days	Thu 3/3/22	Mon 3/7/22	2252,2243,2258SF-1 day
2258	4650	NA	0%	Party & Corridor Walls L4	10 days	Tue 3/8/22	Mon 3/21/22	2256,2175,2240,2238,2247,22
2259	4651	NA	0%	Top Down & Tub Walls	5 days	Tue 3/15/22	Mon 3/21/22	2258FF
2260	4652	NA	0%	Install Tubs & Fill Test	10 days	Fri 3/18/22	Thu 3/31/22	2259FS-2 days
2261	4653	NA	0%	HVAC Rigid Distribution @ Corridors/Kitchens/Soffits	10 days	Thu 3/17/22	Thu 3/31/22	2259FS-2 days
2262	4654	NA	0%	Frame Ceilings	10 days	Tue 3/29/22	Tue 4/12/22	2259,2260FS-2 days,2261FS-2
2263	4655	NA	0%	Rough-In MEPS/DAS, Walls,CEILINGS (COMPLETE ELECTRICAL PANELS & B	10 days	Fri 4/8/22	Fri 4/22/22	2262FS-2 days
2264	4656	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS) L4	1 day	Mon 4/25/22	Mon 4/25/22	2263
2265	4657	NA	0%	Build Group Quality Control Inspection (Consultant's/Client/Arch if Required) Subcontractor's Distributes One Collilated Complete List To	1 day	Tue 4/19/22	Wed 4/20/22	2263FS-3 days
2266	4658	NA	0%	Subcontractors Complete Build Group's Quality Control Inspection	1 day	Thu 4/21/22	Thu 4/21/22	2265
2267	4659	NA	0%	Build Group Back-Check Subcontractors Completion	1 day	Thu 4/21/22	Fri 4/22/22	2266
2268	<b>4660</b>	<b>NA</b>	<b>0%</b>	<b>Rock and Tape</b>	<b>33 days</b>	<b>Fri 4/22/22</b>	<b>Wed 6/8/22</b>	
2269	4661	NA	0%	Insulate Walls	5 days	Mon 4/25/22	Fri 4/29/22	2264SF,2267
2270	4662	NA	0%	Drywall Delivery After MEPS Rough IN	1 day	Fri 4/22/22	Fri 4/22/22	2263FF
2271	4663	NA	0%	Door Frames	5 days	Mon 4/25/22	Fri 4/29/22	2263FF,2270
2272	4664	NA	0%	Hang Drywall L4	10 days	Wed 5/11/22	Tue 5/24/22	2264,2267,2271,2189
2273	4665	NA	0%	Tape & Drywall Touch Up (Walls/Ceilings & Corridors)	10 days	Wed 5/25/22	Wed 6/8/22	2272
2274	<b>4666</b>	<b>NA</b>	<b>0%</b>	<b>Finishes</b>	<b>65 days</b>	<b>Wed 6/8/22</b>	<b>Thu 9/8/22</b>	
2275	4667	NA	0%	Prime Paint/1ST COAT PAINT	10 days	Wed 6/8/22	Tue 6/21/22	2273FS-1 day
2276	4668	NA	0%	Install Interior Door Frames	10 days	Tue 6/21/22	Tue 7/5/22	2275FS-1 day
2277	4669	NA	0%	Install Unit Entry Doors/Hardware	10 days	Tue 6/21/22	Tue 7/5/22	2276SS
2278	4670	NA	0%	Install WP Redgard at Tube/Shower Walls & Floors	5 days	Wed 6/22/22	Tue 6/28/22	2275
2279	4671	NA	0%	Flood Test Shower Pans	2 days	Wed 6/29/22	Thu 6/30/22	2278
2280	4672	NA	0%	Install Cabinets/Trim/Linen Closets	10 days	Fri 7/1/22	Fri 7/15/22	2276FS-2 days
2281	4673	NA	0%	Install Kitchen Stone Countertops	10 days	Fri 7/15/22	Thu 7/28/22	2280FS-1 day
2282	4674	NA	0%	Install Stone Backsplash at Kitchen Counters	10 days	Fri 7/15/22	Thu 7/28/22	2281FF
2283	4675	NA	0%	Install Tile/Vinyl flooring/Base	10 days	Fri 7/15/22	Fri 7/29/22	2279,2280
2284	4676	NA	0%	Install Stone Entry Threshold & Protection	10 days	Thu 7/14/22	Thu 7/28/22	2281FF,2282FF
2285	4677	NA	0%	Install Vanities/Medicine Cabinets	5 days	Wed 7/27/22	Wed 8/3/22	2283FS-2 days

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2286	4678	NA	0%	Install Vanity Countertops	5 days	Mon 8/1/22	Mon 8/8/22	2285FS-2 days
2287	4679	NA	0%	Install Unit Flooring & Base	10 days	Wed 8/3/22	Wed 8/17/22	2284,2285
2288	4680	NA	0%	Install Window Blinds	10 days	Wed 8/17/22	Wed 8/31/22	2287
2289	4681	NA	0%	Appliances/Dish-Washer/Refrigerator/Microwave	5 days	Wed 8/17/22	Wed 8/24/22	2287
2290	4684	NA	0%	Install Bathroom Accessories/Mirrors/Tube/Shower Enclosures/Closet	10 days	Wed 8/17/22	Wed 8/31/22	2283,2287
2291	4685	NA	0%	Install MEPS Trim	10 days	Wed 8/24/22	Wed 9/7/22	2286,2289,2208
2292	4686	NA	0%	Tube Mending	1 day	Wed 8/31/22	Thu 9/1/22	2290
2293	4687	NA	0%	LOCK DOORS	1 day	Thu 9/8/22	Thu 9/8/22	2291
2294	<b>5824</b>	<b>NA</b>	<b>0%</b>	<b>PUNCH/CLEANING &amp; UNIT ACCEPTANCE</b>	<b>21 days</b>	<b>Thu 9/8/22</b>	<b>Thu 10/6/22</b>	
2295	4688	NA	0%	BG Pre-Punch List	0 days	Thu 9/8/22	Thu 9/8/22	2290,2292FF,2293SS
2296	4689	NA	0%	Subcontractor Complete Pre-Punch List L4	2 days	Thu 9/8/22	Fri 9/9/22	2295
2297	4690	NA	0%	Rough Cleaning	2 days	Mon 9/12/22	Tue 9/13/22	2296
2298	4691	NA	0%	Owners Punch	1 day	Wed 9/14/22	Wed 9/14/22	2297
2299	4692	NA	0%	Subcontractor Complete Owner Punch	2 days	Thu 9/15/22	Fri 9/16/22	2298
2300	4693	NA	0%	Paint 2nd Coat Finish	10 days	Mon 9/19/22	Fri 9/30/22	2299
2301	4694	NA	0%	Final Cleaning	3 days	Mon 10/3/22	Wed 10/5/22	2300
2302	4695	NA	0%	Unit Acceptance L4	1 day	Thu 10/6/22	Thu 10/6/22	2301
2303	<b>3205</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 5</b>	<b>190.88 days</b>	<b>Thu 1/20/22</b>	<b>Thu 10/20/22</b>	
2304	<b>7770</b>	<b>NA</b>	<b>0%</b>	<b>MEPS VERTICAL</b>	<b>24.88 days</b>	<b>Thu 1/20/22</b>	<b>Wed 2/23/22</b>	
2305	7771	NA	0%	PROSHORE SHORING L 8	0 days	Thu 1/20/22	Thu 1/20/22	1110SS
2306	7772	NA	0%	Fire Sprinkler Risers	10 days	Thu 2/10/22	Wed 2/23/22	2305,2223
2307	<b>7773</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Tue 1/25/22</b>	<b>Mon 2/14/22</b>	
2308	7774	NA	0%	Storm/Waste/Vent	5 days	Tue 1/25/22	Mon 1/31/22	2305,2153,2230
2309	7777	NA	0%	Duct Riser	5 days	Tue 2/1/22	Mon 2/7/22	2308,2231
2310	7775	NA	0%	Water/Gas/Fuel	5 days	Tue 2/8/22	Mon 2/14/22	2232,2309
2311	7776	NA	0%	Heat Pump Risers	5 days	Tue 2/8/22	Mon 2/14/22	2233,2309
2312	<b>7778</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Tue 2/1/22</b>	<b>Mon 2/21/22</b>	
2313	7779	NA	0%	Storm/Waste/Vent	5 days	Tue 2/1/22	Mon 2/7/22	2308
2314	7782	NA	0%	Duct Riser	5 days	Tue 2/8/22	Mon 2/14/22	2309,2313
2315	7780	NA	0%	Water/Gas/Fuel	5 days	Tue 2/15/22	Mon 2/21/22	2310
2316	7781	NA	0%	Heat Pump Risers	5 days	Tue 2/15/22	Mon 2/21/22	2311
2317	<b>7799</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT/SPRINKLERS-ELECTRICAL DISTRIBUTION/SHAFTS</b>	<b>32.88 days</b>	<b>Mon 2/7/22</b>	<b>Wed 3/23/22</b>	
2318	7783	NA	0%	Re-Shores have been Removed/Dry Finish/ Prep Ceilings	3 days	Mon 2/7/22	Thu 2/10/22	1154,1120
2319	7784	NA	0%	Spray Concrete Ceiling Bonding Agent	2 days	Tue 2/22/22	Wed 2/23/22	2307,2312,2318
2320	<b>7785</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Thu 2/24/22</b>	<b>Wed 3/16/22</b>	
2321	7786	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 2/24/22	Wed 3/2/22	2319
2322	7787	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Thu 2/24/22	Wed 3/2/22	2321FF
2323	7789	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 3/3/22	Wed 3/9/22	2309,2321
2324	9820	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 3/10/22	Thu 3/10/22	2323
2325	9821	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 3/10/22	Thu 3/10/22	2324FF
2326	9822	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 3/10/22	Thu 3/10/22	2324FF,2325FF
2327	7788	NA	0%	Fire Sprinkler Distribution	5 days	Thu 3/10/22	Wed 3/16/22	2323
2328	7790	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 3/10/22	Wed 3/16/22	2319,2327SS
2329	<b>7791</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Thu 3/3/22</b>	<b>Wed 3/23/22</b>	
2330	7792	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 3/3/22	Wed 3/9/22	2321
2331	7793	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Thu 3/3/22	Wed 3/9/22	2330FF
2332	7795	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 3/10/22	Wed 3/16/22	2314,2330

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2333	9824	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 3/17/22	Thu 3/17/22	2332
2334	9825	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 3/17/22	Thu 3/17/22	2333FF
2335	9826	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 3/17/22	Thu 3/17/22	2333FF,2334FF
2336	7794	NA	0%	Fire Sprinkler Distribution	5 days	Thu 3/17/22	Wed 3/23/22	2332
2337	7796	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 3/17/22	Wed 3/23/22	2321,2336SS
2338	<b>4843</b>	<b>NA</b>	<b>0%</b>	<b>Rough-In</b>	<b>41 days</b>	<b>Tue 3/15/22</b>	<b>Wed 5/11/22</b>	
2339	4844	NA	0%	L5 Window Walls/Precast Panels Complete	0 days	Tue 3/15/22	Tue 3/15/22	3487
2340	9827	NA	0%	Insulate Shafts with Moisture Barrier Insulation	2 days	Mon 3/21/22	Wed 3/23/22	2341SF-1 day,2326,2335
2341	4845	NA	0%	Party & Corridor Walls L5	10 days	Thu 3/24/22	Wed 4/6/22	2339,2258,2321,2322,2330,2331
2342	4846	NA	0%	Top Down & Tub Walls	5 days	Thu 3/31/22	Wed 4/6/22	2341FF
2343	4847	NA	0%	Install Tubs & Fill Test	10 days	Tue 4/5/22	Mon 4/18/22	2342FS-2 days
2344	4848	NA	0%	HVAC Rigid Distribution @ Corridors/Kitchens/Soffits	10 days	Mon 4/4/22	Mon 4/18/22	2342FS-2 days
2345	4849	NA	0%	Frame Ceilings	10 days	Thu 4/14/22	Thu 4/28/22	2342,2343FS-2 days,2344FS-2
2346	4850	NA	0%	Rough-In MEPS/DAS, Walls,CEILINGS (COMPLETE ELECTRICAL PANELS & BUS)	10 days	Tue 4/26/22	Tue 5/10/22	2345FS-2 days
2347	4851	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS) L5	1 day	Wed 5/11/22	Wed 5/11/22	2346
2348	4852	NA	0%	Build Group Quality Control Inspection (Consultant's/Client/Arch if Required) Subcontractor's Distributes One Collilated Complete List To	1 day	Thu 5/5/22	Fri 5/6/22	2346FS-3 days
2349	4853	NA	0%	Subcontractors Complete Build Group's Quality Control Inspection	1 day	Mon 5/9/22	Mon 5/9/22	2348
2350	4854	NA	0%	Build Group Back-Check Subcontractors Completion	1 day	Mon 5/9/22	Tue 5/10/22	2349
2351	<b>4855</b>	<b>NA</b>	<b>0%</b>	<b>Rock and Tape</b>	<b>31 days</b>	<b>Tue 5/10/22</b>	<b>Wed 6/22/22</b>	
2352	4856	NA	0%	Insulate Walls	5 days	Wed 5/11/22	Tue 5/17/22	2347SF,2350
2353	4857	NA	0%	Drywall Delivery After MEPS Rough IN	1 day	Tue 5/10/22	Tue 5/10/22	2346FF
2354	4858	NA	0%	Door Frames	5 days	Wed 5/11/22	Tue 5/17/22	2346FF,2353
2355	4859	NA	0%	Hang Drywall L5	10 days	Wed 5/25/22	Wed 6/8/22	2347,2350,2354,2272
2356	4860	NA	0%	Tape & Drywall Touch Up (Walls/Ceilings & Corridors)	10 days	Thu 6/9/22	Wed 6/22/22	2355
2357	<b>4861</b>	<b>NA</b>	<b>0%</b>	<b>Finishes</b>	<b>65 days</b>	<b>Wed 6/22/22</b>	<b>Thu 9/22/22</b>	
2358	4862	NA	0%	Prime Paint/1ST COAT PAINT	10 days	Wed 6/22/22	Wed 7/6/22	2356FS-1 day
2359	4863	NA	0%	Install Interior Door Frames	10 days	Wed 7/6/22	Tue 7/19/22	2358FS-1 day
2360	4864	NA	0%	Install Unit Entry Doors/Hardware	10 days	Wed 7/6/22	Tue 7/19/22	2359SS
2361	4865	NA	0%	Install WP Redgard at Tube/Shower Walls & Floors	5 days	Thu 7/7/22	Wed 7/13/22	2358
2362	4866	NA	0%	Flood Test Shower Pans	2 days	Thu 7/14/22	Fri 7/15/22	2361
2363	4867	NA	0%	Install Cabinets/Trim/Linen Closets	10 days	Mon 7/18/22	Fri 7/29/22	2359FS-2 days
2364	4868	NA	0%	Install Kitchen Stone Countertops	10 days	Fri 7/29/22	Thu 8/11/22	2363FS-1 day
2365	4869	NA	0%	Install Stone Backsplash at Kitchen Counters	10 days	Fri 7/29/22	Thu 8/11/22	2364FF
2366	4870	NA	0%	Install Tile/Vinyl flooring/Base	10 days	Fri 7/29/22	Fri 8/12/22	2362,2363
2367	4871	NA	0%	Install Stone Entry Threshold & Protection	10 days	Thu 7/28/22	Thu 8/11/22	2364FF,2365FF
2368	4872	NA	0%	Install Vanities/Medicine Cabinets	5 days	Wed 8/10/22	Wed 8/17/22	2366FS-2 days
2369	4873	NA	0%	Install Vanity Countertops	5 days	Mon 8/15/22	Mon 8/22/22	2368FS-2 days
2370	4874	NA	0%	Install Unit Flooring & Base	10 days	Wed 8/17/22	Wed 8/31/22	2367,2368
2371	4875	NA	0%	Install Window Blinds	10 days	Wed 8/31/22	Wed 9/14/22	2370
2372	4876	NA	0%	Appliances/Dish-Washer/Refrigerator/Microwave	5 days	Wed 8/31/22	Wed 9/7/22	2370
2373	4879	NA	0%	Install Bathroom Accessories/Mirrors/Tube/Shower Enclosures/Closet Liner	10 days	Wed 8/31/22	Wed 9/14/22	2366,2370
2374	4880	NA	0%	Install MEPS Trim	10 days	Wed 9/7/22	Wed 9/21/22	2369,2372,2291
2375	4881	NA	0%	Tube Mending	1 day	Wed 9/14/22	Thu 9/15/22	2373
2376	4882	NA	0%	LOCK DOORS	1 day	Thu 9/22/22	Thu 9/22/22	2374
2377	<b>5826</b>	<b>NA</b>	<b>0%</b>	<b>PUNCH/CLEANING &amp; UNIT ACCEPTANCE</b>	<b>21 days</b>	<b>Thu 9/22/22</b>	<b>Thu 10/20/22</b>	
2378	4883	NA	0%	BG Pre-Punch List	0 days	Thu 9/22/22	Thu 9/22/22	2373,2375FF,2376SS

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2379	4884	NA	0%	Subcontractor Complete Pre-Punch List L5	2 days	Thu 9/22/22	Fri 9/23/22	2378
2380	4885	NA	0%	Rough Cleaning	2 days	Mon 9/26/22	Tue 9/27/22	2379
2381	4886	NA	0%	Owners Punch	1 day	Wed 9/28/22	Wed 9/28/22	2380
2382	4887	NA	0%	Subcontractor Complete Owner Punch	2 days	Thu 9/29/22	Fri 9/30/22	2381
2383	4888	NA	0%	Paint 2nd Coat Finish	10 days	Mon 10/3/22	Fri 10/14/22	2382
2384	4889	NA	0%	Final Cleaning	3 days	Mon 10/17/22	Wed 10/19/22	2383
2385	4890	NA	0%	Unit Acceptance L5	1 day	Thu 10/20/22	Thu 10/20/22	2384
2386	<b>3304</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 6</b>	<b>193.88 days</b>	<b>Mon 1/31/22</b>	<b>Thu 11/3/22</b>	
2387	<b>7802</b>	<b>NA</b>	<b>0%</b>	<b>MEPS VERTICAL</b>	<b>27.88 days</b>	<b>Mon 1/31/22</b>	<b>Wed 3/9/22</b>	
2388	7803	NA	0%	PROSHORE SHORING L 9	0 days	Mon 1/31/22	Mon 1/31/22	1154SS
2389	7804	NA	0%	Fire Sprinkler Risers	10 days	Thu 2/24/22	Wed 3/9/22	2388,2306
2390	<b>7805</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Tue 2/8/22</b>	<b>Mon 2/28/22</b>	
2391	7806	NA	0%	Storm/Waste/Vent	5 days	Tue 2/8/22	Mon 2/14/22	2388,2313
2392	7809	NA	0%	Duct Riser	5 days	Tue 2/15/22	Mon 2/21/22	2391,2314
2393	7807	NA	0%	Water/Gas/Fuel	5 days	Tue 2/22/22	Mon 2/28/22	2315
2394	7808	NA	0%	Heat Pump Risers	5 days	Tue 2/22/22	Mon 2/28/22	2316
2395	<b>7810</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Tue 2/15/22</b>	<b>Mon 3/7/22</b>	
2396	7811	NA	0%	Storm/Waste/Vent	5 days	Tue 2/15/22	Mon 2/21/22	2391
2397	7814	NA	0%	Duct Riser	5 days	Tue 2/22/22	Mon 2/28/22	2392,2396
2398	7812	NA	0%	Water/Gas/Fuel	5 days	Tue 3/1/22	Mon 3/7/22	2393,2397
2399	7813	NA	0%	Heat Pump Risers	5 days	Tue 3/1/22	Mon 3/7/22	2394
2400	<b>7815</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT/SPRINKLERS-ELECTRICAL DISTRIBUTION/SHAFTS</b>	<b>32.88 days</b>	<b>Mon 2/21/22</b>	<b>Wed 4/6/22</b>	
2401	7816	NA	0%	Re-Shores have been Removed/Dry Finish/ Prep Ceilings	3 days	Mon 2/21/22	Thu 2/24/22	1198,1164
2402	7817	NA	0%	Spray Concrete Ceiling Bonding Agent	2 days	Tue 3/8/22	Wed 3/9/22	2390,2395,2401
2403	<b>7818</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Thu 3/10/22</b>	<b>Wed 3/30/22</b>	
2404	7819	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 3/10/22	Wed 3/16/22	2402
2405	7820	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Thu 3/10/22	Wed 3/16/22	2404FF
2406	7822	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 3/17/22	Wed 3/23/22	2392,2404
2407	9829	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 3/24/22	Thu 3/24/22	2406
2408	9830	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 3/24/22	Thu 3/24/22	2407FF
2409	9831	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 3/24/22	Thu 3/24/22	2407FF,2408FF
2410	7821	NA	0%	Fire Sprinkler Distribution	5 days	Thu 3/24/22	Wed 3/30/22	2406
2411	7823	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 3/24/22	Wed 3/30/22	2402,2410SS
2412	<b>7824</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Thu 3/17/22</b>	<b>Wed 4/6/22</b>	
2413	7825	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 3/17/22	Wed 3/23/22	2404
2414	7826	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Thu 3/17/22	Wed 3/23/22	2413FF
2415	7828	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 3/24/22	Wed 3/30/22	2397,2413
2416	9833	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 3/31/22	Thu 3/31/22	2415
2417	9834	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 3/31/22	Thu 3/31/22	2416FF
2418	9835	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 3/31/22	Thu 3/31/22	2416FF,2417FF
2419	7827	NA	0%	Fire Sprinkler Distribution	5 days	Thu 3/31/22	Wed 4/6/22	2415
2420	7829	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 3/31/22	Wed 4/6/22	2404,2419SS
2421	<b>4941</b>	<b>NA</b>	<b>0%</b>	<b>Rough-In</b>	<b>41 days</b>	<b>Tue 3/29/22</b>	<b>Wed 5/25/22</b>	
2422	4942	NA	0%	L6 Window Walls/Precast Panels Complete	0 days	Tue 3/29/22	Tue 3/29/22	3493
2423	9836	NA	0%	Insulate Shafts with Moisture Barrier Insulation	2 days	Mon 4/4/22	Wed 4/6/22	2424SF-1 day,2409,2418
2424	4943	NA	0%	Party & Corridor Walls L6	10 days	Thu 4/7/22	Wed 4/20/22	2422,2341,2413,2414,2404,24
2425	4944	NA	0%	Top Down & Tub Walls	5 days	Thu 4/14/22	Wed 4/20/22	2424FF



University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2426	4945	NA	0%	Install Tubs & Fill Test	10 days	Tue 4/19/22	Mon 5/2/22	2425FS-2 days
2427	4946	NA	0%	HVAC Rigid Distribution @ Corridors/Kitchens/Soffits	10 days	Mon 4/18/22	Mon 5/2/22	2425FS-2 days
2428	4947	NA	0%	Frame Ceilings	10 days	Thu 4/28/22	Thu 5/12/22	2425,2426FS-2 days,2427FS-2
2429	4948	NA	0%	Rough-In MEPS/DAS, Walls,CEILING (COMPLETE ELECTRICAL PANELS & B	10 days	Tue 5/10/22	Tue 5/24/22	2428FS-2 days
2430	4949	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS) L6	1 day	Wed 5/25/22	Wed 5/25/22	2429
2431	4950	NA	0%	Build Group Quality Control Inspection (Consultant's/Client/Arch if Required) Subcontractor's Distributes One Collilated Complete List To	1 day	Thu 5/19/22	Fri 5/20/22	2429FS-3 days
2432	4951	NA	0%	Subcontractors Complete Build Group's Quality Control Inspection	1 day	Mon 5/23/22	Mon 5/23/22	2431
2433	4952	NA	0%	Build Group Back-Check Subcontractors Completion	1 day	Mon 5/23/22	Tue 5/24/22	2432
2434	<b>4953</b>	<b>NA</b>	<b>0%</b>	<b>Rock and Tape</b>	<b>29 days</b>	<b>Tue 5/24/22</b>	<b>Tue 7/5/22</b>	
2435	4954	NA	0%	Insulate Walls	5 days	Wed 5/25/22	Wed 6/1/22	2430SF,2433
2436	4955	NA	0%	Drywall Delivery After MEPS Rough IN	1 day	Tue 5/24/22	Tue 5/24/22	2429FF
2437	4956	NA	0%	Door Frames	5 days	Wed 5/25/22	Wed 6/1/22	2429FF,2436
2438	4957	NA	0%	Hang Drywall L6	10 days	Thu 6/9/22	Wed 6/22/22	2430,2433,2437,2355
2439	4958	NA	0%	Tape & Drywall Touch Up (Walls/Ceilings & Corridors)	10 days	Tue 6/21/22	Tue 7/5/22	2438FS-2 days
2440	<b>4959</b>	<b>NA</b>	<b>0%</b>	<b>Finishes</b>	<b>66 days</b>	<b>Wed 7/6/22</b>	<b>Thu 10/6/22</b>	
2441	4960	NA	0%	Prime Paint/1ST COAT PAINT	10 days	Wed 7/6/22	Tue 7/19/22	2439FS-1 day,2358FS-1 day
2442	4961	NA	0%	Install Interior Door Frames	10 days	Tue 7/19/22	Mon 8/1/22	2441FS-1 day
2443	4962	NA	0%	Install Unit Entry Doors/Hardware	10 days	Tue 7/19/22	Mon 8/1/22	2442SS
2444	4963	NA	0%	Install WP Redgard at Tube/Shower Walls & Floors	5 days	Wed 7/20/22	Tue 7/26/22	2441
2445	4964	NA	0%	Flood Test Shower Pans	2 days	Wed 7/27/22	Thu 7/28/22	2444
2446	4965	NA	0%	Install Cabinets/Trim/Linen Closets	10 days	Fri 7/29/22	Thu 8/11/22	2442FS-2 days
2447	4966	NA	0%	Install Kitchen Stone Countertops	10 days	Thu 8/11/22	Wed 8/24/22	2446FS-1 day
2448	4967	NA	0%	Install Stone Backsplash at Kitchen Counters	10 days	Thu 8/11/22	Wed 8/24/22	2447FF
2449	4968	NA	0%	Install Tile/Vinyl flooring/Base	10 days	Thu 8/11/22	Thu 8/25/22	2445,2446
2450	4969	NA	0%	Install Stone Entry Threshold & Protection	10 days	Wed 8/10/22	Wed 8/24/22	2447FF,2448FF
2451	4970	NA	0%	Install Vanities/Medicine Cabinets	5 days	Tue 8/23/22	Tue 8/30/22	2449FS-2 days
2452	4971	NA	0%	Install Vanity Countertops	5 days	Fri 8/26/22	Fri 9/2/22	2451FS-2 days
2453	4972	NA	0%	Install Unit Flooring & Base	10 days	Tue 8/30/22	Tue 9/13/22	2450,2451
2454	4973	NA	0%	Install Window Blinds	10 days	Tue 9/13/22	Tue 9/27/22	2453
2455	4974	NA	0%	Appliances/Dish-Washer/Refrigerator/Microwave	5 days	Tue 9/13/22	Tue 9/20/22	2453
2456	4977	NA	0%	Install Bathroom Accessories/Mirrors/Tube/Shower Enclosures/Closet I	10 days	Tue 9/13/22	Tue 9/27/22	2449,2453
2457	4978	NA	0%	Install MEPS Trim	10 days	Wed 9/21/22	Wed 10/5/22	2452,2455,2374
2458	4979	NA	0%	Tube Mending	1 day	Tue 9/27/22	Wed 9/28/22	2456
2459	4980	NA	0%	LOCK DOORS	1 day	Thu 10/6/22	Thu 10/6/22	2457
2460	<b>5828</b>	<b>NA</b>	<b>0%</b>	<b>PUNCH/CLEANING &amp; UNIT ACCEPTANCE</b>	<b>21 days</b>	<b>Thu 10/6/22</b>	<b>Thu 11/3/22</b>	
2461	4981	NA	0%	BG Pre-Punch List	0 days	Thu 10/6/22	Thu 10/6/22	2456,2458FF,2459SS
2462	4982	NA	0%	Subcontractor Complete Pre-Punch List L6	2 days	Thu 10/6/22	Fri 10/7/22	2461
2463	4983	NA	0%	Rough Cleaning	2 days	Mon 10/10/22	Tue 10/11/22	2462
2464	4984	NA	0%	Owners Punch	1 day	Wed 10/12/22	Wed 10/12/22	2463
2465	4985	NA	0%	Subcontractor Complete Owner Punch	2 days	Thu 10/13/22	Fri 10/14/22	2464
2466	4986	NA	0%	Paint 2nd Coat Finish	10 days	Mon 10/17/22	Fri 10/28/22	2465
2467	4987	NA	0%	Final Cleaning	3 days	Mon 10/31/22	Wed 11/2/22	2466
2468	4988	NA	0%	Unit Acceptance L6	1 day	Thu 11/3/22	Thu 11/3/22	2467
2469	<b>3403</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 7</b>	<b>191.88 days</b>	<b>Tue 2/15/22</b>	<b>Thu 11/17/22</b>	
2470	<b>7832</b>	<b>NA</b>	<b>0%</b>	<b>MEPS VERTICAL</b>	<b>26.88 days</b>	<b>Tue 2/15/22</b>	<b>Wed 3/23/22</b>	
2471	7833	NA	0%	PROSHORE SHORING L 10	0 days	Tue 2/15/22	Tue 2/15/22	1198SS

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2472	7834	NA	0%	Fire Sprinkler Risers	10 days	Thu 3/10/22	Wed 3/23/22	2471,2389
2473	<b>7835</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Tue 2/22/22</b>	<b>Mon 3/14/22</b>	
2474	7836	NA	0%	Storm/Waste/Vent	5 days	Tue 2/22/22	Mon 2/28/22	2471,2396
2475	7839	NA	0%	Duct Riser	5 days	Tue 3/1/22	Mon 3/7/22	2397,2474
2476	7837	NA	0%	Water/Gas/Fuel	5 days	Tue 3/8/22	Mon 3/14/22	2398,2475
2477	7838	NA	0%	Heat Pump Risers	5 days	Tue 3/8/22	Mon 3/14/22	2399
2478	<b>7840</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Tue 3/1/22</b>	<b>Mon 3/21/22</b>	
2479	7841	NA	0%	Storm/Waste/Vent	5 days	Tue 3/1/22	Mon 3/7/22	2474
2480	7844	NA	0%	Duct Riser	5 days	Tue 3/8/22	Mon 3/14/22	2475,2479
2481	7842	NA	0%	Water/Gas/Fuel	5 days	Tue 3/15/22	Mon 3/21/22	2479,2476
2482	7843	NA	0%	Heat Pump Risers	5 days	Tue 3/15/22	Mon 3/21/22	2477,2479
2483	<b>7845</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT/SPRINKLERS-ELECTRICAL DISTRIBUTION/SHAFTS</b>	<b>34.88 days</b>	<b>Thu 3/3/22</b>	<b>Wed 4/20/22</b>	
2484	7846	NA	0%	Re-Shores have been Removed/Dry Finish/ Prep Ceilings	3 days	Thu 3/3/22	Tue 3/8/22	1242,1208
2485	7847	NA	0%	Spray Concrete Ceiling Bonding Agent	2 days	Tue 3/22/22	Wed 3/23/22	2473,2478,2484
2486	<b>7848</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Thu 3/24/22</b>	<b>Wed 4/13/22</b>	
2487	7849	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 3/24/22	Wed 3/30/22	2485
2488	7850	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Thu 3/24/22	Wed 3/30/22	2487FF
2489	7852	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 3/31/22	Wed 4/6/22	2475,2487
2490	9838	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 4/7/22	Thu 4/7/22	2489
2491	9839	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 4/7/22	Thu 4/7/22	2490FF
2492	9840	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 4/7/22	Thu 4/7/22	2490FF,2491FF
2493	7851	NA	0%	Fire Sprinkler Distribution	5 days	Thu 4/7/22	Wed 4/13/22	2489
2494	7853	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 4/7/22	Wed 4/13/22	2485,2493SS
2495	<b>7854</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Thu 3/31/22</b>	<b>Wed 4/20/22</b>	
2496	7855	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 3/31/22	Wed 4/6/22	2487
2497	7856	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Thu 3/31/22	Wed 4/6/22	2496FF
2498	7858	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 4/7/22	Wed 4/13/22	2480,2496,2497
2499	9842	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 4/14/22	Thu 4/14/22	2498
2500	9843	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 4/14/22	Thu 4/14/22	2499FF
2501	9844	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 4/14/22	Thu 4/14/22	2499FF,2500FF
2502	7857	NA	0%	Fire Sprinkler Distribution	5 days	Thu 4/14/22	Wed 4/20/22	2498
2503	7859	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 4/14/22	Wed 4/20/22	2487,2494,2502SS
2504	<b>5039</b>	<b>NA</b>	<b>0%</b>	<b>Rough-In</b>	<b>40 days</b>	<b>Tue 4/12/22</b>	<b>Wed 6/8/22</b>	
2505	5040	NA	0%	L7 Window Walls/Precast Panels Complete	0 days	Tue 4/12/22	Tue 4/12/22	3499
2506	9845	NA	0%	Insulate Shafts with Moisture Barrier Insulation	2 days	Mon 4/18/22	Wed 4/20/22	2507SF-1 day,2492,2501
2507	5041	NA	0%	Party & Corridor Walls L7	10 days	Thu 4/21/22	Wed 5/4/22	2505,2424,2487,2488,2496,2497
2508	5042	NA	0%	Top Down & Tub Walls	5 days	Thu 4/28/22	Wed 5/4/22	2507FF
2509	5043	NA	0%	Install Tubs & Fill Test	10 days	Tue 5/3/22	Mon 5/16/22	2508FS-2 days
2510	5044	NA	0%	HVAC Rigid Distribution @ Corridors/Kitchens/Soffits	10 days	Mon 5/2/22	Mon 5/16/22	2508FS-2 days
2511	5045	NA	0%	Frame Ceilings	10 days	Thu 5/12/22	Thu 5/26/22	2508,2509FS-2 days,2510FS-2
2512	5046	NA	0%	Rough-In MEPS/DAS, Walls,CEILINGS (COMPLETE ELECTRICAL PANELS & B	10 days	Tue 5/24/22	Tue 6/7/22	2511FS-2 days
2513	5047	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Wed 6/8/22	Wed 6/8/22	2512
2514	5048	NA	0%	Build Group Quality Control Inspection (Consultant's/Client/Arch if Required) Subcontractor's Distributes One Collilated Complete List To	1 day	Thu 6/2/22	Fri 6/3/22	2512FS-3 days
2515	5049	NA	0%	Subcontractors Complete Build Group's Quality Control Inspection	1 day	Mon 6/6/22	Mon 6/6/22	2514
2516	5050	NA	0%	Build Group Back-Check Subcontractors Completion	1 day	Mon 6/6/22	Tue 6/7/22	2515
2517	<b>5051</b>	<b>NA</b>	<b>0%</b>	<b>Rock and Tape</b>	<b>30 days</b>	<b>Tue 6/7/22</b>	<b>Tue 7/19/22</b>	

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2518	5052	NA	0%	Insulate Walls	5 days	Wed 6/8/22	Tue 6/14/22	2513SF,2516
2519	5053	NA	0%	Drywall Delivery After MEPS Rough IN	1 day	Tue 6/7/22	Tue 6/7/22	2512FF
2520	5054	NA	0%	Door Frames	5 days	Wed 6/8/22	Tue 6/14/22	2512FF,2519
2521	5055	NA	0%	Hang Drywall L7	10 days	Thu 6/23/22	Thu 7/7/22	2513,2516,2520,2438
2522	5056	NA	0%	Tape & Drywall Touch Up (Walls/Ceilings & Corridors)	10 days	Wed 7/6/22	Tue 7/19/22	2521FS-2 days
2523	<b>5057</b>	<b>NA</b>	<b>0%</b>	<b>Finishes</b>	<b>66 days</b>	<b>Tue 7/19/22</b>	<b>Thu 10/20/22</b>	
2524	5058	NA	0%	Prime Paint/1ST COAT PAINT	10 days	Tue 7/19/22	Mon 8/1/22	2522FS-1 day,2441FS-1 day
2525	5059	NA	0%	Install Interior Door Frames	10 days	Mon 8/1/22	Fri 8/12/22	2524FS-1 day
2526	5060	NA	0%	Install Unit Entry Doors/Hardware	10 days	Mon 8/1/22	Fri 8/12/22	2525SS
2527	5061	NA	0%	Install WP Redgard at Tube/Shower Walls & Floors	5 days	Tue 8/2/22	Mon 8/8/22	2524
2528	5062	NA	0%	Flood Test Shower Pans	2 days	Tue 8/9/22	Wed 8/10/22	2527
2529	5063	NA	0%	Install Cabinets/Trim/Linen Closets	10 days	Thu 8/11/22	Wed 8/24/22	2525FS-2 days
2530	5064	NA	0%	Install Kitchen Stone Countertops	10 days	Wed 8/24/22	Wed 9/7/22	2529FS-1 day
2531	5065	NA	0%	Install Stone Backsplash at Kitchen Counters	10 days	Wed 8/24/22	Wed 9/7/22	2530FF
2532	5066	NA	0%	Install Tile/Vinyl flooring/Base	10 days	Wed 8/24/22	Wed 9/7/22	2528,2529
2533	5067	NA	0%	Install Stone Entry Threshold & Protection	10 days	Wed 8/24/22	Wed 9/7/22	2530FF,2531FF
2534	5068	NA	0%	Install Vanities/Medicine Cabinets	5 days	Mon 9/5/22	Mon 9/12/22	2532FS-2 days
2535	5069	NA	0%	Install Vanity Countertops	5 days	Thu 9/8/22	Thu 9/15/22	2534FS-2 days
2536	5070	NA	0%	Install Unit Flooring & Base	10 days	Mon 9/12/22	Mon 9/26/22	2533,2534
2537	5071	NA	0%	Install Window Blinds	10 days	Mon 9/26/22	Mon 10/10/22	2536
2538	5072	NA	0%	Appliances/Dish-Washer/Refrigerator/Microwave	5 days	Mon 9/26/22	Mon 10/3/22	2536
2539	5075	NA	0%	Install Bathroom Accessories/Mirrors/Tube/Shower Enclosures/Closet	10 days	Mon 9/26/22	Mon 10/10/22	2532,2536
2540	5076	NA	0%	Install MEPS Trim	10 days	Wed 10/5/22	Wed 10/19/22	2535,2538,2457
2541	5077	NA	0%	Tube Mending	1 day	Mon 10/10/22	Tue 10/11/22	2539
2542	5078	NA	0%	LOCK DOORS	1 day	Thu 10/20/22	Thu 10/20/22	2540
2543	<b>5830</b>	<b>NA</b>	<b>0%</b>	<b>PUNCH/CLEANING &amp; UNIT ACCEPTANCE</b>	<b>21 days</b>	<b>Thu 10/20/22</b>	<b>Thu 11/17/22</b>	
2544	5079	NA	0%	BG Pre-Punch List	0 days	Thu 10/20/22	Thu 10/20/22	2539,2541FF,2542SS
2545	5080	NA	0%	Subcontractor Complete Pre-Punch List L7	2 days	Thu 10/20/22	Fri 10/21/22	2544
2546	5081	NA	0%	Rough Cleaning	2 days	Mon 10/24/22	Tue 10/25/22	2545
2547	5082	NA	0%	Owners Punch	1 day	Wed 10/26/22	Wed 10/26/22	2546
2548	5083	NA	0%	Subcontractor Complete Owner Punch	2 days	Thu 10/27/22	Fri 10/28/22	2547
2549	5084	NA	0%	Paint 2nd Coat Finish	10 days	Mon 10/31/22	Fri 11/11/22	2548
2550	5085	NA	0%	Final Cleaning	3 days	Mon 11/14/22	Wed 11/16/22	2549
2551	5086	NA	0%	Unit Acceptance L7	1 day	Thu 11/17/22	Thu 11/17/22	2550
2552	<b>3502</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 8</b>	<b>192.88 days</b>	<b>Fri 2/25/22</b>	<b>Thu 12/1/22</b>	
2553	<b>7862</b>	<b>NA</b>	<b>0%</b>	<b>MEPS VERTICAL</b>	<b>28.88 days</b>	<b>Fri 2/25/22</b>	<b>Wed 4/6/22</b>	
2554	7863	NA	0%	PROSHORE SHORING L 11	0 days	Fri 2/25/22	Fri 2/25/22	1242SS
2555	7864	NA	0%	Fire Sprinkler Risers	10 days	Thu 3/24/22	Wed 4/6/22	2554,2472
2556	<b>7865</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Tue 3/8/22</b>	<b>Mon 3/28/22</b>	
2557	7866	NA	0%	Storm/Waste/Vent	5 days	Tue 3/8/22	Mon 3/14/22	2554,2479
2558	7867	NA	0%	Duct Riser	5 days	Tue 3/15/22	Mon 3/21/22	2557,2480
2559	7868	NA	0%	Water/Gas/Fuel	5 days	Tue 3/22/22	Mon 3/28/22	2558,2481
2560	7869	NA	0%	Heat Pump Risers	5 days	Tue 3/22/22	Mon 3/28/22	2482
2561	<b>7870</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Tue 3/15/22</b>	<b>Mon 4/4/22</b>	
2562	7871	NA	0%	Storm/Waste/Vent	5 days	Tue 3/15/22	Mon 3/21/22	2557
2563	7872	NA	0%	Duct Riser	5 days	Tue 3/22/22	Mon 3/28/22	2558
2564	7873	NA	0%	Water/Gas/Fuel	5 days	Tue 3/29/22	Mon 4/4/22	2559

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2565	7874	NA	0%	Heat Pump Risers	5 days	Tue 3/29/22	Mon 4/4/22	2560
2566	<b>7875</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT/SPRINKLERS-ELECTRICAL DISTRIBUTION/SHAFTS</b>	<b>35.88 days</b>	<b>Wed 3/16/22</b>	<b>Wed 5/4/22</b>	
2567	7876	NA	0%	Re-Shores have been Removed/Dry Finish/ Prep Ceilings	3 days	Wed 3/16/22	Mon 3/21/22	1286,1252
2568	7877	NA	0%	Spray Concrete Ceiling Bonding Agent	2 days	Tue 4/5/22	Wed 4/6/22	2556,2561,2567
2569	<b>7878</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Thu 4/7/22</b>	<b>Wed 4/27/22</b>	
2570	7879	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 4/7/22	Wed 4/13/22	2568
2571	7880	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Thu 4/7/22	Wed 4/13/22	2570FF
2572	7882	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 4/14/22	Wed 4/20/22	2558,2570
2573	9847	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 4/21/22	Thu 4/21/22	2572
2574	9848	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 4/21/22	Thu 4/21/22	2573FF
2575	9849	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 4/21/22	Thu 4/21/22	2573FF,2574FF
2576	7881	NA	0%	Fire Sprinkler Distribution	5 days	Thu 4/21/22	Wed 4/27/22	2571,2572
2577	7883	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 4/21/22	Wed 4/27/22	2568,2576SS
2578	<b>7884</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Thu 4/14/22</b>	<b>Wed 5/4/22</b>	
2579	7885	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 4/14/22	Wed 4/20/22	2570
2580	7886	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Thu 4/14/22	Wed 4/20/22	2579FF
2581	7888	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 4/21/22	Wed 4/27/22	2563,2579
2582	9851	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 4/28/22	Thu 4/28/22	2581
2583	9852	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 4/28/22	Thu 4/28/22	2582FF
2584	9853	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 4/28/22	Thu 4/28/22	2582FF,2583FF
2585	7887	NA	0%	Fire Sprinkler Distribution	5 days	Thu 4/28/22	Wed 5/4/22	2581
2586	7889	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 4/28/22	Wed 5/4/22	2570,2577,2585SS
2587	<b>5137</b>	<b>NA</b>	<b>0%</b>	<b>Rough-In</b>	<b>41 days</b>	<b>Tue 4/26/22</b>	<b>Thu 6/23/22</b>	
2588	5138	NA	0%	L8 Window Walls/Precast Panels Complete	0 days	Tue 4/26/22	Tue 4/26/22	3505
2589	9854	NA	0%	Insulate Shafts with Moisture Barrier Insulation	2 days	Mon 5/2/22	Wed 5/4/22	2590SF-1 day,2575,2584
2590	5139	NA	0%	Party & Corridor Walls L8	10 days	Thu 5/5/22	Wed 5/18/22	2588,2507,2570,2571,2579,25
2591	5140	NA	0%	Top Down & Tub Walls	5 days	Thu 5/12/22	Wed 5/18/22	2590FF
2592	5141	NA	0%	Install Tubs & Fill Test	10 days	Tue 5/17/22	Tue 5/31/22	2591FS-2 days
2593	5142	NA	0%	HVAC Rigid Distribution @ Corridors/Kitchens/Soffits	10 days	Mon 5/16/22	Mon 5/30/22	2591FS-2 days
2594	5143	NA	0%	Frame Ceilings	10 days	Fri 5/27/22	Fri 6/10/22	2591,2592FS-2 days,2593FS-2
2595	5144	NA	0%	Rough-In MEPS/DAS, Walls,CEILINGS (COMPLETE ELECTRICAL PANELS & B	10 days	Wed 6/8/22	Wed 6/22/22	2594FS-2 days
2596	5145	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Thu 6/23/22	Thu 6/23/22	2595
2597	5146	NA	0%	Build Group Quality Control Inspection (Consultant's/Client/Arch if Required) Subcontractor's Distributes One Collilated Complete List To	1 day	Fri 6/17/22	Mon 6/20/22	2595FS-3 days
2598	5147	NA	0%	Subcontractors Complete Build Group's Quality Control Inspection	1 day	Tue 6/21/22	Tue 6/21/22	2597
2599	5148	NA	0%	Build Group Back-Check Subcontractors Completion	1 day	Tue 6/21/22	Wed 6/22/22	2598
2600	<b>5149</b>	<b>NA</b>	<b>0%</b>	<b>Rock and Tape</b>	<b>29 days</b>	<b>Wed 6/22/22</b>	<b>Tue 8/2/22</b>	
2601	5150	NA	0%	Insulate Walls	5 days	Thu 6/23/22	Wed 6/29/22	2596SF,2599
2602	5151	NA	0%	Drywall Delivery After MEPS Rough IN	1 day	Wed 6/22/22	Wed 6/22/22	2595FF
2603	5152	NA	0%	Door Frames	5 days	Thu 6/23/22	Wed 6/29/22	2595FF,2602
2604	5153	NA	0%	Hang Drywall L8	10 days	Fri 7/8/22	Thu 7/21/22	2596,2599,2521
2605	5154	NA	0%	Tape & Drywall Touch Up (Walls/Ceilings & Corridors)	10 days	Wed 7/20/22	Tue 8/2/22	2604FS-2 days
2606	<b>5155</b>	<b>NA</b>	<b>0%</b>	<b>Finishes</b>	<b>66 days</b>	<b>Tue 8/2/22</b>	<b>Thu 11/3/22</b>	
2607	5156	NA	0%	Prime Paint/1ST COAT PAINT	10 days	Tue 8/2/22	Mon 8/15/22	2605FS-1 day,2524FS-1 day
2608	5157	NA	0%	Install Interior Door Frames	10 days	Mon 8/15/22	Fri 8/26/22	2607FS-1 day
2609	5158	NA	0%	Install Unit Entry Doors/Hardware	10 days	Mon 8/15/22	Fri 8/26/22	2608SS
2610	5159	NA	0%	Install WP Redgard at Tube/Shower Walls & Floors	5 days	Tue 8/16/22	Mon 8/22/22	2607

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2611	5160	NA	0%	Flood Test Shower Pans	2 days	Tue 8/23/22	Wed 8/24/22	2610
2612	5161	NA	0%	Install Cabinets/Trim/Linen Closets	10 days	Thu 8/25/22	Thu 9/8/22	2608FS-2 days
2613	5162	NA	0%	Install Kitchen Stone Countertops	10 days	Thu 9/8/22	Wed 9/21/22	2612FS-1 day
2614	5163	NA	0%	Install Stone Backsplash at Kitchen Counters	10 days	Thu 9/8/22	Wed 9/21/22	2613FF
2615	5164	NA	0%	Install Tile/Vinyl flooring/Base	10 days	Thu 9/8/22	Thu 9/22/22	2611,2612
2616	5165	NA	0%	Install Stone Entry Threshold & Protection	10 days	Wed 9/7/22	Wed 9/21/22	2613FF,2614FF
2617	5166	NA	0%	Install Vanities/Medicine Cabinets	5 days	Tue 9/20/22	Tue 9/27/22	2615FS-2 days
2618	5167	NA	0%	Install Vanity Countertops	5 days	Fri 9/23/22	Fri 9/30/22	2617FS-2 days
2619	5168	NA	0%	Install Unit Flooring & Base	10 days	Tue 9/27/22	Tue 10/11/22	2616,2617
2620	5169	NA	0%	Install Window Blinds	10 days	Tue 10/11/22	Tue 10/25/22	2619
2621	5170	NA	0%	Appliances/Dish-Washer/Refrigerator/Microwave	5 days	Tue 10/11/22	Tue 10/18/22	2619
2622	5173	NA	0%	Install Bathroom Accessories/Mirrors/Tube/Shower Enclosures/Closet	10 days	Tue 10/11/22	Tue 10/25/22	2615,2619
2623	5174	NA	0%	Install MEPS Trim	10 days	Wed 10/19/22	Wed 11/2/22	2618,2621,2540
2624	5175	NA	0%	Tube Mending	1 day	Tue 10/25/22	Wed 10/26/22	2622
2625	5176	NA	0%	LOCK DOORS	1 day	Thu 11/3/22	Thu 11/3/22	2623
2626	<b>5832</b>	<b>NA</b>	<b>0%</b>	<b>PUNCH/CLEANING &amp; UNIT ACCEPTANCE</b>	<b>21 days</b>	<b>Thu 11/3/22</b>	<b>Thu 12/1/22</b>	
2627	5177	NA	0%	BG Pre-Punch List	0 days	Thu 11/3/22	Thu 11/3/22	2622,2624FF,2625SS
2628	5178	NA	0%	Subcontractor Complete Pre-Punch List L8	2 days	Thu 11/3/22	Fri 11/4/22	2627
2629	5179	NA	0%	Rough Cleaning	2 days	Mon 11/7/22	Tue 11/8/22	2628
2630	5180	NA	0%	Owners Punch	1 day	Wed 11/9/22	Wed 11/9/22	2629
2631	5181	NA	0%	Subcontractor Complete Owner Punch	2 days	Thu 11/10/22	Fri 11/11/22	2630
2632	5182	NA	0%	Paint 2nd Coat Finish	10 days	Mon 11/14/22	Fri 11/25/22	2631
2633	5183	NA	0%	Final Cleaning	3 days	Mon 11/28/22	Wed 11/30/22	2632
2634	5184	NA	0%	Unit Acceptance L8	1 day	Thu 12/1/22	Thu 12/1/22	2633
2635	<b>3601</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 9</b>	<b>193.88 days</b>	<b>Thu 3/10/22</b>	<b>Thu 12/15/22</b>	
2636	<b>7892</b>	<b>NA</b>	<b>0%</b>	<b>MEPS VERTICAL</b>	<b>29.88 days</b>	<b>Thu 3/10/22</b>	<b>Wed 4/20/22</b>	
2637	7893	NA	0%	PROSHORE SHORING L 12	0 days	Thu 3/10/22	Thu 3/10/22	1286SS
2638	7894	NA	0%	Fire Sprinkler Risers	10 days	Thu 4/7/22	Wed 4/20/22	2637,2555
2639	<b>7895</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Tue 3/22/22</b>	<b>Mon 4/11/22</b>	
2640	7896	NA	0%	Storm/Waste/Vent	5 days	Tue 3/22/22	Mon 3/28/22	2637,2562
2641	7897	NA	0%	Duct Riser	5 days	Tue 3/29/22	Mon 4/4/22	2640,2563
2642	7898	NA	0%	Water/Gas/Fuel	5 days	Tue 4/5/22	Mon 4/11/22	2641,2564
2643	7899	NA	0%	Heat Pump Risers	5 days	Tue 4/5/22	Mon 4/11/22	2641,2565
2644	<b>7900</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Tue 3/29/22</b>	<b>Mon 4/18/22</b>	
2645	7901	NA	0%	Storm/Waste/Vent	5 days	Tue 3/29/22	Mon 4/4/22	2640
2646	7902	NA	0%	Duct Riser	5 days	Tue 4/5/22	Mon 4/11/22	2641
2647	7903	NA	0%	Water/Gas/Fuel	5 days	Tue 4/12/22	Mon 4/18/22	2642
2648	7904	NA	0%	Heat Pump Risers	5 days	Tue 4/12/22	Mon 4/18/22	2643
2649	<b>7905</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT/SPRINKLERS-ELECTRICAL DISTRIBUTION/SHAFTS</b>	<b>36.88 days</b>	<b>Tue 3/29/22</b>	<b>Wed 5/18/22</b>	
2650	7906	NA	0%	Re-Shores have been Removed/Dry Finish/ Prep Ceilings	3 days	Tue 3/29/22	Fri 4/1/22	1329,1296
2651	7907	NA	0%	Spray Concrete Ceiling Bonding Agent	2 days	Tue 4/19/22	Wed 4/20/22	2639,2644,2650
2652	<b>7908</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Thu 4/21/22</b>	<b>Wed 5/11/22</b>	
2653	7909	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 4/21/22	Wed 4/27/22	2651
2654	7910	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Thu 4/21/22	Wed 4/27/22	2653FF
2655	7912	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 4/28/22	Wed 5/4/22	2641,2653
2656	9856	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 5/5/22	Thu 5/5/22	2655
2657	9857	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 5/5/22	Thu 5/5/22	2656FF

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2658	9858	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 5/5/22	Thu 5/5/22	2656FF,2657FF
2659	7911	NA	0%	Fire Sprinkler Distribution	5 days	Thu 5/5/22	Wed 5/11/22	2655
2660	7913	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 5/5/22	Wed 5/11/22	2651,2659SS
2661	<b>7914</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Thu 4/28/22</b>	<b>Wed 5/18/22</b>	
2662	7915	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 4/28/22	Wed 5/4/22	2653
2663	7916	NA	0%	Layout MEPS Wall/Ceiling/Acess Panel Openings	5 days	Thu 4/28/22	Wed 5/4/22	2662FF
2664	7918	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 5/5/22	Wed 5/11/22	2646,2662
2665	9860	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 5/12/22	Thu 5/12/22	2664
2666	9861	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 5/12/22	Thu 5/12/22	2665FF
2667	9862	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 5/12/22	Thu 5/12/22	2665FF,2666FF
2668	7917	NA	0%	Fire Sprinkler Distribution	5 days	Thu 5/12/22	Wed 5/18/22	2664
2669	7919	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 5/5/22	Wed 5/11/22	2653,2660SS
2670	<b>5235</b>	<b>NA</b>	<b>0%</b>	<b>Rough-In</b>	<b>40 days</b>	<b>Tue 5/10/22</b>	<b>Thu 7/7/22</b>	
2671	5236	NA	0%	L9 Window Walls/Precast Panels Complete	0 days	Tue 5/10/22	Tue 5/10/22	3511
2672	9863	NA	0%	Insulate Shafts with Moisture Barrier Insulation	2 days	Mon 5/16/22	Wed 5/18/22	2673SF-1 day,2667,2658
2673	5237	NA	0%	Party & Corridor Walls L9	10 days	Thu 5/19/22	Thu 6/2/22	2671,2590,2653,2654,2655,26
2674	5238	NA	0%	Top Down & Tub Walls	5 days	Thu 5/26/22	Thu 6/2/22	2673FF
2675	5239	NA	0%	Install Tubs & Fill Test	10 days	Wed 6/1/22	Tue 6/14/22	2674FS-2 days
2676	5240	NA	0%	HVAC Rigid Distribution @ Corridors/Kitchens/Soffits	10 days	Tue 5/31/22	Tue 6/14/22	2674FS-2 days
2677	5241	NA	0%	Frame Ceilings	10 days	Fri 6/10/22	Fri 6/24/22	2674,2675FS-2 days,2676FS-2
2678	5242	NA	0%	Rough-In MEPS/DAS, Walls,CEILINGS (COMPLETE ELECTRICAL PANELS & B	10 days	Wed 6/22/22	Wed 7/6/22	2677FS-2 days
2679	5243	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Thu 7/7/22	Thu 7/7/22	2678
2680	5244	NA	0%	Build Group Quality Control Inspection (Consultant's/Client/Arch if Required) Subcontractor's Distributes One Collilated Complete List To	1 day	Fri 7/1/22	Mon 7/4/22	2678FS-3 days
2681	5245	NA	0%	Subcontractors Complete Build Group's Quality Control Inspection	1 day	Tue 7/5/22	Tue 7/5/22	2680
2682	5246	NA	0%	Build Group Back-Check Subcontractors Completion	1 day	Tue 7/5/22	Wed 7/6/22	2681
2683	<b>5247</b>	<b>NA</b>	<b>0%</b>	<b>Rock and Tape</b>	<b>34 days</b>	<b>Wed 6/29/22</b>	<b>Tue 8/16/22</b>	
2684	5248	NA	0%	Insulate Walls	5 days	Thu 7/7/22	Wed 7/13/22	2679SF,2682
2685	5249	NA	0%	Drywall Delivery After MEPS Rough IN	1 day	Wed 7/6/22	Wed 7/6/22	2678FF
2686	5250	NA	0%	Door Frames	5 days	Wed 6/29/22	Wed 7/6/22	2678FF
2687	5251	NA	0%	Hang Drywall L9	10 days	Fri 7/22/22	Thu 8/4/22	2679,2686,2604
2688	5252	NA	0%	Tape & Drywall Touch Up (Walls/Ceilings & Corridors)	10 days	Wed 8/3/22	Tue 8/16/22	2687FS-2 days
2689	<b>5253</b>	<b>NA</b>	<b>0%</b>	<b>Finishes</b>	<b>65 days</b>	<b>Tue 8/16/22</b>	<b>Thu 11/17/22</b>	
2690	5254	NA	0%	Prime Paint/1ST COAT PAINT	10 days	Tue 8/16/22	Mon 8/29/22	2688FS-1 day,2607FS-1 day
2691	5255	NA	0%	Install Interior Door Frames	10 days	Mon 8/29/22	Mon 9/12/22	2690FS-1 day
2692	5256	NA	0%	Install Unit Entry Doors/Hardware	10 days	Mon 8/29/22	Mon 9/12/22	2691SS
2693	5257	NA	0%	Install WP Redgard at Tube/Shower Walls & Floors	5 days	Tue 8/30/22	Tue 9/6/22	2690
2694	5258	NA	0%	Flood Test Shower Pans	2 days	Wed 9/7/22	Thu 9/8/22	2693
2695	5259	NA	0%	Install Cabinets/Trim/Linen Closets	10 days	Fri 9/9/22	Thu 9/22/22	2691FS-2 days
2696	5260	NA	0%	Install Kitchen Stone Countertops	10 days	Thu 9/22/22	Wed 10/5/22	2695FS-1 day
2697	5261	NA	0%	Install Stone Backsplash at Kitchen Counters	10 days	Thu 9/22/22	Wed 10/5/22	2696FF
2698	5262	NA	0%	Install Tile/Vinyl flooring/Base	10 days	Thu 9/22/22	Thu 10/6/22	2694,2695
2699	5263	NA	0%	Install Stone Entry Threshold & Protection	10 days	Wed 9/21/22	Wed 10/5/22	2696FF,2697FF
2700	5264	NA	0%	Install Vanities/Medicine Cabinets	5 days	Tue 10/4/22	Tue 10/11/22	2698FS-2 days
2701	5265	NA	0%	Install Vanity Countertops	5 days	Fri 10/7/22	Fri 10/14/22	2700FS-2 days
2702	5266	NA	0%	Install Unit Flooring & Base	10 days	Tue 10/11/22	Tue 10/25/22	2699,2700
2703	5267	NA	0%	Install Window Blinds	10 days	Tue 10/25/22	Tue 11/8/22	2702

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2704	5268	NA	0%	Appliances/Dish-Washer/Refrigerator/Microwave	5 days	Tue 10/25/22	Tue 11/1/22	2702
2705	5271	NA	0%	Install Bathroom Accessories/Mirrors/Tube/Shower Enclosures/Closet	10 days	Tue 10/25/22	Tue 11/8/22	2698,2702
2706	5272	NA	0%	Install MEPS Trim	10 days	Wed 11/2/22	Wed 11/16/22	2701,2704,2623
2707	5273	NA	0%	Tube Mending	1 day	Tue 11/8/22	Wed 11/9/22	2705
2708	5274	NA	0%	LOCK DOORS	1 day	Thu 11/17/22	Thu 11/17/22	2706
2709	<b>5834</b>	<b>NA</b>	<b>0%</b>	<b>PUNCH/CLEANING &amp; UNIT ACCEPTANCE</b>	<b>21 days</b>	<b>Thu 11/17/22</b>	<b>Thu 12/15/22</b>	
2710	5275	NA	0%	BG Pre-Punch List	0 days	Thu 11/17/22	Thu 11/17/22	2705,2707FF,2708SS
2711	5276	NA	0%	Subcontractor Complete Pre-Punch List L9	2 days	Thu 11/17/22	Fri 11/18/22	2710
2712	5277	NA	0%	Rough Cleaning	2 days	Mon 11/21/22	Tue 11/22/22	2711
2713	5278	NA	0%	Owners Punch	1 day	Wed 11/23/22	Wed 11/23/22	2712
2714	5279	NA	0%	Subcontractor Complete Owner Punch	2 days	Thu 11/24/22	Fri 11/25/22	2713
2715	5280	NA	0%	Paint 2nd Coat Finish	10 days	Mon 11/28/22	Fri 12/9/22	2714
2716	5281	NA	0%	Final Cleaning	3 days	Mon 12/12/22	Wed 12/14/22	2715
2717	5282	NA	0%	Unit Acceptance L9	1 day	Thu 12/15/22	Thu 12/15/22	2716
2718	<b>3700</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 10</b>	<b>193.88 days</b>	<b>Wed 3/23/22</b>	<b>Thu 12/29/22</b>	
2719	<b>7922</b>	<b>NA</b>	<b>0%</b>	<b>MEPS VERTICAL</b>	<b>30.88 days</b>	<b>Wed 3/23/22</b>	<b>Wed 5/4/22</b>	
2720	7923	NA	0%	PROSHORE SHORING L 13	0 days	Wed 3/23/22	Wed 3/23/22	1329SS
2721	7924	NA	0%	Fire Sprinkler Risers	10 days	Thu 4/21/22	Wed 5/4/22	2720,2638
2722	<b>7925</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Tue 4/5/22</b>	<b>Mon 4/25/22</b>	
2723	7926	NA	0%	Storm/Waste/Vent	5 days	Tue 4/5/22	Mon 4/11/22	2720,2645
2724	7927	NA	0%	Duct Riser	5 days	Tue 4/12/22	Mon 4/18/22	2723,2646
2725	7928	NA	0%	Water/Gas/Fuel	5 days	Tue 4/19/22	Mon 4/25/22	2724,2647
2726	7929	NA	0%	Heat Pump Risers	5 days	Tue 4/19/22	Mon 4/25/22	2724,2648
2727	<b>7930</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Tue 4/12/22</b>	<b>Mon 5/2/22</b>	
2728	7931	NA	0%	Storm/Waste/Vent	5 days	Tue 4/12/22	Mon 4/18/22	2723
2729	7932	NA	0%	Duct Riser	5 days	Tue 4/19/22	Mon 4/25/22	2724
2730	7933	NA	0%	Water/Gas/Fuel	5 days	Tue 4/26/22	Mon 5/2/22	2725
2731	7934	NA	0%	Heat Pump Risers	5 days	Tue 4/26/22	Mon 5/2/22	2726
2732	<b>7935</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT/SPRINKLERS-ELECTRICAL DISTRIBUTION/SHAFTS</b>	<b>37.88 days</b>	<b>Mon 4/11/22</b>	<b>Wed 6/1/22</b>	
2733	7936	NA	0%	Re-Shores have been Removed/Dry Finish/ Prep Ceilings	3 days	Mon 4/11/22	Thu 4/14/22	1372,1339
2734	7937	NA	0%	Spray Concrete Ceiling Bonding Agent	2 days	Tue 5/3/22	Wed 5/4/22	2722,2727,2733
2735	<b>7938</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Thu 5/5/22</b>	<b>Wed 5/25/22</b>	
2736	7939	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 5/5/22	Wed 5/11/22	2734
2737	7940	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Thu 5/5/22	Wed 5/11/22	2736FF
2738	7942	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 5/12/22	Wed 5/18/22	2724,2736
2739	9865	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 5/19/22	Thu 5/19/22	2738
2740	9866	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 5/19/22	Thu 5/19/22	2739FF
2741	9867	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 5/19/22	Thu 5/19/22	2739FF,2740FF
2742	7941	NA	0%	Fire Sprinkler Distribution	5 days	Thu 5/19/22	Wed 5/25/22	2738
2743	7943	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 5/19/22	Wed 5/25/22	2734,2742SS
2744	<b>7944</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Thu 5/12/22</b>	<b>Wed 6/1/22</b>	
2745	7945	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 5/12/22	Wed 5/18/22	2736
2746	7946	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Thu 5/12/22	Wed 5/18/22	2745FF
2747	7948	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 5/19/22	Wed 5/25/22	2729,2745
2748	9869	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 5/26/22	Thu 5/26/22	2747
2749	9870	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 5/26/22	Thu 5/26/22	2748FF
2750	9871	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 5/26/22	Thu 5/26/22	2748FF,2749FF

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2751	7947	NA	0%	Fire Sprinkler Distribution	5 days	Thu 5/26/22	Wed 6/1/22	2747
2752	7949	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 5/26/22	Wed 6/1/22	2736,2743,2751SS
2753	<b>5333</b>	<b>NA</b>	<b>0%</b>	<b>Rough-In</b>	<b>40 days</b>	<b>Tue 5/24/22</b>	<b>Thu 7/21/22</b>	
2754	5334	NA	0%	L10 Window Walls/Precast Panels Complete	0 days	Tue 5/24/22	Tue 5/24/22	3517
2755	9872	NA	0%	Insulate Shafts with Moisture Barrier Insulation	2 days	Tue 5/31/22	Thu 6/2/22	2756SF-1 day,2750,2741
2756	5335	NA	0%	Party & Corridor Walls L10	10 days	Fri 6/3/22	Thu 6/16/22	2754,2673,2736,2737,2738,27
2757	5336	NA	0%	Top Down & Tub Walls	5 days	Fri 6/10/22	Thu 6/16/22	2756FF
2758	5337	NA	0%	Install Tubs & Fill Test	10 days	Wed 6/15/22	Tue 6/28/22	2757FS-2 days
2759	5338	NA	0%	HVAC Rigid Distribution @ Corridors/Kitchens/Soffits	10 days	Tue 6/14/22	Tue 6/28/22	2757FS-2 days
2760	5339	NA	0%	Frame Ceilings	10 days	Fri 6/24/22	Fri 7/8/22	2757,2758FS-2 days,2759FS-2
2761	5340	NA	0%	Rough-In MEPS/DAS, Walls,CEILINGS (COMPLETE ELECICAL PANELS & B	10 days	Wed 7/6/22	Wed 7/20/22	2760FS-2 days
2762	5341	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Thu 7/21/22	Thu 7/21/22	2761
2763	5342	NA	0%	Build Group Quality Control Inspection (Consultant's/Client/Arch if Required) Subcontractor's Distributes One Collilated Complete List To	1 day	Fri 7/15/22	Mon 7/18/22	2761FS-3 days
2764	5343	NA	0%	Subcontractors Complete Build Group's Quality Control Inspection	1 day	Tue 7/19/22	Tue 7/19/22	2763
2765	5344	NA	0%	Build Group Back-Check Subcontractors Completion	1 day	Tue 7/19/22	Wed 7/20/22	2764
2766	<b>5345</b>	<b>NA</b>	<b>0%</b>	<b>Rock and Tape</b>	<b>34 days</b>	<b>Thu 7/14/22</b>	<b>Tue 8/30/22</b>	
2767	5346	NA	0%	Insulate Walls	5 days	Thu 7/21/22	Wed 7/27/22	2762SF,2765
2768	5347	NA	0%	Drywall Delivery After MEPS Rough IN	1 day	Wed 7/20/22	Wed 7/20/22	2761FF
2769	5348	NA	0%	Door Frames	5 days	Thu 7/14/22	Wed 7/20/22	2761FF
2770	5349	NA	0%	Hang Drywall L10	10 days	Fri 8/5/22	Thu 8/18/22	2762,2765,2769,2687
2771	5350	NA	0%	Tape & Drywall Touch Up (Walls/Ceilings & Corridors)	10 days	Wed 8/17/22	Tue 8/30/22	2770FS-2 days
2772	<b>5351</b>	<b>NA</b>	<b>0%</b>	<b>Finishes</b>	<b>63 days</b>	<b>Tue 8/30/22</b>	<b>Thu 12/1/22</b>	
2773	5352	NA	0%	Prime Paint/1ST COAT PAINT	10 days	Tue 8/30/22	Tue 9/13/22	2771FS-1 day,2690FS-1 day
2774	5353	NA	0%	Install Interior Door Frames	10 days	Tue 9/13/22	Mon 9/26/22	2773FS-1 day
2775	5354	NA	0%	Install Unit Entry Doors/Hardware	10 days	Tue 9/13/22	Mon 9/26/22	2774SS
2776	5355	NA	0%	Install WP Redgard at Tube/Shower Walls & Floors	5 days	Wed 9/14/22	Tue 9/20/22	2773
2777	5356	NA	0%	Flood Test Shower Pans	2 days	Wed 9/21/22	Thu 9/22/22	2776
2778	5357	NA	0%	Install Cabinets/Trim/Linen Closets	10 days	Fri 9/23/22	Thu 10/6/22	2774FS-2 days
2779	5358	NA	0%	Install Kitchen Stone Countertops	10 days	Thu 10/6/22	Thu 10/20/22	2778FS-1 day
2780	5359	NA	0%	Install Stone Backsplash at Kitchen Counters	10 days	Thu 10/6/22	Thu 10/20/22	2779FF
2781	5360	NA	0%	Install Tile/Vinyl flooring/Base	10 days	Thu 10/6/22	Thu 10/20/22	2777,2778
2782	5361	NA	0%	Install Stone Entry Threshold & Protection	10 days	Thu 10/6/22	Thu 10/20/22	2779FF,2780FF
2783	5362	NA	0%	Install Vanities/Medicine Cabinets	5 days	Tue 10/18/22	Tue 10/25/22	2781FS-2 days
2784	5363	NA	0%	Install Vanity Countertops	5 days	Fri 10/21/22	Fri 10/28/22	2783FS-2 days
2785	5364	NA	0%	Install Unit Flooring & Base	10 days	Tue 10/25/22	Tue 11/8/22	2782,2783
2786	5365	NA	0%	Install Window Blinds	10 days	Tue 11/8/22	Tue 11/22/22	2785
2787	5366	NA	0%	Appliances/Dish-Washer/Refrigerator/Microwave	5 days	Tue 11/8/22	Tue 11/15/22	2785
2788	5369	NA	0%	Install Bathroom Accessories/Mirrors/Tube/Shower Enclosures/Closet I	10 days	Tue 11/8/22	Tue 11/22/22	2781,2785
2789	5370	NA	0%	Install MEPS Trim L 10	10 days	Wed 11/16/22	Wed 11/30/22	2784,2787,2706
2790	5371	NA	0%	Tube Mending	1 day	Tue 11/22/22	Wed 11/23/22	2788
2791	5372	NA	0%	LOCK DOORS	1 day	Thu 12/1/22	Thu 12/1/22	2789
2792	<b>5836</b>	<b>NA</b>	<b>0%</b>	<b>PUNCH/CLEANING &amp; UNIT ACCEPTANCE</b>	<b>21 days</b>	<b>Thu 12/1/22</b>	<b>Thu 12/29/22</b>	
2793	5373	NA	0%	BG Pre-Punch List	0 days	Thu 12/1/22	Thu 12/1/22	2788,2790FF,2791SS
2794	5374	NA	0%	Subcontractor Complete Pre-Punch List L10	2 days	Thu 12/1/22	Fri 12/2/22	2793
2795	5375	NA	0%	Rough Cleaning	2 days	Mon 12/5/22	Tue 12/6/22	2794
2796	5376	NA	0%	Owners Punch	1 day	Wed 12/7/22	Wed 12/7/22	2795



University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2797	5377	NA	0%	Subcontractor Complete Owner Punch	2 days	Thu 12/8/22	Fri 12/9/22	2796
2798	5378	NA	0%	Paint 2nd Coat Finish	10 days	Mon 12/12/22	Fri 12/23/22	2797
2799	5379	NA	0%	Final Cleaning	3 days	Mon 12/26/22	Wed 12/28/22	2798
2800	5380	NA	0%	Unit Acceptance L10	1 day	Thu 12/29/22	Thu 12/29/22	2799
2801	<b>3799</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 11</b>	<b>192.88 days</b>	<b>Tue 4/5/22</b>	<b>Wed 1/11/23</b>	
2802	<b>7952</b>	<b>NA</b>	<b>0%</b>	<b>MEPS VERTICAL</b>	<b>31.88 days</b>	<b>Tue 4/5/22</b>	<b>Wed 5/18/22</b>	
2803	7953	NA	0%	PROSHORE SHORING L 14	0 days	Tue 4/5/22	Tue 4/5/22	1372SS
2804	7954	NA	0%	Fire Sprinkler Risers	10 days	Thu 5/5/22	Wed 5/18/22	2803,2721
2805	<b>7955</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Tue 4/19/22</b>	<b>Mon 5/9/22</b>	
2806	7956	NA	0%	Storm/Waste/Vent	5 days	Tue 4/19/22	Mon 4/25/22	2803,2728
2807	7957	NA	0%	Duct Riser	5 days	Tue 4/26/22	Mon 5/2/22	2806,2729
2808	7958	NA	0%	Water/Gas/Fuel	5 days	Tue 5/3/22	Mon 5/9/22	2807,2730
2809	7959	NA	0%	Heat Pump Risers	5 days	Tue 5/3/22	Mon 5/9/22	2807,2731
2810	<b>7960</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Tue 4/26/22</b>	<b>Mon 5/16/22</b>	
2811	7961	NA	0%	Storm/Waste/Vent	5 days	Tue 4/26/22	Mon 5/2/22	2806
2812	7962	NA	0%	Duct Riser	5 days	Tue 5/3/22	Mon 5/9/22	2807
2813	7963	NA	0%	Water/Gas/Fuel	5 days	Tue 5/10/22	Mon 5/16/22	2808
2814	7964	NA	0%	Heat Pump Risers	5 days	Tue 5/10/22	Mon 5/16/22	2809
2815	<b>7965</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT/SPRINKLERS-ELECTRICAL DISTRIBUTION/SHAFTS</b>	<b>40.88 days</b>	<b>Wed 4/20/22</b>	<b>Wed 6/15/22</b>	
2816	7966	NA	0%	Re-Shores have been Removed/Dry Finish/ Prep Ceilings	3 days	Wed 4/20/22	Mon 4/25/22	1417,1383
2817	7967	NA	0%	Spray Concrete Ceiling Bonding Agent	2 days	Tue 5/17/22	Wed 5/18/22	2805,2810,2816
2818	<b>7968</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Thu 5/19/22</b>	<b>Wed 6/8/22</b>	
2819	7969	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 5/19/22	Wed 5/25/22	2817
2820	7970	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Thu 5/19/22	Wed 5/25/22	2819FF
2821	7972	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 5/26/22	Wed 6/1/22	2807,2819
2822	9874	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 6/2/22	Thu 6/2/22	2821
2823	9875	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 6/2/22	Thu 6/2/22	2822FF
2824	9876	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 6/2/22	Thu 6/2/22	2822FF,2823FF
2825	7971	NA	0%	Fire Sprinkler Distribution	5 days	Thu 6/2/22	Wed 6/8/22	2821
2826	7973	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 6/2/22	Wed 6/8/22	2817,2825SS
2827	<b>7974</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Thu 5/26/22</b>	<b>Wed 6/15/22</b>	
2828	7975	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 5/26/22	Wed 6/1/22	2819
2829	7976	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Thu 5/26/22	Wed 6/1/22	2828FF
2830	7978	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 6/2/22	Wed 6/8/22	2812,2828
2831	9878	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 6/9/22	Thu 6/9/22	2830
2832	9879	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 6/9/22	Thu 6/9/22	2831FF
2833	9880	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 6/9/22	Thu 6/9/22	2831FF,2832FF
2834	7977	NA	0%	Fire Sprinkler Distribution	5 days	Thu 6/9/22	Wed 6/15/22	2830
2835	7979	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 6/9/22	Wed 6/15/22	2819,2826,2834SS
2836	<b>5431</b>	<b>NA</b>	<b>0%</b>	<b>Rough-In</b>	<b>41 days</b>	<b>Wed 6/8/22</b>	<b>Fri 8/5/22</b>	
2837	5432	NA	0%	L11 Window Walls/Precast Panels Complete	0 days	Wed 6/8/22	Wed 6/8/22	3523
2838	9881	NA	0%	Insulate Shafts with Moisture Barrier Insulation	2 days	Tue 6/14/22	Thu 6/16/22	2839SF-1 day,2833,2824
2839	5433	NA	0%	Party & Corridor Walls L11	10 days	Fri 6/17/22	Thu 6/30/22	2837,2756,2819,2820,2828,28
2840	5434	NA	0%	Top Down & Tub Walls	5 days	Fri 6/24/22	Thu 6/30/22	2839FF
2841	5435	NA	0%	Install Tubs & Fill Test	10 days	Wed 6/29/22	Wed 7/13/22	2840FS-2 days
2842	5436	NA	0%	HVAC Rigid Distribution @ Corridors/Kitchens/Soffits	10 days	Tue 6/28/22	Tue 7/12/22	2840FS-2 days
2843	5437	NA	0%	Frame Ceilings	10 days	Mon 7/11/22	Mon 7/25/22	2840,2841FS-2 days,2842FS-2

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2844	5438	NA	0%	Rough-In MEPS/DAS, Walls,CEILING (COMPLETE ELECRICAL PANELS & B	10 days	Thu 7/21/22	Thu 8/4/22	2843FS-2 days
2845	5439	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILING/SLABS)	1 day	Fri 8/5/22	Fri 8/5/22	2844
2846	5440	NA	0%	Build Group Quality Control Inspection (Consultant's/Client/Arch if Required) Subcontractor's Distributes One Collilated Complete List To	1 day	Mon 8/1/22	Tue 8/2/22	2844FS-3 days
2847	5441	NA	0%	Subcontractors Complete Build Group's Quality Control Inspection	1 day	Wed 8/3/22	Wed 8/3/22	2846
2848	5442	NA	0%	Build Group Back-Check Subcontractors Completion	1 day	Wed 8/3/22	Thu 8/4/22	2847
2849	<b>5443</b>	<b>NA</b>	<b>0%</b>	<b>Rock and Tape</b>	<b>33 days</b>	<b>Fri 7/29/22</b>	<b>Wed 9/14/22</b>	
2850	5444	NA	0%	Insulate Walls	5 days	Fri 8/5/22	Thu 8/11/22	2845SF,2848
2851	5445	NA	0%	Drywall Delivery After MEPS Rough IN	1 day	Thu 8/4/22	Thu 8/4/22	2844FF
2852	5446	NA	0%	Door Frames	5 days	Fri 7/29/22	Thu 8/4/22	2844FF
2853	5447	NA	0%	Hang Drywall L11	10 days	Fri 8/19/22	Thu 9/1/22	2845,2848,2852,2770
2854	5448	NA	0%	Tape & Drywall Touch Up (Walls/Ceilings & Corridors)	10 days	Wed 8/31/22	Wed 9/14/22	2853FS-2 days
2855	<b>5449</b>	<b>NA</b>	<b>0%</b>	<b>Finishes</b>	<b>63 days</b>	<b>Wed 9/14/22</b>	<b>Thu 12/15/22</b>	
2856	5450	NA	0%	Prime Paint/1ST COAT PAINT	10 days	Wed 9/14/22	Tue 9/27/22	2854FS-1 day,2773FS-1 day
2857	5451	NA	0%	Install Interior Door Frames	10 days	Tue 9/27/22	Tue 10/11/22	2856FS-1 day
2858	5452	NA	0%	Install Unit Entry Doors/Hardware	10 days	Tue 9/27/22	Tue 10/11/22	2857SS
2859	5453	NA	0%	Install WP Redgard at Tube/Shower Walls & Floors	5 days	Wed 9/28/22	Tue 10/4/22	2856
2860	5454	NA	0%	Flood Test Shower Pans	2 days	Wed 10/5/22	Thu 10/6/22	2859
2861	5455	NA	0%	Install Cabinets/Trim/Linen Closets	10 days	Fri 10/7/22	Fri 10/21/22	2857FS-2 days
2862	5456	NA	0%	Install Kitchen Stone Countertops	10 days	Fri 10/21/22	Thu 11/3/22	2861FS-1 day
2863	5457	NA	0%	Install Stone Backsplash at Kitchen Counters	10 days	Fri 10/21/22	Thu 11/3/22	2862FF
2864	5458	NA	0%	Install Tile/Vinyl flooring/Base	10 days	Fri 10/21/22	Fri 11/4/22	2860,2861
2865	5459	NA	0%	Install Stone Entry Threshold & Protection	10 days	Thu 10/20/22	Thu 11/3/22	2862FF,2863FF
2866	5460	NA	0%	Install Vanities/Medicine Cabinets	5 days	Wed 11/2/22	Wed 11/9/22	2864FS-2 days
2867	5461	NA	0%	Install Vanity Countertops	5 days	Mon 11/7/22	Mon 11/14/22	2866FS-2 days
2868	5462	NA	0%	Install Unit Flooring & Base	10 days	Wed 11/9/22	Wed 11/23/22	2865,2866
2869	5463	NA	0%	Install Window Blinds	10 days	Wed 11/23/22	Wed 12/7/22	2868
2870	5464	NA	0%	Appliances/Dish-Washer/Refrigerator/Microwave	5 days	Wed 11/23/22	Wed 11/30/22	2868
2871	5467	NA	0%	Install Bathroom Accessories/Mirrors/Tube/Shower Enclosures/Closet I	10 days	Wed 11/23/22	Wed 12/7/22	2864,2868
2872	5468	NA	0%	Install MEPS TriM	10 days	Wed 11/30/22	Wed 12/14/22	2867,2870,2789
2873	5469	NA	0%	Tube Mending	1 day	Wed 12/7/22	Thu 12/8/22	2871
2874	5470	NA	0%	LOCK DOORS	1 day	Thu 12/15/22	Thu 12/15/22	2872
2875	<b>5838</b>	<b>NA</b>	<b>0%</b>	<b>PUNCH/CLEANING &amp; UNIT ACCEPTANCE</b>	<b>21 days</b>	<b>Thu 12/15/22</b>	<b>Wed 1/11/23</b>	
2876	5471	NA	0%	BG Pre-Punch List	0 days	Thu 12/15/22	Thu 12/15/22	2871,2873FF,2874SS
2877	5472	NA	0%	Subcontractor Complete Pre-Punch List L11	2 days	Thu 12/15/22	Fri 12/16/22	2876
2878	5473	NA	0%	Rough Cleaning	2 days	Mon 12/19/22	Tue 12/20/22	2877
2879	5474	NA	0%	Owners Punch	1 day	Wed 12/21/22	Wed 12/21/22	2878
2880	5475	NA	0%	Subcontractor Complete Owner Punch	2 days	Thu 12/22/22	Fri 12/23/22	2879
2881	5476	NA	0%	Paint 2nd Coat Finish	10 days	Mon 12/26/22	Fri 1/6/23	2880
2882	5477	NA	0%	Final Cleaning	3 days	Sat 1/7/23	Tue 1/10/23	2881
2883	5478	NA	0%	Unit Acceptance L11	1 day	Wed 1/11/23	Wed 1/11/23	2882
2884	<b>3898</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 12</b>	<b>194.88 days</b>	<b>Fri 4/15/22</b>	<b>Wed 1/25/23</b>	
2885	<b>7982</b>	<b>NA</b>	<b>0%</b>	<b>MEPS VERTICAL</b>	<b>33.88 days</b>	<b>Fri 4/15/22</b>	<b>Wed 6/1/22</b>	
2886	7983	NA	0%	PROSHORE SHORING L15/ROOF	0 days	Fri 4/15/22	Fri 4/15/22	1417SS
2887	7984	NA	0%	Fire Sprinkler Risers	10 days	Thu 5/19/22	Wed 6/1/22	2886,2804
2888	<b>7985</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Tue 5/3/22</b>	<b>Mon 5/23/22</b>	
2889	7986	NA	0%	Storm/Waste/Vent	5 days	Tue 5/3/22	Mon 5/9/22	2886,2811

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2890	7987	NA	0%	Duct Riser	5 days	Tue 5/10/22	Mon 5/16/22	2889,2812
2891	7988	NA	0%	Water/Gas/Fuel	5 days	Tue 5/17/22	Mon 5/23/22	2890,2813
2892	7989	NA	0%	Heat Pump Risers	5 days	Tue 5/17/22	Mon 5/23/22	2890,2814
2893	<b>7990</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Tue 5/10/22</b>	<b>Mon 5/30/22</b>	
2894	7991	NA	0%	Storm/Waste/Vent	5 days	Tue 5/10/22	Mon 5/16/22	2889
2895	7992	NA	0%	Duct Riser	5 days	Tue 5/17/22	Mon 5/23/22	2890,2894
2896	7993	NA	0%	Water/Gas/Fuel	5 days	Tue 5/24/22	Mon 5/30/22	2891
2897	7994	NA	0%	Heat Pump Risers	5 days	Tue 5/24/22	Mon 5/30/22	2892
2898	<b>7995</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT/SPRINKLERS-ELECTRICAL DISTRIBUTION/SHAFTS</b>	<b>39 days</b>	<b>Fri 5/6/22</b>	<b>Wed 6/29/22</b>	
2899	7996	NA	0%	Re-Shores have been Removed/Dry Finish/ Prep Ceilings	3 days	Fri 5/6/22	Tue 5/10/22	1429,1428
2900	7997	NA	0%	Spray Concrete Ceiling Bonding Agent	2 days	Tue 5/31/22	Wed 6/1/22	2888,2893,2899
2901	<b>7998</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Thu 6/2/22</b>	<b>Wed 6/22/22</b>	
2902	7999	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 6/2/22	Wed 6/8/22	2900
2903	8000	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Thu 6/2/22	Wed 6/8/22	2902FF
2904	8002	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 6/9/22	Wed 6/15/22	2890,2902
2905	9883	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 6/16/22	Thu 6/16/22	2904
2906	9884	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 6/16/22	Thu 6/16/22	2905FF
2907	9885	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 6/16/22	Thu 6/16/22	2905FF,2906FF
2908	8001	NA	0%	Fire Sprinkler Distribution	5 days	Thu 6/16/22	Wed 6/22/22	2904
2909	8003	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 6/16/22	Wed 6/22/22	2900,2908SS
2910	<b>8004</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Thu 6/9/22</b>	<b>Wed 6/29/22</b>	
2911	8005	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 6/9/22	Wed 6/15/22	2902
2912	8006	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Thu 6/9/22	Wed 6/15/22	2911FF
2913	8008	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 6/16/22	Wed 6/22/22	2895,2911
2914	9887	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 6/23/22	Thu 6/23/22	2913
2915	9888	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 6/23/22	Thu 6/23/22	2914FF
2916	9889	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 6/23/22	Thu 6/23/22	2914FF,2915FF
2917	8007	NA	0%	Fire Sprinkler Distribution	5 days	Thu 6/23/22	Wed 6/29/22	2913
2918	8009	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 6/23/22	Wed 6/29/22	2902,2909,2917SS
2919	<b>5529</b>	<b>NA</b>	<b>0%</b>	<b>Rough-In</b>	<b>41 days</b>	<b>Wed 6/22/22</b>	<b>Fri 8/19/22</b>	
2920	5530	NA	0%	L12 Window Walls/Precast Panels Complete	0 days	Wed 6/22/22	Wed 6/22/22	3529
2921	9890	NA	0%	Insulate Shafts with Moisture Barrier Insulation	2 days	Tue 6/28/22	Thu 6/30/22	2922SF-1 day,2916,2907
2922	5531	NA	0%	Party & Corridor Walls L12	10 days	Fri 7/1/22	Fri 7/15/22	2920,2839,2902,2903,2904,2905
2923	5532	NA	0%	Top Down & Tub Walls	5 days	Mon 7/11/22	Fri 7/15/22	2922FF
2924	5533	NA	0%	Install Tubs & Fill Test	10 days	Thu 7/14/22	Wed 7/27/22	2923FS-2 days
2925	5534	NA	0%	HVAC Rigid Distribution @ Corridors/Kitchens/Soffits	10 days	Wed 7/13/22	Wed 7/27/22	2923FS-2 days
2926	5535	NA	0%	Frame Ceilings	10 days	Mon 7/25/22	Mon 8/8/22	2923,2924FS-2 days,2925FS-2 days
2927	5536	NA	0%	Rough-In MEPS/DAS, Walls,CEILINGS (COMPLETE ELECTRICAL PANELS & B	10 days	Thu 8/4/22	Thu 8/18/22	2926FS-2 days
2928	5537	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Fri 8/19/22	Fri 8/19/22	2927
2929	5538	NA	0%	Build Group Quality Control Inspection (Consultant's/Client/Arch if Required) Subcontractor's Distributes One Collilated Complete List To	1 day	Mon 8/15/22	Tue 8/16/22	2927FS-3 days
2930	5539	NA	0%	Subcontractors Complete Build Group's Quality Control Inspection	1 day	Wed 8/17/22	Wed 8/17/22	2929
2931	5540	NA	0%	Build Group Back-Check Subcontractors Completion	1 day	Wed 8/17/22	Thu 8/18/22	2930
2932	<b>5541</b>	<b>NA</b>	<b>0%</b>	<b>Rock and Tape</b>	<b>33 days</b>	<b>Fri 8/12/22</b>	<b>Wed 9/28/22</b>	
2933	5542	NA	0%	Insulate Walls	5 days	Fri 8/19/22	Thu 8/25/22	2928SF,2931
2934	5543	NA	0%	Drywall Delivery After MEPS Rough IN	1 day	Thu 8/18/22	Thu 8/18/22	2927FF
2935	5544	NA	0%	Door Frames	5 days	Fri 8/12/22	Thu 8/18/22	2927FF

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2936	5545	NA	0%	Hang Drywall L12	10 days	Fri 9/2/22	Fri 9/16/22	2928,2931,2935,2853
2937	5546	NA	0%	Tape & Drywall Touch Up (Walls/Ceilings & Corridors)	10 days	Thu 9/15/22	Wed 9/28/22	2936FS-2 days
2938	<b>5547</b>	<b>NA</b>	<b>0%</b>	<b>Finishes</b>	<b>62 days</b>	<b>Wed 9/28/22</b>	<b>Thu 12/29/22</b>	
2939	5548	NA	0%	Prime Paint/1ST COAT PAINT	10 days	Wed 9/28/22	Wed 10/12/22	2937FS-1 day,2856FS-1 day
2940	5549	NA	0%	Install Interior Door Frames	10 days	Wed 10/12/22	Tue 10/25/22	2939FS-1 day
2941	5550	NA	0%	Install Unit Entry Doors/Hardware	10 days	Wed 10/12/22	Tue 10/25/22	2940SS
2942	5551	NA	0%	Install WP Redgard at Tube/Shower Walls & Floors	5 days	Thu 10/13/22	Wed 10/19/22	2939
2943	5552	NA	0%	Flood Test Shower Pans	2 days	Thu 10/20/22	Fri 10/21/22	2942
2944	5553	NA	0%	Install Cabinets/Trim/Linen Closets	10 days	Mon 10/24/22	Fri 11/4/22	2940FS-2 days
2945	5554	NA	0%	Install Kitchen Stone Countertops	10 days	Fri 11/4/22	Fri 11/18/22	2944FS-1 day
2946	5555	NA	0%	Install Stone Backsplash at Kitchen Counters	10 days	Fri 11/4/22	Fri 11/18/22	2945FF
2947	5556	NA	0%	Install Tile/Vinyl flooring/Base	10 days	Fri 11/4/22	Fri 11/18/22	2943,2944
2948	5557	NA	0%	Install Stone Entry Threshold & Protection	10 days	Fri 11/4/22	Fri 11/18/22	2945FF,2946FF
2949	5558	NA	0%	Install Vanities/Medicine Cabinets	5 days	Wed 11/16/22	Wed 11/23/22	2947FS-2 days
2950	5559	NA	0%	Install Vanity Countertops	5 days	Mon 11/21/22	Mon 11/28/22	2949FS-2 days
2951	5560	NA	0%	Install Unit Flooring & Base	10 days	Wed 11/23/22	Wed 12/7/22	2948,2949
2952	5561	NA	0%	Install Window Blinds	10 days	Wed 12/7/22	Wed 12/21/22	2951
2953	5562	NA	0%	Appliances/Dish-Washer/Refrigerator/Microwave	5 days	Wed 12/7/22	Wed 12/14/22	2951
2954	5565	NA	0%	Install Bathroom Accessories/Mirrors/Tube/Shower Enclosures/Closet	10 days	Wed 12/7/22	Wed 12/21/22	2947,2951
2955	5566	NA	0%	Install MEPS Trim L12	10 days	Wed 12/14/22	Wed 12/28/22	2950,2953,2872
2956	5567	NA	0%	Tube Mending	1 day	Wed 12/21/22	Thu 12/22/22	2954
2957	5568	NA	0%	LOCK DOORS	1 day	Thu 12/29/22	Thu 12/29/22	2955
2958	<b>5840</b>	<b>NA</b>	<b>0%</b>	<b>PUNCH/CLEANING &amp; UNIT ACCEPTANCE</b>	<b>21 days</b>	<b>Thu 12/29/22</b>	<b>Wed 1/25/23</b>	
2959	5569	NA	0%	BG Pre-Punch List	0 days	Thu 12/29/22	Thu 12/29/22	2954,2956FF,2957SS
2960	5570	NA	0%	Subcontractor Complete Pre-Punch List L12	2 days	Thu 12/29/22	Fri 12/30/22	2959
2961	5571	NA	0%	Rough Cleaning	2 days	Mon 1/2/23	Tue 1/3/23	2960
2962	5572	NA	0%	Owners Punch	1 day	Wed 1/4/23	Wed 1/4/23	2961
2963	5573	NA	0%	Subcontractor Complete Owner Punch	2 days	Thu 1/5/23	Fri 1/6/23	2962
2964	5574	NA	0%	Paint 2nd Coat Finish	10 days	Sat 1/7/23	Thu 1/19/23	2963
2965	5575	NA	0%	Final Cleaning	3 days	Fri 1/20/23	Tue 1/24/23	2964
2966	5576	NA	0%	Unit Acceptance L12	1 day	Wed 1/25/23	Wed 1/25/23	2965
2967	<b>3997</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 13</b>	<b>186.88 days</b>	<b>Thu 5/12/22</b>	<b>Thu 2/9/23</b>	
2968	<b>8012</b>	<b>NA</b>	<b>0%</b>	<b>MEPS VERTICAL</b>	<b>24.88 days</b>	<b>Thu 5/12/22</b>	<b>Wed 6/15/22</b>	
2969	8013	NA	0%	STRIP DECK L15	0 days	Thu 5/12/22	Thu 5/12/22	1451
2970	8014	NA	0%	Fire Sprinkler Risers	10 days	Thu 6/2/22	Wed 6/15/22	2969,2887
2971	<b>8015</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Tue 5/17/22</b>	<b>Mon 6/6/22</b>	
2972	8016	NA	0%	Storm/Waste/Vent	5 days	Tue 5/17/22	Mon 5/23/22	2969,2894
2973	8017	NA	0%	Duct Riser	5 days	Tue 5/24/22	Mon 5/30/22	2972,2895
2974	8018	NA	0%	Water/Gas/Fuel	5 days	Tue 5/31/22	Mon 6/6/22	2973,2896
2975	8019	NA	0%	Heat Pump Risers	5 days	Tue 5/31/22	Mon 6/6/22	2973,2897
2976	<b>8020</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Tue 5/24/22</b>	<b>Mon 6/13/22</b>	
2977	8021	NA	0%	Storm/Waste/Vent	5 days	Tue 5/24/22	Mon 5/30/22	2972
2978	8022	NA	0%	Duct Riser	5 days	Tue 5/31/22	Mon 6/6/22	2973,2977
2979	8023	NA	0%	Water/Gas/Fuel	5 days	Tue 6/7/22	Mon 6/13/22	2974
2980	8024	NA	0%	Heat Pump Risers	5 days	Tue 6/7/22	Mon 6/13/22	2975
2981	<b>8025</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT/SPRINKLERS-ELECTRICAL DISTRIBUTION/SHAFTS</b>	<b>44.88 days</b>	<b>Thu 5/12/22</b>	<b>Wed 7/13/22</b>	
2982	8026	NA	0%	Re-Shores have been Removed/Dry Finish/ Prep Ceilings	3 days	Thu 5/12/22	Tue 5/17/22	1451,2899

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
2983	8027	NA	0%	Spray Concrete Ceiling Bonding Agent	2 days	Tue 6/14/22	Wed 6/15/22	2971,2976,2982
2984	<b>8028</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Thu 6/16/22</b>	<b>Wed 7/6/22</b>	
2985	8029	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 6/16/22	Wed 6/22/22	2983
2986	8030	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Thu 6/16/22	Wed 6/22/22	2985FF
2987	8032	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 6/23/22	Wed 6/29/22	2973,2985
2988	9892	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 6/30/22	Thu 6/30/22	2987
2989	9893	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 6/30/22	Thu 6/30/22	2988FF
2990	9894	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 6/30/22	Thu 6/30/22	2988FF,2989FF
2991	8031	NA	0%	Fire Sprinkler Distribution	5 days	Thu 6/30/22	Wed 7/6/22	2987
2992	8033	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 6/30/22	Wed 7/6/22	2983,2991SS
2993	<b>8034</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Thu 6/23/22</b>	<b>Wed 7/13/22</b>	
2994	8035	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 6/23/22	Wed 6/29/22	2985
2995	8036	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Thu 6/23/22	Wed 6/29/22	2994FF
2996	8038	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 6/30/22	Wed 7/6/22	2978,2994
2997	9896	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 7/7/22	Thu 7/7/22	2996
2998	9897	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 7/7/22	Thu 7/7/22	2997FF
2999	9898	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 7/7/22	Thu 7/7/22	2997FF,2998FF
3000	8037	NA	0%	Fire Sprinkler Distribution	5 days	Thu 7/7/22	Wed 7/13/22	2994,2996
3001	8039	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 7/7/22	Wed 7/13/22	2985,2992,3000SS
3002	<b>5627</b>	<b>NA</b>	<b>0%</b>	<b>Rough-In</b>	<b>41 days</b>	<b>Thu 7/7/22</b>	<b>Fri 9/2/22</b>	
3003	5628	NA	0%	L13 Window Walls/Precast Panels Complete	0 days	Thu 7/7/22	Thu 7/7/22	3535
3004	9899	NA	0%	Insulate Shafts with Moisture Barrier Insulation	2 days	Wed 7/13/22	Fri 7/15/22	3005SF-1 day,2990,2999
3005	5629	NA	0%	Party & Corridor Walls L13	10 days	Mon 7/18/22	Fri 7/29/22	3003,2922,2985,2987,2994,2999
3006	5630	NA	0%	Top Down & Tub Walls	5 days	Mon 7/25/22	Fri 7/29/22	3005FF
3007	5631	NA	0%	Install Tubs & Fill Test	10 days	Thu 7/28/22	Wed 8/10/22	3006FS-2 days
3008	5632	NA	0%	HVAC Rigid Distribution @ Corridors/Kitchens/Soffits	10 days	Wed 7/27/22	Wed 8/10/22	3006FS-2 days
3009	5633	NA	0%	Frame Ceilings	10 days	Mon 8/8/22	Mon 8/22/22	3006,3007FS-2 days,3008FS-2
3010	5634	NA	0%	Rough-In MEPS/DAS, Walls,CEILINGS (COMPLETE ELECTRICAL PANELS & B	10 days	Thu 8/18/22	Thu 9/1/22	3009FS-2 days
3011	5635	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Fri 9/2/22	Fri 9/2/22	3010
3012	5636	NA	0%	Build Group Quality Control Inspection (Consultant's/Client/Arch if Required) Subcontractor's Distributes One Collilated Complete List To	1 day	Mon 8/29/22	Tue 8/30/22	3010FS-3 days
3013	5637	NA	0%	Subcontractors Complete Build Group's Quality Control Inspection	1 day	Wed 8/31/22	Wed 8/31/22	3012
3014	5638	NA	0%	Build Group Back-Check Subcontractors Completion	1 day	Wed 8/31/22	Thu 9/1/22	3013
3015	<b>5639</b>	<b>NA</b>	<b>0%</b>	<b>Rock and Tape</b>	<b>33 days</b>	<b>Fri 8/26/22</b>	<b>Thu 10/13/22</b>	
3016	5640	NA	0%	Insulate Walls	5 days	Fri 9/2/22	Fri 9/9/22	3011SF,3014
3017	5641	NA	0%	Drywall Delivery After MEPS Rough IN	1 day	Thu 9/1/22	Thu 9/1/22	3010FF
3018	5642	NA	0%	Door Frames	5 days	Fri 8/26/22	Thu 9/1/22	3010FF
3019	5643	NA	0%	Hang Drywall L13	10 days	Mon 9/19/22	Fri 9/30/22	3011,3014,3018,2936
3020	5644	NA	0%	Tape & Drywall Touch Up (Walls/Ceilings & Corridors)	10 days	Thu 9/29/22	Thu 10/13/22	3019FS-2 days
3021	<b>5645</b>	<b>NA</b>	<b>0%</b>	<b>Finishes</b>	<b>61 days</b>	<b>Thu 10/13/22</b>	<b>Thu 1/12/23</b>	
3022	5646	NA	0%	Prime Paint/1ST COAT PAINT	10 days	Thu 10/13/22	Wed 10/26/22	3020FS-1 day,2939FS-1 day
3023	5647	NA	0%	Install Interior Door Frames	10 days	Wed 10/26/22	Tue 11/8/22	3022FS-1 day
3024	5648	NA	0%	Install Unit Entry Doors/Hardware	10 days	Wed 10/26/22	Tue 11/8/22	3023SS
3025	5649	NA	0%	Install WP Redgard at Tube/Shower Walls & Floors	5 days	Thu 10/27/22	Wed 11/2/22	3022
3026	5650	NA	0%	Flood Test Shower Pans	2 days	Thu 11/3/22	Fri 11/4/22	3025
3027	5651	NA	0%	Install Cabinets/Trim/Linen Closets	10 days	Mon 11/7/22	Mon 11/21/22	3023FS-2 days
3028	5652	NA	0%	Install Kitchen Stone Countertops	10 days	Mon 11/21/22	Tue 12/6/22	3027FS-1 day

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
3029	5653	NA	0%	Install Stone Backsplash at Kitchen Counters	10 days	Mon 11/21/22	Tue 12/6/22	3028FF
3030	5654	NA	0%	Install Tile/Vinyl flooring/Base	10 days	Mon 11/21/22	Mon 12/5/22	3026,3027
3031	5655	NA	0%	Install Stone Entry Threshold & Protection	10 days	Tue 11/22/22	Tue 12/6/22	3028FF,3029FF
3032	5656	NA	0%	Install Vanities/Medicine Cabinets	5 days	Thu 12/1/22	Thu 12/8/22	3030FS-2 days
3033	5657	NA	0%	Install Vanity Countertops	5 days	Tue 12/6/22	Tue 12/13/22	3032FS-2 days
3034	5658	NA	0%	Install Unit Flooring & Base	10 days	Thu 12/8/22	Thu 12/22/22	3031,3032
3035	5659	NA	0%	Install Window Blinds	10 days	Thu 12/22/22	Thu 1/5/23	3034
3036	5660	NA	0%	Appliances/Dish-Washer/Refrigerator/Microwave	5 days	Thu 12/22/22	Thu 12/29/22	3034
3037	5663	NA	0%	Install Bathroom Accessories/Mirrors/Tube/Shower Enclosures/Closet	10 days	Thu 12/22/22	Thu 1/5/23	3030,3034
3038	5664	NA	0%	Install MEPS Trim	10 days	Thu 12/29/22	Wed 1/11/23	3033,3036,2955
3039	5665	NA	0%	Tube Mending	1 day	Thu 1/5/23	Fri 1/6/23	3037
3040	5666	NA	0%	LOCK DOORS	1 day	Thu 1/12/23	Thu 1/12/23	3038
3041	<b>5842</b>	<b>NA</b>	<b>0%</b>	<b>PUNCH/CLEANING &amp; UNIT ACCEPTANCE</b>	<b>21 days</b>	<b>Thu 1/12/23</b>	<b>Thu 2/9/23</b>	
3042	5667	NA	0%	BG Pre-Punch List	0 days	Thu 1/12/23	Thu 1/12/23	3037,3039FF,3040SS
3043	5668	NA	0%	Subcontractor Complete Pre-Punch List L13	2 days	Thu 1/12/23	Fri 1/13/23	3042
3044	5669	NA	0%	Rough Cleaning	2 days	Mon 1/16/23	Tue 1/17/23	3043
3045	5670	NA	0%	Owners Punch	1 day	Wed 1/18/23	Wed 1/18/23	3044
3046	5671	NA	0%	Subcontractor Complete Owner Punch	2 days	Thu 1/19/23	Fri 1/20/23	3045
3047	5672	NA	0%	Paint 2nd Coat Finish	10 days	Mon 1/23/23	Fri 2/3/23	3046
3048	5673	NA	0%	Final Cleaning	3 days	Mon 2/6/23	Wed 2/8/23	3047
3049	5674	NA	0%	Unit Acceptance L13	1 day	Thu 2/9/23	Thu 2/9/23	3048
3050	<b>4096</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 14</b>	<b>196.88 days</b>	<b>Thu 5/12/22</b>	<b>Thu 2/23/23</b>	
3051	<b>8042</b>	<b>NA</b>	<b>0%</b>	<b>MEPS VERTICAL</b>	<b>34.88 days</b>	<b>Thu 5/12/22</b>	<b>Wed 6/29/22</b>	
3052	8043	NA	0%	STRIP DECK L15	0 days	Thu 5/12/22	Thu 5/12/22	1451
3053	8044	NA	0%	Fire Sprinkler Risers	10 days	Thu 6/16/22	Wed 6/29/22	3052,2970
3054	<b>8045</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Tue 5/31/22</b>	<b>Mon 6/20/22</b>	
3055	8046	NA	0%	Storm/Waste/Vent	5 days	Tue 5/31/22	Mon 6/6/22	3052,2977
3056	8047	NA	0%	Duct Riser	5 days	Tue 6/7/22	Mon 6/13/22	3055,2978
3057	8048	NA	0%	Water/Gas/Fuel (SOUTH & NORTH OR HANG NORTH)	5 days	Tue 6/14/22	Mon 6/20/22	3056,2979
3058	8049	NA	0%	Heat Pump Risers Water/Gas/Fuel (SOUTH & NORTH OR HANG NORTH)	5 days	Tue 6/14/22	Mon 6/20/22	3056,2980
3059	<b>8050</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>10 days</b>	<b>Tue 6/7/22</b>	<b>Mon 6/20/22</b>	
3060	8051	NA	0%	Storm/Waste/Vent	5 days	Tue 6/7/22	Mon 6/13/22	3055
3061	8052	NA	0%	Duct Riser	5 days	Tue 6/14/22	Mon 6/20/22	3056,3060
3062	8053	NA	0%	Water/Gas/Fuel L 14 Water/Gas/Fuel (SOUTH & NORTH OR HANG NORTH)	5 days	Tue 6/14/22	Mon 6/20/22	3057FF
3063	8054	NA	0%	Heat Pump Risers Water/Gas/Fuel (SOUTH & NORTH OR HANG NORTH)	5 days	Tue 6/14/22	Mon 6/20/22	3058FF
3064	<b>8055</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT/SPRINKLERS-ELECTRICAL DISTRIBUTION/SHAFTS</b>	<b>46.88 days</b>	<b>Tue 5/17/22</b>	<b>Wed 7/20/22</b>	
3065	8056	NA	0%	Re-Shores have been Removed/Dry Finish/ Prep Ceilings	3 days	Tue 5/17/22	Fri 5/20/22	1451,2982
3066	8057	NA	0%	Spray Concrete Ceiling Bonding Agent	2 days	Tue 6/21/22	Wed 6/22/22	3054,3059,3065
3067	<b>8058</b>	<b>NA</b>	<b>0%</b>	<b>SOUTH SIDE</b>	<b>15 days</b>	<b>Thu 6/23/22</b>	<b>Wed 7/13/22</b>	
3068	8059	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 6/23/22	Wed 6/29/22	3066
3069	8060	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Thu 6/23/22	Wed 6/29/22	3068FF
3070	8062	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 6/30/22	Wed 7/6/22	3056,3068
3071	9901	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 7/7/22	Thu 7/7/22	3070
3072	9902	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 7/7/22	Thu 7/7/22	3071FF
3073	9903	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 7/7/22	Thu 7/7/22	3071FF,3072FF
3074	8061	NA	0%	Fire Sprinkler Distribution	5 days	Thu 7/7/22	Wed 7/13/22	3069,3070
3075	8063	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 7/7/22	Wed 7/13/22	3066,3074SS

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
3076	<b>8064</b>	<b>NA</b>	<b>0%</b>	<b>NORTH SIDE</b>	<b>15 days</b>	<b>Thu 6/30/22</b>	<b>Wed 7/20/22</b>	
3077	8065	NA	0%	Layout Walls Install Top Tracks	5 days	Thu 6/30/22	Wed 7/6/22	3068
3078	8066	NA	0%	Layout MEPS Wall/Ceiling/Access Panel Openings	5 days	Thu 6/30/22	Wed 7/6/22	3077FF
3079	8068	NA	0%	Shafts Vertical/Horizontal (Mechanical/Electrical Rooms)	5 days	Thu 7/7/22	Wed 7/13/22	3061,3077
3080	9905	NA	0%	Shafts Firecaulk Coreboard (Complete by 11:00 AM)	1 day	Thu 7/14/22	Thu 7/14/22	3079
3081	9906	NA	0%	Shafts HVAC Firecaulk Coreboard Distribution (Complete by 11:00 AM)	1 day	Thu 7/14/22	Thu 7/14/22	3080FF
3082	9907	NA	0%	Inspection Shafts & FireCaulking (Inspection PM)	0 days	Thu 7/14/22	Thu 7/14/22	3080FF,3081FF
3083	8067	NA	0%	Fire Sprinkler Distribution	5 days	Thu 7/14/22	Wed 7/20/22	3077,3079
3084	8069	NA	0%	Electrical Distribution Strapped to Underneath Concrete Slab	5 days	Thu 7/14/22	Wed 7/20/22	3068,3075,3083SS
3085	<b>5725</b>	<b>NA</b>	<b>0%</b>	<b>Rough-In</b>	<b>40 days</b>	<b>Thu 7/21/22</b>	<b>Fri 9/16/22</b>	
3086	5726	NA	0%	L14 Window Walls/Precast Panels Complete	0 days	Thu 7/21/22	Thu 7/21/22	3541
3087	9908	NA	0%	Insulate Shafts with Moisture Barrier Insulation	2 days	Wed 7/27/22	Fri 7/29/22	3088SF-1 day,3073,3082
3088	5727	NA	0%	Party & Corridor Walls L14	10 days	Mon 8/1/22	Fri 8/12/22	3086,3005,3068,3069,3070,30
3089	5728	NA	0%	Top Down & Tub Walls	5 days	Mon 8/8/22	Fri 8/12/22	3088FF
3090	5729	NA	0%	Install Tubs & Fill Test	10 days	Thu 8/11/22	Wed 8/24/22	3089FS-2 days
3091	5730	NA	0%	HVAC Rigid Distribution @ Corridors/Kitchens/Soffits	10 days	Wed 8/10/22	Wed 8/24/22	3089FS-2 days
3092	5731	NA	0%	Frame Ceilings	10 days	Mon 8/22/22	Mon 9/5/22	3089,3090FS-2 days,3091FS-2
3093	5732	NA	0%	Rough-In MEPS/DAS, Walls,CEILINGS (COMPLETE ELECTRICAL PANELS & B	10 days	Thu 9/1/22	Thu 9/15/22	3092FS-2 days
3094	5733	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Fri 9/16/22	Fri 9/16/22	3093
3095	5734	NA	0%	Build Group Quality Control Inspection (Consultant's/Client/Arch if Required) Subcontractor's Distributes One Collilated Complete List To	1 day	Mon 9/12/22	Tue 9/13/22	3093FS-3 days
3096	5735	NA	0%	Subcontractors Complete Build Group's Quality Control Inspection	1 day	Wed 9/14/22	Wed 9/14/22	3095
3097	5736	NA	0%	Build Group Back-Check Subcontractors Completion	1 day	Wed 9/14/22	Thu 9/15/22	3096
3098	<b>5737</b>	<b>NA</b>	<b>0%</b>	<b>Rock and Tape</b>	<b>34 days</b>	<b>Fri 9/9/22</b>	<b>Thu 10/27/22</b>	
3099	5738	NA	0%	Insulate Walls	5 days	Fri 9/16/22	Thu 9/22/22	3094SF,3097
3100	5739	NA	0%	Drywall Delivery After MEPS Rough IN	1 day	Thu 9/15/22	Thu 9/15/22	3093FF
3101	5740	NA	0%	Door Frames	5 days	Fri 9/9/22	Thu 9/15/22	3093FF
3102	5741	NA	0%	Hang Drywall L14	10 days	Mon 10/3/22	Mon 10/17/22	3094,3097,3101,3019
3103	5742	NA	0%	Tape & Drywall Touch Up (Walls/Ceilings & Corridors)	10 days	Fri 10/14/22	Thu 10/27/22	3102FS-2 days
3104	<b>5743</b>	<b>NA</b>	<b>0%</b>	<b>Finishes</b>	<b>63 days</b>	<b>Thu 10/27/22</b>	<b>Mon 1/30/23</b>	
3105	5744	NA	0%	Prime Paint/1ST COAT PAINT	10 days	Thu 10/27/22	Wed 11/9/22	3103FS-1 day,3022FS-1 day
3106	5745	NA	0%	Install Interior Door Frames	10 days	Wed 11/9/22	Wed 11/23/22	3105FS-1 day
3107	5746	NA	0%	Install Unit Entry Doors/Hardware L14	10 days	Wed 11/9/22	Wed 11/23/22	3106SS
3108	5747	NA	0%	Install WP Redgard at Tube/Shower Walls & Floors	5 days	Thu 11/10/22	Thu 11/17/22	3105
3109	5748	NA	0%	Flood Test Shower Pans	2 days	Fri 11/18/22	Mon 11/21/22	3108
3110	5749	NA	0%	Install Cabinets/Trim/Linen Closets	10 days	Tue 11/22/22	Wed 12/7/22	3106FS-2 days
3111	5750	NA	0%	Install Kitchen Stone Countertops	10 days	Wed 12/7/22	Tue 12/20/22	3110FS-1 day
3112	5751	NA	0%	Install Stone Backsplash at Kitchen Counters	10 days	Wed 12/7/22	Tue 12/20/22	3111FF
3113	5752	NA	0%	Install Tile/Vinyl flooring/Base	10 days	Wed 12/7/22	Wed 12/21/22	3109,3110
3114	5753	NA	0%	Install Stone Entry Threshold & Protection	10 days	Tue 12/6/22	Tue 12/20/22	3111FF,3112FF
3115	5754	NA	0%	Install Vanities/Medicine Cabinets	5 days	Mon 12/19/22	Mon 12/26/22	3113FS-2 days
3116	5755	NA	0%	Install Vanity Countertops	5 days	Thu 12/22/22	Thu 12/29/22	3115FS-2 days
3117	5756	NA	0%	Install Unit Flooring & Base	10 days	Mon 12/26/22	Sat 1/7/23	3114,3115
3118	5757	NA	0%	Install Window Blinds	10 days	Sat 1/7/23	Fri 1/20/23	3117
3119	5758	NA	0%	Appliances/Dish-Washer/Refrigerator/Microwave	5 days	Sat 1/7/23	Fri 1/13/23	3117
3120	5761	NA	0%	Install Bathroom Accessories/Mirrors/Tube/Shower Enclosures/Closet I	10 days	Sat 1/7/23	Fri 1/20/23	3113,3117
3121	5762	NA	0%	Install MEPS Trim L14	10 days	Fri 1/13/23	Fri 1/27/23	3116,3119,3038



University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
3122	5763	NA	0%	Tube Mending	1 day	Fri 1/20/23	Mon 1/23/23	3120
3123	5764	NA	0%	LOCK DOORS	1 day	Mon 1/30/23	Mon 1/30/23	3121
3124	<b>5844</b>	<b>NA</b>	<b>0%</b>	<b>PUNCH/CLEANING &amp; UNIT ACCEPTANCE</b>	<b>19 days</b>	<b>Mon 1/30/23</b>	<b>Thu 2/23/23</b>	
3125	5765	NA	0%	BG Pre-Punch List	0 days	Mon 1/30/23	Mon 1/30/23	3120,3122FF,3123SS
3126	5766	NA	0%	Subcontractor Complete Pre-Punch List L14	2 days	Mon 1/30/23	Tue 1/31/23	3125
3127	5767	NA	0%	Rough Cleaning	2 days	Wed 2/1/23	Thu 2/2/23	3126
3128	5768	NA	0%	Owners Punch	1 day	Fri 2/3/23	Fri 2/3/23	3127
3129	5769	NA	0%	Subcontractor Complete Owner Punch	2 days	Mon 2/6/23	Tue 2/7/23	3128
3130	5770	NA	0%	Paint 2nd Coat Finish	10 days	Wed 2/8/23	Tue 2/21/23	3129
3131	5771	NA	0%	Final Cleaning	2 days	Wed 2/22/23	Thu 2/23/23	3130
3132	5772	NA	0%	Unit Acceptance L 14	1 day	Thu 2/23/23	Thu 2/23/23	3131FF
3133	10424	NA	0%	<b>L2 - L14 UNIT OWNER ACCEPTANCE</b>	1 day	Thu 2/23/23	Thu 2/23/23	3132FF,3049FF,2966FF,2883FF
3134	<b>7243</b>	<b>NA</b>	<b>0%</b>	<b>CORRIDOR &amp; ELEVATOR LOBBY FINISHES</b>	<b>111 days</b>	<b>Wed 9/7/22</b>	<b>Wed 2/8/23</b>	
3135	<b>4476</b>	<b>NA</b>	<b>0%</b>	<b>L 3 CORRIDORS</b>	<b>13 days</b>	<b>Fri 10/7/22</b>	<b>Wed 10/26/22</b>	
3136	4247	NA	0%	MEPS Finish Trim / FECs (FINISH WITH MEPS UNITS TRIM)	0 days	Fri 10/7/22	Fri 10/7/22	2208FF,2126FF
3137	4244	NA	0%	Flooring (Carpet/Stone/Base) & Protection L3	3 days	Tue 10/11/22	Thu 10/13/22	3136
3138	4245	NA	0%	Doors and Hardware / Mag Hold Opens	1 day	Fri 10/14/22	Fri 10/14/22	3137
3139	4248	NA	0%	Signage	1 day	Thu 10/13/22	Fri 10/14/22	3137
3140	4249	NA	0%	Owners Punch	1 day	Fri 10/14/22	Mon 10/17/22	3139,3136,3137,3138
3141	4250	NA	0%	Subcontractor Complete Owner Punch	2 days	Mon 10/17/22	Wed 10/19/22	3140
3142	4251	NA	0%	Paint 2nd Coat Finish	2 days	Wed 10/19/22	Fri 10/21/22	3141
3143	4252	NA	0%	Final Cleaning	2 days	Fri 10/21/22	Tue 10/25/22	3142
3144	4253	NA	0%	OWNER Acceptance L 3 CORRIDORS	1 day	Tue 10/25/22	Wed 10/26/22	3143
3145	<b>7239</b>	<b>NA</b>	<b>0%</b>	<b>L 4 CORRIDORS</b>	<b>12 days</b>	<b>Wed 9/7/22</b>	<b>Fri 9/23/22</b>	
3146	6758	NA	0%	MEPS Finish Trim / FECs (FINISH WITH MEPS UNITS TRIM)	0 days	Wed 9/7/22	Wed 9/7/22	2291FF
3147	5866	NA	0%	Flooring (Carpet/Stone/Base) & Protection L4	3 days	Thu 9/8/22	Mon 9/12/22	3146
3148	5867	NA	0%	Doors and Hardware / Mag Hold Opens	1 day	Tue 9/13/22	Tue 9/13/22	3147
3149	5870	NA	0%	Signage	1 day	Mon 9/12/22	Tue 9/13/22	3147
3150	5871	NA	0%	Owners Punch	1 day	Tue 9/13/22	Wed 9/14/22	3149,3148,3147,3146
3151	5872	NA	0%	Subcontractor Complete Owner Punch	2 days	Wed 9/14/22	Fri 9/16/22	3150
3152	5873	NA	0%	Paint 2nd Coat Finish	2 days	Fri 9/16/22	Tue 9/20/22	3151
3153	5874	NA	0%	Final Cleaning	2 days	Tue 9/20/22	Thu 9/22/22	3152
3154	5875	NA	0%	OWNER Acceptance L 4 CORRIDORS	1 day	Thu 9/22/22	Fri 9/23/22	3153
3155	<b>6004</b>	<b>NA</b>	<b>0%</b>	<b>L 5 CORRIDORS</b>	<b>12 days</b>	<b>Wed 9/21/22</b>	<b>Fri 10/7/22</b>	
3156	6760	NA	0%	MEPS Finish Trim / FECs (FINISH WITH MEPS UNITS TRIM)	0 days	Wed 9/21/22	Wed 9/21/22	2374FF
3157	5914	NA	0%	Flooring (Carpet/Stone/Base) & Protection L5	3 days	Thu 9/22/22	Mon 9/26/22	3156
3158	5915	NA	0%	Doors and Hardware / Mag Hold Opens	1 day	Tue 9/27/22	Tue 9/27/22	3157
3159	5918	NA	0%	Signage	1 day	Mon 9/26/22	Tue 9/27/22	3157
3160	5919	NA	0%	Owners Punch	1 day	Tue 9/27/22	Wed 9/28/22	3159,3156,3157,3158
3161	5920	NA	0%	Subcontractor Complete Owner Punch	2 days	Wed 9/28/22	Fri 9/30/22	3160
3162	5921	NA	0%	Paint 2nd Coat Finish	2 days	Fri 9/30/22	Tue 10/4/22	3161
3163	5922	NA	0%	Final Cleaning	2 days	Tue 10/4/22	Thu 10/6/22	3162
3164	5923	NA	0%	OWNER Acceptance L 5 CORRIDORS	1 day	Thu 10/6/22	Fri 10/7/22	3163
3165	<b>5936</b>	<b>NA</b>	<b>0%</b>	<b>L 6 CORRIDORS</b>	<b>13 days</b>	<b>Wed 10/5/22</b>	<b>Mon 10/24/22</b>	
3166	6762	NA	0%	MEPS Finish Trim / FECs (FINISH WITH MEPS UNITS TRIM)	0 days	Wed 10/5/22	Wed 10/5/22	2457FF
3167	5938	NA	0%	Flooring (Carpet/Stone/Base) & Protection L6	3 days	Thu 10/6/22	Tue 10/11/22	3166
3168	5939	NA	0%	Doors and Hardware / Mag Hold Opens	1 day	Wed 10/12/22	Wed 10/12/22	3167



University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
3169	5942	NA	0%	Signage	1 day	Tue 10/11/22	Wed 10/12/22	3167
3170	5943	NA	0%	Owners Punch	1 day	Wed 10/12/22	Thu 10/13/22	3169,3166
3171	5944	NA	0%	Subcontractor Complete Owner Punch	2 days	Thu 10/13/22	Mon 10/17/22	3170
3172	5945	NA	0%	Paint 2nd Coat Finish	2 days	Mon 10/17/22	Wed 10/19/22	3171
3173	5946	NA	0%	Final Cleaning	2 days	Wed 10/19/22	Fri 10/21/22	3172
3174	5947	NA	0%	OWNER Acceptance L 6 CORRIDORS	1 day	Fri 10/21/22	Mon 10/24/22	3173
3175	<b>6006</b>	<b>NA</b>	<b>0%</b>	<b>L 7 CORRIDORS</b>	<b>12 days</b>	<b>Wed 10/19/22</b>	<b>Fri 11/4/22</b>	
3176	6764	NA	0%	MEPS Finish Trim / FECs (FINISH WITH MEPS UNITS TRIM)	0 days	Wed 10/19/22	Wed 10/19/22	2540FF
3177	5962	NA	0%	Flooring (Carpet/Stone/Base) & Protection L7	3 days	Thu 10/20/22	Mon 10/24/22	3176
3178	5963	NA	0%	Doors and Hardware / Mag Hold Opens	1 day	Tue 10/25/22	Tue 10/25/22	3177
3179	5966	NA	0%	Signage	1 day	Mon 10/24/22	Tue 10/25/22	3177
3180	5967	NA	0%	Owners Punch	1 day	Tue 10/25/22	Wed 10/26/22	3179,3176,3178,3177
3181	5968	NA	0%	Subcontractor Complete Owner Punch	2 days	Wed 10/26/22	Fri 10/28/22	3180
3182	5969	NA	0%	Paint 2nd Coat Finish	2 days	Fri 10/28/22	Tue 11/1/22	3181
3183	5970	NA	0%	Final Cleaning	2 days	Tue 11/1/22	Thu 11/3/22	3182
3184	5971	NA	0%	OWNER Acceptance L 7 CORRIDORS	1 day	Thu 11/3/22	Fri 11/4/22	3183
3185	<b>6008</b>	<b>NA</b>	<b>0%</b>	<b>L 8 CORRIDORS</b>	<b>14.88 days</b>	<b>Tue 10/25/22</b>	<b>Mon 11/14/22</b>	
3186	6766	NA	0%	MEPS Finish Trim / FECs (FINISH WITH MEPS UNITS TRIM)	0 days	Wed 11/2/22	Wed 11/2/22	2623FF
3187	6010	NA	0%	Flooring (Carpet/Stone/Base) & Protection L8	3 days	Tue 10/25/22	Thu 10/27/22	3177
3188	6011	NA	0%	Doors and Hardware / Mag Hold Opens	1 day	Fri 10/28/22	Fri 10/28/22	3187
3189	6014	NA	0%	Signage	1 day	Thu 10/27/22	Fri 10/28/22	3187
3190	6015	NA	0%	Owners Punch	1 day	Wed 11/2/22	Thu 11/3/22	3189,3186,3187,3188
3191	6016	NA	0%	Subcontractor Complete Owner Punch	2 days	Thu 11/3/22	Mon 11/7/22	3190
3192	6017	NA	0%	Paint 2nd Coat Finish	2 days	Mon 11/7/22	Wed 11/9/22	3191
3193	6018	NA	0%	Final Cleaning	2 days	Wed 11/9/22	Fri 11/11/22	3192
3194	6019	NA	0%	OWNER Acceptance L 8 CORRIDORS	1 day	Fri 11/11/22	Mon 11/14/22	3193
3195	<b>6033</b>	<b>NA</b>	<b>0%</b>	<b>L 9 CORRIDORS</b>	<b>12 days</b>	<b>Wed 11/16/22</b>	<b>Fri 12/2/22</b>	
3196	6768	NA	0%	MEPS Finish Trim / FECs (FINISH WITH MEPS UNITS TRIM)	0 days	Wed 11/16/22	Wed 11/16/22	2706FF
3197	6035	NA	0%	Flooring (Carpet/Stone/Base) & Protection L9	3 days	Thu 11/17/22	Mon 11/21/22	3196
3198	6036	NA	0%	Doors and Hardware / Mag Hold Opens	1 day	Tue 11/22/22	Tue 11/22/22	3197
3199	6039	NA	0%	Signage	1 day	Mon 11/21/22	Tue 11/22/22	3197
3200	6040	NA	0%	Owners Punch	1 day	Tue 11/22/22	Wed 11/23/22	3199,3196,3197,3198
3201	6041	NA	0%	Subcontractor Complete Owner Punch	2 days	Wed 11/23/22	Fri 11/25/22	3200
3202	6042	NA	0%	Paint 2nd Coat Finish	2 days	Fri 11/25/22	Tue 11/29/22	3201
3203	6043	NA	0%	Final Cleaning	2 days	Tue 11/29/22	Thu 12/1/22	3202
3204	6044	NA	0%	OWNER Acceptance L 9 CORRIDORS	1 day	Thu 12/1/22	Fri 12/2/22	3203
3205	<b>6057</b>	<b>NA</b>	<b>0%</b>	<b>L 10 CORRIDORS</b>	<b>14.88 days</b>	<b>Tue 11/22/22</b>	<b>Mon 12/12/22</b>	
3206	6770	NA	0%	MEPS Finish Trim / FECs (FINISH WITH MEPS UNITS TRIM)	0 days	Wed 11/30/22	Wed 11/30/22	2789FF
3207	6059	NA	0%	Flooring (Carpet/Stone/Base) & Protection L10	3 days	Tue 11/22/22	Mon 11/28/22	3197
3208	6060	NA	0%	Doors and Hardware / Mag Hold Opens	1 day	Tue 11/29/22	Tue 11/29/22	3207
3209	6063	NA	0%	Signage	1 day	Mon 11/28/22	Tue 11/29/22	3207
3210	6064	NA	0%	Owners Punch	1 day	Wed 11/30/22	Thu 12/1/22	3209,3206,3207,3208
3211	6065	NA	0%	Subcontractor Complete Owner Punch	2 days	Thu 12/1/22	Mon 12/5/22	3210
3212	6066	NA	0%	Paint 2nd Coat Finish	2 days	Mon 12/5/22	Wed 12/7/22	3211
3213	6067	NA	0%	Final Cleaning	2 days	Wed 12/7/22	Fri 12/9/22	3212
3214	6068	NA	0%	OWNER Acceptance L 10 CORRIDORS	1 day	Fri 12/9/22	Mon 12/12/22	3213
3215	<b>6081</b>	<b>NA</b>	<b>0%</b>	<b>L 11 CORRIDORS</b>	<b>20.88 days</b>	<b>Tue 11/29/22</b>	<b>Tue 12/27/22</b>	

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
3216	6772	NA	0%	MEPS Finish Trim / FECs (FINISH WITH MEPS UNITS TRIM)	0 days	Wed 12/14/22	Wed 12/14/22	2872FF
3217	6083	NA	0%	Flooring (Carpet/Stone/Base) & Protection L11	3 days	Tue 11/29/22	Thu 12/1/22	3207
3218	6084	NA	0%	Doors and Hardware / Mag Hold Opens	1 day	Fri 12/2/22	Fri 12/2/22	3217
3219	6087	NA	0%	Signage	1 day	Thu 12/1/22	Fri 12/2/22	3217
3220	6088	NA	0%	Owners Punch	1 day	Wed 12/14/22	Thu 12/15/22	3219,3216,3217,3218
3221	6089	NA	0%	Subcontractor Complete Owner Punch	2 days	Thu 12/15/22	Mon 12/19/22	3220
3222	6090	NA	0%	Paint 2nd Coat Finish	3 days	Mon 12/19/22	Thu 12/22/22	3221
3223	6091	NA	0%	Final Cleaning	2 days	Thu 12/22/22	Mon 12/26/22	3222
3224	6092	NA	0%	OWNER Acceptance L 11 CORRIDORS	1 day	Mon 12/26/22	Tue 12/27/22	3223
3225	<b>6105</b>	<b>NA</b>	<b>0%</b>	<b>L 12 CORRIDORS</b>	<b>27.88 days</b>	<b>Fri 12/2/22</b>	<b>Mon 1/9/23</b>	
3226	6774	NA	0%	MEPS Finish Trim / FECs (FINISH WITH MEPS UNITS TRIM)	0 days	Wed 12/28/22	Wed 12/28/22	2955FF
3227	6107	NA	0%	Flooring (Carpet/Stone/Base) & Protection L12	3 days	Fri 12/2/22	Tue 12/6/22	3217
3228	6108	NA	0%	Doors and Hardware / Mag Hold Opens	1 day	Wed 12/7/22	Wed 12/7/22	3227
3229	6111	NA	0%	Signage	1 day	Tue 12/6/22	Wed 12/7/22	3227
3230	6112	NA	0%	Owners Punch	1 day	Wed 12/28/22	Thu 12/29/22	3229,3226
3231	6113	NA	0%	Subcontractor Complete Owner Punch	2 days	Thu 12/29/22	Mon 1/2/23	3230
3232	6114	NA	0%	Paint 2nd Coat Finish	3 days	Mon 1/2/23	Thu 1/5/23	3231
3233	6115	NA	0%	Final Cleaning	2 days	Thu 1/5/23	Sat 1/7/23	3232
3234	6116	NA	0%	OWNER Acceptance L 12 CORRIDORS	1 day	Sat 1/7/23	Mon 1/9/23	3233
3235	<b>6129</b>	<b>NA</b>	<b>0%</b>	<b>L 13 CORRIDORS</b>	<b>35.88 days</b>	<b>Wed 12/7/22</b>	<b>Tue 1/24/23</b>	
3236	6776	NA	0%	MEPS Finish Trim / FECs (FINISH WITH MEPS UNITS TRIM)	0 days	Wed 1/11/23	Wed 1/11/23	3038FF
3237	6131	NA	0%	Flooring (Carpet/Stone/Base) & Protection L13	3 days	Wed 12/7/22	Fri 12/9/22	3227
3238	6132	NA	0%	Doors and Hardware / Mag Hold Opens	1 day	Mon 12/12/22	Mon 12/12/22	3237
3239	6135	NA	0%	Signage	1 day	Fri 12/9/22	Mon 12/12/22	3237
3240	6136	NA	0%	Owners Punch	1 day	Wed 1/11/23	Thu 1/12/23	3239,3238,3237,3236
3241	6137	NA	0%	Subcontractor Complete Owner Punch	2 days	Thu 1/12/23	Mon 1/16/23	3240
3242	6138	NA	0%	Paint 2nd Coat Finish	3 days	Mon 1/16/23	Thu 1/19/23	3241
3243	6139	NA	0%	Final Cleaning	2 days	Thu 1/19/23	Mon 1/23/23	3242
3244	6140	NA	0%	OWNER Acceptance L 13 CORRIDORS	1 day	Mon 1/23/23	Tue 1/24/23	3243
3245	<b>6153</b>	<b>NA</b>	<b>0%</b>	<b>L 14 CORRIDORS</b>	<b>43.88 days</b>	<b>Mon 12/12/22</b>	<b>Wed 2/8/23</b>	
3246	6778	NA	0%	MEPS Finish Trim / FECs (FINISH WITH MEPS UNITS TRIM)	0 days	Fri 1/27/23	Fri 1/27/23	3121FF
3247	6155	NA	0%	Flooring EVENING (Carpet/Stone/Base) & Protection L14	3 days	Mon 12/12/22	Wed 12/14/22	3237
3248	6156	NA	0%	Doors and Hardware / Mag Hold Opens L14	1 day	Wed 12/14/22	Wed 12/14/22	3247FF
3249	6159	NA	0%	Signage	1 day	Tue 12/13/22	Wed 12/14/22	3247FF
3250	10458	NA	0%	Prepare Corridors for State Elevator Inspector Cars #2,#3,#4,#5	5 days	Thu 12/15/22	Wed 12/21/22	3249
3251	6160	NA	0%	Owners Punch	1 day	Fri 1/27/23	Mon 1/30/23	3249,3246,3247,3248
3252	6161	NA	0%	Subcontractor Complete Owner Punch	2 days	Mon 1/30/23	Wed 2/1/23	3251
3253	6162	NA	0%	Paint 2nd Coat Finish L 14 CORRIDORS	2 days	Wed 2/1/23	Fri 2/3/23	3252
3254	6163	NA	0%	Final Cleaning	2 days	Fri 2/3/23	Tue 2/7/23	3253
3255	6164	NA	0%	OWNER Acceptance L 14 CORRIDOR	1 day	Tue 2/7/23	Wed 2/8/23	3254
3256	10425	NA	0%	<b>CORRIDOR &amp; ELEVATOR LOBBY OWNER ACCEPTANCE</b>	1 day	Tue 2/7/23	Wed 2/8/23	3255FF,3244FF,3234FF,3224FF
3257	<b>6862</b>	<b>NA</b>	<b>0%</b>	<b>MAN LIFT UNITS MCALLISTER &amp; HYDE ST</b>	<b>113 days</b>	<b>Tue 8/16/22</b>	<b>Thu 1/19/23</b>	
3258	<b>6861</b>	<b>NA</b>	<b>0%</b>	<b>MCALLISTER ST</b>	<b>107 days</b>	<b>Tue 8/16/22</b>	<b>Wed 1/11/23</b>	
3259	<b>6866</b>	<b>NA</b>	<b>0%</b>	<b>Level L3-L8 (12 UNITS)</b>	<b>102 days</b>	<b>Tue 8/16/22</b>	<b>Thu 1/5/23</b>	
3260	6867	NA	0%	Man Lift Down	18 days	Tue 8/16/22	Fri 9/9/22	286FF
3261	7187	NA	0%	INFILL BAY MANLIFT 2 MCALLISTER ST	10 days	Fri 9/9/22	Fri 9/23/22	286,3260
3262	6868	NA	0%	Temp Loading Dock Removed	0 days	Fri 9/9/22	Fri 9/9/22	3260

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
3263	6869	NA	0%	Terminate Below Grade Waterproofing	2 days	Fri 9/9/22	Tue 9/13/22	3262
3264	<b>6872</b>	<b>NA</b>	<b>0%</b>	<b>MEPS Rough/Rock and Tape</b>	<b>23 days</b>	<b>Fri 9/23/22</b>	<b>Thu 10/27/22</b>	
3265	6873	NA	0%	Frame Walls/Ceilings	4 days	Fri 9/23/22	Thu 9/29/22	3560,3261
3266	6874	NA	0%	Install Entry Door Frame	2 days	Thu 9/29/22	Mon 10/3/22	3265
3267	6875	NA	0%	MEPS Walls/Ceilings	4 days	Thu 9/29/22	Wed 10/5/22	3265
3268	6876	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Wed 10/5/22	Thu 10/6/22	3267
3269	6877	NA	0%	Insulate Walls	1 day	Thu 10/6/22	Fri 10/7/22	3268
3270	6878	NA	0%	Hang Drywall	4 days	Thu 10/6/22	Thu 10/13/22	3269FS-1 day
3271	6879	NA	0%	Tape	10 days	Thu 10/13/22	Thu 10/27/22	3270
3272	<b>6880</b>	<b>NA</b>	<b>0%</b>	<b>Finishes</b>	<b>31 days</b>	<b>Thu 10/27/22</b>	<b>Wed 12/14/22</b>	
3273	6881	NA	0%	Install Interior Door Frames	4 days	Thu 10/27/22	Wed 11/2/22	3271
3274	6882	NA	0%	Install Unit Entry Doors/Hardware	2 days	Mon 10/31/22	Wed 11/2/22	3273FF
3275	6883	NA	0%	Prime Paint/1ST COAT PAINT	4 days	Wed 11/2/22	Tue 11/8/22	3271,3273
3276	6884	NA	0%	Install WP Redgard at Tube/Shower Walls & Floors	2 days	Tue 11/8/22	Thu 11/10/22	3275
3277	6885	NA	0%	Flood Test Shower Pans	1 day	Thu 11/10/22	Mon 11/14/22	3276
3278	6886	NA	0%	Install Cabinets/Trim	4 days	Tue 11/8/22	Tue 11/15/22	3273,3275
3279	6890	NA	0%	Install Tile flooring/Base	4 days	Tue 11/15/22	Mon 11/21/22	3277,3278
3280	6888	NA	0%	Install Kitchen Stone Countertops	2 days	Fri 11/18/22	Tue 11/22/22	3278FS+3 days
3281	6889	NA	0%	Install Stone Backsplash at Kitchen Counters	2 days	Tue 11/22/22	Mon 11/28/22	3280
3282	6891	NA	0%	Install Stone Entry Threshold & Protection	2 days	Tue 11/22/22	Mon 11/28/22	3280FF,3281FF
3283	6892	NA	0%	Install Vanities/Medicine Cabinets	2 days	Mon 11/21/22	Wed 11/23/22	3279
3284	6893	NA	0%	Install Vanity Countertops	2 days	Mon 11/28/22	Wed 11/30/22	3278SS,3280FF,3283FS+1 day
3285	6894	NA	0%	Install Unit Flooring & Base	4 days	Mon 11/28/22	Fri 12/2/22	3278,3282
3286	6895	NA	0%	Install Window Blinds	2 days	Fri 12/2/22	Tue 12/6/22	3285
3287	6896	NA	0%	Install Appliances	2 days	Fri 12/2/22	Tue 12/6/22	3280,3285
3288	6976	NA	0%	Install Appliance Panels	2 days	Fri 12/2/22	Tue 12/6/22	3287FF
3289	6900	NA	0%	Install MEPS Trim Man Lift Units MCALLISTER LEVELS 3-8	4 days	Tue 12/6/22	Mon 12/12/22	3284,3287
3290	6901	NA	0%	Install Bathroom Accessories/Mirrors/Tube/Shower Enclosures	2 days	Mon 12/12/22	Wed 12/14/22	3289
3291	6902	NA	0%	LOCK DOORS	0 days	Wed 12/14/22	Wed 12/14/22	3290
3292	<b>6979</b>	<b>NA</b>	<b>0%</b>	<b>PUNCH/CLEANING &amp; UNIT ACCEPTANCE</b>	<b>14 days</b>	<b>Wed 12/14/22</b>	<b>Thu 1/5/23</b>	
3293	6980	NA	0%	BG Pre-Punch List	1 day	Wed 12/14/22	Thu 12/15/22	3291
3294	6981	NA	0%	Subcontractor Complete Pre-Punch List	2 days	Thu 12/15/22	Mon 12/19/22	3293
3295	6982	NA	0%	Rough Cleaning	2 days	Mon 12/19/22	Wed 12/21/22	3294
3296	6983	NA	0%	Owners Punch	1 day	Wed 12/21/22	Thu 12/22/22	3295
3297	6984	NA	0%	Subcontractor Complete Owner Punch	2 days	Thu 12/22/22	Tue 12/27/22	3296
3298	6985	NA	0%	Paint 2nd Coat Finish	4 days	Tue 12/27/22	Mon 1/2/23	3297
3299	6986	NA	0%	Final Cleaning	2 days	Mon 1/2/23	Wed 1/4/23	3298
3300	6987	NA	0%	Unit Acceptance Level L3-L8 (12 UNITS) MCALLISTER ST	1 day	Wed 1/4/23	Thu 1/5/23	3299
3301	<b>6988</b>	<b>NA</b>	<b>0%</b>	<b>Level L9-L14 (12 UNITS)</b>	<b>68 days</b>	<b>Thu 9/29/22</b>	<b>Wed 1/11/23</b>	
3302	<b>7069</b>	<b>NA</b>	<b>0%</b>	<b>MEPS Rough/Rock and Tape</b>	<b>23 days</b>	<b>Thu 9/29/22</b>	<b>Wed 11/2/22</b>	
3303	7070	NA	0%	Frame Walls/Ceilings	4 days	Thu 9/29/22	Wed 10/5/22	3265
3304	7071	NA	0%	Install Entry Door Frame	2 days	Wed 10/5/22	Fri 10/7/22	3303
3305	7072	NA	0%	MEPS Walls/Ceilings	4 days	Wed 10/5/22	Wed 10/12/22	3303
3306	7073	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Wed 10/12/22	Thu 10/13/22	3305
3307	7074	NA	0%	Insulate Walls	1 day	Thu 10/13/22	Fri 10/14/22	3306
3308	7075	NA	0%	Hang Drywall	4 days	Thu 10/13/22	Wed 10/19/22	3307FS-1 day
3309	7076	NA	0%	Tape	10 days	Wed 10/19/22	Wed 11/2/22	3308

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
3310	<b>7077</b>	<b>NA</b>	<b>0%</b>	<b>Finishes</b>	<b>31 days</b>	<b>Wed 11/2/22</b>	<b>Tue 12/20/22</b>	
3311	7078	NA	0%	Install Interior Door Frames	4 days	Wed 11/2/22	Tue 11/8/22	3309
3312	7079	NA	0%	Install Unit Entry Doors/Hardware	2 days	Fri 11/4/22	Tue 11/8/22	3311FF
3313	7080	NA	0%	Prime Paint/1ST COAT PAINT	4 days	Tue 11/8/22	Tue 11/15/22	3309,3311
3314	7081	NA	0%	Install WP Redgard at Tube/Shower Walls & Floors	2 days	Tue 11/15/22	Thu 11/17/22	3313
3315	7082	NA	0%	Flood Test Shower Pans	1 day	Thu 11/17/22	Fri 11/18/22	3314
3316	7083	NA	0%	Install Cabinets/Trim	4 days	Tue 11/15/22	Mon 11/21/22	3311,3313
3317	7084	NA	0%	Install Tile flooring/Base	4 days	Mon 11/21/22	Tue 11/29/22	3315,3316
3318	7085	NA	0%	Install Kitchen Stone Countertops	2 days	Mon 11/28/22	Wed 11/30/22	3316FS+3 days
3319	7086	NA	0%	Install Stone Backsplash at Kitchen Counters	2 days	Wed 11/30/22	Fri 12/2/22	3318
3320	7087	NA	0%	Install Stone Entry Threshold & Protection	2 days	Wed 11/30/22	Fri 12/2/22	3318FF,3319FF
3321	7088	NA	0%	Install Vanities/Medicine Cabinets	2 days	Tue 11/29/22	Thu 12/1/22	3317
3322	7089	NA	0%	Install Vanity Countertops	2 days	Fri 12/2/22	Tue 12/6/22	3316SS,3318FF,3321FS+1 day
3323	7090	NA	0%	Install Unit Flooring & Base	4 days	Fri 12/2/22	Thu 12/8/22	3316,3320
3324	7091	NA	0%	Install Window Blinds	2 days	Thu 12/8/22	Mon 12/12/22	3323
3325	7092	NA	0%	Install Appliances	2 days	Thu 12/8/22	Mon 12/12/22	3318,3323
3326	7093	NA	0%	Install Appliance Panels	2 days	Thu 12/8/22	Mon 12/12/22	3325FF
3327	7094	NA	0%	Install MEPS Trim Man Lift Units MCALLISTER LEVELS 9-14	4 days	Mon 12/12/22	Fri 12/16/22	3322,3325
3328	7095	NA	0%	Install Bathroom Accessories/Mirrors/Tube/Shower Enclosures	2 days	Fri 12/16/22	Tue 12/20/22	3327
3329	7096	NA	0%	LOCK DOORS	0 days	Tue 12/20/22	Tue 12/20/22	3328
3330	<b>7097</b>	<b>NA</b>	<b>0%</b>	<b>PUNCH/CLEANING &amp; UNIT ACCEPTANCE</b>	<b>14 days</b>	<b>Tue 12/20/22</b>	<b>Wed 1/11/23</b>	
3331	7098	NA	0%	BG Pre-Punch List	1 day	Tue 12/20/22	Wed 12/21/22	3329
3332	7099	NA	0%	Subcontractor Complete Pre-Punch List	2 days	Wed 12/21/22	Fri 12/23/22	3331
3333	7100	NA	0%	Rough Cleaning	2 days	Fri 12/23/22	Wed 12/28/22	3332
3334	7101	NA	0%	Owners Punch	1 day	Wed 12/28/22	Thu 12/29/22	3333
3335	7102	NA	0%	Subcontractor Complete Owner Punch	2 days	Thu 12/29/22	Tue 1/3/23	3334
3336	7103	NA	0%	Paint 2nd Coat Finish	4 days	Tue 1/3/23	Sat 1/7/23	3335
3337	7104	NA	0%	Final Cleaning	2 days	Sat 1/7/23	Tue 1/10/23	3336
3338	7105	NA	0%	Unit Acceptance Level L9-L14 (12 UNITS) MCALLISTER ST	1 day	Tue 1/10/23	Wed 1/11/23	3337
3339	<b>6860</b>	<b>NA</b>	<b>0%</b>	<b>HYDE ST</b>	<b>107 days</b>	<b>Wed 8/24/22</b>	<b>Thu 1/19/23</b>	
3340	<b>7108</b>	<b>NA</b>	<b>0%</b>	<b>Level L3-L8 (12 UNITS)</b>	<b>102 days</b>	<b>Wed 8/24/22</b>	<b>Thu 1/12/23</b>	
3341	7109	NA	0%	Man Lift Down	17 days	Wed 8/24/22	Fri 9/16/22	308FF
3342	7189	NA	0%	INFILL BAY MANLIFT 1 HYDE ST	10 days	Fri 9/16/22	Fri 9/30/22	308,3341
3343	7110	NA	0%	Temp Loading Dock Removed	0 days	Fri 9/16/22	Fri 9/16/22	3341
3344	7111	NA	0%	Terminate Below Grade Waterproofing	2 days	Fri 9/16/22	Tue 9/20/22	3343
3345	<b>7112</b>	<b>NA</b>	<b>0%</b>	<b>MEPS Rough/Rock and Tape</b>	<b>23 days</b>	<b>Fri 9/30/22</b>	<b>Thu 11/3/22</b>	
3346	7113	NA	0%	Frame Walls/Ceilings	4 days	Fri 9/30/22	Thu 10/6/22	3342
3347	7114	NA	0%	Install Entry Door Frame	2 days	Thu 10/6/22	Tue 10/11/22	3346
3348	7115	NA	0%	MEPS Walls/Ceilings	4 days	Thu 10/6/22	Thu 10/13/22	3346
3349	7116	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Thu 10/13/22	Fri 10/14/22	3348
3350	7117	NA	0%	Insulate Walls	1 day	Fri 10/14/22	Mon 10/17/22	3349
3351	7118	NA	0%	Hang Drywall	4 days	Fri 10/14/22	Thu 10/20/22	3350FS-1 day
3352	7119	NA	0%	Tape	10 days	Thu 10/20/22	Thu 11/3/22	3351
3353	<b>7120</b>	<b>NA</b>	<b>0%</b>	<b>Finishes</b>	<b>31 days</b>	<b>Thu 11/3/22</b>	<b>Wed 12/21/22</b>	
3354	7121	NA	0%	Install Interior Door Frames	4 days	Thu 11/3/22	Wed 11/9/22	3352
3355	7122	NA	0%	Install Unit Entry Doors/Hardware	2 days	Mon 11/7/22	Wed 11/9/22	3354FF
3356	7123	NA	0%	Prime Paint/1ST COAT PAINT	4 days	Wed 11/9/22	Wed 11/16/22	3352,3354

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
3357	7124	NA	0%	Install WP Redgard at Tube/Shower Walls & Floors	2 days	Wed 11/16/22	Fri 11/18/22	3356
3358	7125	NA	0%	Flood Test Shower Pans	1 day	Fri 11/18/22	Mon 11/21/22	3357
3359	7126	NA	0%	Install Cabinets/Trim	4 days	Wed 11/16/22	Tue 11/22/22	3354,3356
3360	7127	NA	0%	Install Tile flooring/Base	4 days	Tue 11/22/22	Wed 11/30/22	3358,3359
3361	7128	NA	0%	Install Kitchen Stone Countertops	2 days	Tue 11/29/22	Thu 12/1/22	3359FS+3 days
3362	7129	NA	0%	Install Stone Backsplash at Kitchen Counters	2 days	Thu 12/1/22	Mon 12/5/22	3361
3363	7130	NA	0%	Install Stone Entry Threshold & Protection	2 days	Thu 12/1/22	Mon 12/5/22	3361FF,3362FF
3364	7131	NA	0%	Install Vanities/Medicine Cabinets	2 days	Wed 11/30/22	Fri 12/2/22	3360
3365	7132	NA	0%	Install Vanity Countertops	2 days	Mon 12/5/22	Wed 12/7/22	3359SS,3361FF,3364FS+1 day
3366	7133	NA	0%	Install Unit Flooring & Base	4 days	Mon 12/5/22	Fri 12/9/22	3359,3363
3367	7134	NA	0%	Install Window Blinds	2 days	Fri 12/9/22	Tue 12/13/22	3366
3368	7135	NA	0%	Install Appliances	2 days	Fri 12/9/22	Tue 12/13/22	3361,3366
3369	7136	NA	0%	Install Appliance Panels	2 days	Fri 12/9/22	Tue 12/13/22	3368FF
3370	7137	NA	0%	Install MEPS Trim Man Lift Units HYDE ST LEVEL 3 - 8	4 days	Tue 12/13/22	Mon 12/19/22	3365,3368
3371	7138	NA	0%	Install Bathroom Accessories/Mirrors/Tube/Shower Enclosures	2 days	Mon 12/19/22	Wed 12/21/22	3370
3372	7139	NA	0%	LOCK DOORS	0 days	Wed 12/21/22	Wed 12/21/22	3371
3373	<b>7140</b>	<b>NA</b>	<b>0%</b>	<b>PUNCH/CLEANING &amp; UNIT ACCEPTANCE</b>	<b>14 days</b>	<b>Wed 12/21/22</b>	<b>Thu 1/12/23</b>	
3374	7141	NA	0%	BG Pre-Punch List	1 day	Wed 12/21/22	Thu 12/22/22	3372
3375	7142	NA	0%	Subcontractor Complete Pre-Punch List	2 days	Thu 12/22/22	Tue 12/27/22	3374
3376	7143	NA	0%	Rough Cleaning	2 days	Tue 12/27/22	Thu 12/29/22	3375
3377	7144	NA	0%	Owners Punch	1 day	Thu 12/29/22	Fri 12/30/22	3376
3378	7145	NA	0%	Subcontractor Complete Owner Punch	2 days	Fri 12/30/22	Wed 1/4/23	3377
3379	7146	NA	0%	Paint 2nd Coat Finish	4 days	Wed 1/4/23	Mon 1/9/23	3378
3380	7147	NA	0%	Final Cleaning	2 days	Mon 1/9/23	Wed 1/11/23	3379
3381	7148	NA	0%	Unit Acceptance Level L3-L8 (12 UNITS) HYDE ST	1 day	Wed 1/11/23	Thu 1/12/23	3380
3382	<b>7149</b>	<b>NA</b>	<b>0%</b>	<b>Level L9-L14 (12 UNITS)</b>	<b>69 days</b>	<b>Thu 10/6/22</b>	<b>Thu 1/19/23</b>	
3383	<b>7150</b>	<b>NA</b>	<b>0%</b>	<b>MEPS Rough/Rock and Tape</b>	<b>23 days</b>	<b>Thu 10/6/22</b>	<b>Wed 11/9/22</b>	
3384	7151	NA	0%	Frame Walls/Ceilings	4 days	Thu 10/6/22	Thu 10/13/22	3346
3385	7152	NA	0%	Install Entry Door Frame	2 days	Thu 10/13/22	Mon 10/17/22	3384
3386	7153	NA	0%	MEPS Walls/Ceilings	4 days	Thu 10/13/22	Wed 10/19/22	3384
3387	7154	NA	0%	INSPECTIONS (100% FIRECAULKED PENETRATIONS CEILINGS/SLABS)	1 day	Wed 10/19/22	Thu 10/20/22	3386
3388	7155	NA	0%	Insulate Walls	1 day	Thu 10/20/22	Fri 10/21/22	3387
3389	7156	NA	0%	Hang Drywall	4 days	Thu 10/20/22	Wed 10/26/22	3388FS-1 day
3390	7157	NA	0%	Tape	10 days	Wed 10/26/22	Wed 11/9/22	3389
3391	<b>7158</b>	<b>NA</b>	<b>0%</b>	<b>Finishes</b>	<b>31 days</b>	<b>Wed 11/9/22</b>	<b>Wed 12/28/22</b>	
3392	7159	NA	0%	Install Interior Door Frames	4 days	Wed 11/9/22	Wed 11/16/22	3390
3393	7160	NA	0%	Install Unit Entry Doors/Hardware	2 days	Mon 11/14/22	Wed 11/16/22	3392FF
3394	7161	NA	0%	Prime Paint/1ST COAT PAINT	4 days	Wed 11/16/22	Tue 11/22/22	3390,3392
3395	7162	NA	0%	Install WP Redgard at Tube/Shower Walls & Floors	2 days	Tue 11/22/22	Mon 11/28/22	3394
3396	7163	NA	0%	Flood Test Shower Pans	1 day	Mon 11/28/22	Tue 11/29/22	3395
3397	7164	NA	0%	Install Cabinets/Trim	4 days	Tue 11/22/22	Wed 11/30/22	3392,3394
3398	7165	NA	0%	Install Tile flooring/Base	4 days	Wed 11/30/22	Tue 12/6/22	3396,3397
3399	7166	NA	0%	Install Kitchen Stone Countertops	2 days	Mon 12/5/22	Wed 12/7/22	3397FS+3 days
3400	7167	NA	0%	Install Stone Backsplash at Kitchen Counters	2 days	Wed 12/7/22	Fri 12/9/22	3399
3401	7168	NA	0%	Install Stone Entry Threshold & Protection	2 days	Wed 12/7/22	Fri 12/9/22	3399FF,3400FF
3402	7169	NA	0%	Install Vanities/Medicine Cabinets	2 days	Tue 12/6/22	Thu 12/8/22	3398
3403	7170	NA	0%	Install Vanity Countertops	2 days	Fri 12/9/22	Tue 12/13/22	3397SS,3399FF,3402FS+1 day

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
3404	7171	NA	0%	Install Unit Flooring & Base	4 days	Fri 12/9/22	Thu 12/15/22	3397,3401
3405	7172	NA	0%	Install Window Blinds	2 days	Thu 12/15/22	Mon 12/19/22	3404
3406	7173	NA	0%	Install Appliances	2 days	Thu 12/15/22	Mon 12/19/22	3399,3404
3407	7174	NA	0%	Install Appliance Panels	2 days	Thu 12/15/22	Mon 12/19/22	3406FF
3408	7175	NA	0%	Install MEPS Trim Man Lift Units HYDE ST LEVEL 9 - 14	4 days	Mon 12/19/22	Fri 12/23/22	3403,3406
3409	7176	NA	0%	Install Bathroom Accessories/Mirrors/Tube/Shower Enclosures	2 days	Fri 12/23/22	Wed 12/28/22	3408
3410	7177	NA	0%	LOCK DOORS	0 days	Wed 12/28/22	Wed 12/28/22	3409
3411	<b>7178</b>	<b>NA</b>	<b>0%</b>	<b>PUNCH/CLEANING &amp; UNIT ACCEPTANCE</b>	<b>15 days</b>	<b>Wed 12/28/22</b>	<b>Thu 1/19/23</b>	
3412	7179	NA	0%	BG Pre-Punch List	1 day	Wed 12/28/22	Thu 12/29/22	3410
3413	7180	NA	0%	Subcontractor Complete Pre-Punch List	2 days	Thu 12/29/22	Tue 1/3/23	3412
3414	7181	NA	0%	Rough Cleaning	2 days	Tue 1/3/23	Thu 1/5/23	3413
3415	7182	NA	0%	Owners Punch	1 day	Thu 1/5/23	Fri 1/6/23	3414
3416	7183	NA	0%	Subcontractor Complete Owner Punch	2 days	Fri 1/6/23	Tue 1/10/23	3415
3417	7184	NA	0%	Paint 2nd Coat Finish	4 days	Tue 1/10/23	Mon 1/16/23	3416
3418	7185	NA	0%	Final Cleaning	2 days	Mon 1/16/23	Wed 1/18/23	3417
3419	7186	NA	0%	Unit Acceptance Level L9-L14 (12 UNITS) HYDE ST	1 day	Wed 1/18/23	Thu 1/19/23	3418
3420	10426	NA	0%	<b>MAN LIFT UNITS MCALLISTER &amp; HYDE ST OWNER ACCEPTANCE</b>	1 day	Wed 1/18/23	Thu 1/19/23	3419FF,3381FF,3338FF,3300FF
3421	<b>1910</b>	<b>NA</b>	<b>0%</b>	<b>EXTERIOR CONSTRUCTION</b>	<b>303.13 days</b>	<b>Mon 9/20/21</b>	<b>Thu 12/8/22</b>	
3422	1911	NA	0%	MOBILIZE CURTAINWALL	0 days	Thu 12/9/21	Thu 12/9/21	3441,879
3423	1913	NA	0%	MOBILIZE ROOFING	0 days	Tue 4/12/22	Tue 4/12/22	3570,3499
3424	1359	NA	0%	TOWER WEATHERTIGHT	0 days	Thu 8/4/22	Thu 8/4/22	3426,51,3631
3425	1819	NA	0%	CURTAINWALL COMPLETE	5 days	Fri 8/12/22	Thu 8/18/22	3557
3426	1915	NA	0%	ROOFING COMPLETE	0 days	Thu 8/4/22	Thu 8/4/22	3631
3427	1481	NA	0%	PODIUM WATERTIGHT	5 days	Thu 3/17/22	Wed 3/23/22	3444,3449,3463
3428	<b>1921</b>	<b>NA</b>	<b>0%</b>	<b>WATERPROOFING</b>	<b>306.13 days</b>	<b>Mon 9/20/21</b>	<b>Tue 11/22/22</b>	
3429	<b>1922</b>	<b>NA</b>	<b>0%</b>	<b>STORAGE TANKS</b>	<b>9.88 days</b>	<b>Mon 9/20/21</b>	<b>Fri 10/1/21</b>	
3430	1251	NA	0%	WATERPROOF CISTERN	5 days	Mon 9/27/21	Fri 10/1/21	3431
3431	1311	NA	0%	WATERPROOF FIRE TANK ROOM WALLS	5 days	Mon 9/20/21	Fri 9/24/21	696
3432	<b>1923</b>	<b>NA</b>	<b>0%</b>	<b>DECKS, COURTYARDS, PLANTERS</b>	<b>261.13 days</b>	<b>Mon 11/22/21</b>	<b>Tue 11/22/22</b>	
3433	1924	NA	0%	WATERPROOF COURTYARD CURBS & DECK	5 days	Fri 12/10/21	Thu 12/16/21	3785,879
3434	1926	NA	0%	WATERPROOF COURTYARD DECK & PLANTERS	5 days	Mon 11/7/22	Tue 11/15/22	3788,3787
3435	1413	NA	0%	COURTYARD PEDESTALS & PAVERS	5 days	Tue 11/15/22	Tue 11/22/22	3434
3436	1929	NA	0%	WATERPROOF DOG RUN PLANTERS	5 days	Wed 5/18/22	Tue 5/24/22	3776
3437	1931	NA	0%	WATERPROOF LEVEL 7 TERRACE DECK & CURBS	5 days	Fri 5/6/22	Fri 5/13/22	3575
3438	1933	NA	0%	LEVEL 7 TERRACE PEDESTALS & PAVERS	5 days	Fri 5/13/22	Fri 5/20/22	3437
3439	1934	NA	0%	WATERPROOF DOGRUN SUBSTRAIT	5 days	Mon 11/22/21	Tue 11/30/21	928
3440	1614	NA	0%	WATERPROOF CRANE BLOCKOUT	5 days	Mon 10/17/22	Mon 10/24/22	256
3441	1912	NA	0%	WATERPROOF MCALLISTER PLANTER	5 days	Fri 12/3/21	Thu 12/9/21	879
3442	<b>1937</b>	<b>NA</b>	<b>0%</b>	<b>EXITS &amp; ENTRANCES</b>	<b>41.88 days</b>	<b>Tue 1/18/22</b>	<b>Wed 3/16/22</b>	
3443	1938	NA	0%	WATERPROOF LEVEL 1 EXITS	5 days	Tue 1/18/22	Mon 1/24/22	3463
3444	1918	NA	0%	WATERPROOF LEVEL 2 EXITS	5 days	Thu 3/10/22	Wed 3/16/22	3456,3445
3445	1940	NA	0%	WATERPROOF LOADING DOCK	5 days	Tue 1/25/22	Mon 1/31/22	3443
3446	<b>1941</b>	<b>NA</b>	<b>0%</b>	<b>RAINSCREEN WALLS</b>	<b>145.13 days</b>	<b>Fri 12/3/21</b>	<b>Fri 6/24/22</b>	
3447	1942	NA	0%	FRAME, SHEATHE, INSPECT	40 days	Fri 12/10/21	Tue 2/8/22	999FF,992FF,3448,1013FF,102
3448	1943	NA	0%	ERECT SCAFFOLD	5 days	Fri 12/3/21	Thu 12/9/21	928,879
3449	1919	NA	0%	WATERPROOF MEMBRANE, FLOOD TEST	20 days	Wed 2/9/22	Wed 3/9/22	3447
3450	1361	NA	0%	COMPLETE RAINSCREEN	40 days	Wed 4/13/22	Wed 6/8/22	3449,3499

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
3451	1944	NA	0%	DISMANTLE SCAFFOLD	5 days	Thu 6/9/22	Wed 6/15/22	3450
3452	1945	NA	0%	ENCLOSE, WATERPROOF ROOF STRUCTURE	20 days	Thu 5/26/22	Fri 6/24/22	1660
3453	<b>1946</b>	<b>NA</b>	<b>0%</b>	<b>EXTERIOR PANELS</b>	<b>210.13 days</b>	<b>Fri 12/10/21</b>	<b>Fri 9/30/22</b>	
3454	<b>1947</b>	<b>NA</b>	<b>0%</b>	<b>LAYOUT &amp; PREP</b>	<b>134.88 days</b>	<b>Fri 12/10/21</b>	<b>Thu 6/16/22</b>	
3455	62	NA	0%	LAYOUT/PREP PANELS L1 TO L3 (10 DAYS/LEVEL)	20 days	Fri 12/10/21	Mon 1/10/22	3422
3456	1939	NA	0%	LAYOUT/PREP PANELS - LEVEL 3 TO LEVEL 7	40 days	Tue 1/11/22	Wed 3/9/22	3455,970
3457	1950	NA	0%	LAYOUT/PREP PANELS - LEVEL 7 TO LEVEL 11	32 days	Thu 3/10/22	Fri 4/22/22	1078,3456
3458	1949	NA	0%	LAYOUT/PREP PANELS - LEVEL 11 TO LEVEL 13	20 days	Mon 4/25/22	Fri 5/20/22	3457,1274
3459	1948	NA	0%	LAYOUT/PREP PANELS - LEVEL 13 TO ROOF	18 days	Mon 5/23/22	Thu 6/16/22	3458,1361,1406FF
3460	1952	NA	0%	LAYOUT/PREP PANELS - LEVEL 15 STRUCTURES	5 days	Thu 5/26/22	Fri 6/3/22	1638
3461	<b>1953</b>	<b>NA</b>	<b>0%</b>	<b>INSTALL PANELS (10 DAYS/LEVEL)</b>	<b>156.88 days</b>	<b>Mon 1/3/22</b>	<b>Tue 8/9/22</b>	
3462	<b>7583</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 1 - LEVEL 2</b>	<b>13.88 days</b>	<b>Mon 1/3/22</b>	<b>Thu 1/20/22</b>	
3463	152	NA	0%	INSTALL,SECURE PANELS L1 TO L2	10 days	Mon 1/3/22	Fri 1/14/22	3455FS-6 days,989FF,1010FF
3464	7576	NA	0%	FIRESAFE SLAB EDGE	1 day	Tue 1/18/22	Tue 1/18/22	3463
3465	10441	NA	0%	INSPECTIONS FIRESAFE (AM INSPECTION)	1 day	Wed 1/19/22	Wed 1/19/22	3464
3466	7577	NA	0%	FIRE MUD ON TOP OF FIRESAFING	1 day	Wed 1/19/22	Wed 1/19/22	3464,3465SS
3467	7578	NA	0%	INSPEC. FIRE MUD ON TOP OF FIRE SAFE SLAB EDGE L1	1 day	Thu 1/20/22	Thu 1/20/22	3466
3468	<b>8170</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 2</b>	<b>12.88 days</b>	<b>Tue 1/18/22</b>	<b>Thu 2/3/22</b>	
3469	8171	NA	0%	<b>INSTALL L2 PANELS</b>	10 days	Tue 1/18/22	Mon 1/31/22	3463,1053FF,1032FF
3470	8172	NA	0%	FIRESAFE SLAB EDGE	1 day	Tue 2/1/22	Tue 2/1/22	3469
3471	10442	NA	0%	INSPECTIONS FIRESAFE (AM INSPECTION)	1 day	Wed 2/2/22	Wed 2/2/22	3470
3472	8173	NA	0%	FIRE MUD ON TOP OF FIRESAFING	1 day	Wed 2/2/22	Wed 2/2/22	3471SS
3473	8174	NA	0%	INSPEC. FIRE MUD ON TOP OF FIRE SAFE SLAB EDGE L2	1 day	Thu 2/3/22	Thu 2/3/22	3472
3474	<b>7584</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 3</b>	<b>12.88 days</b>	<b>Tue 2/1/22</b>	<b>Thu 2/17/22</b>	
3475	6782	NA	0%	INSTALL L3 PANELS	10 days	Tue 2/1/22	Mon 2/14/22	3469
3476	7580	NA	0%	FIRESAFE SLAB EDGE	1 day	Tue 2/15/22	Tue 2/15/22	3475
3477	10443	NA	0%	INSPECTIONS FIRESAFE (AM INSPECTION)	1 day	Wed 2/16/22	Wed 2/16/22	3476
3478	7581	NA	0%	FIRE MUD ON TOP OF FIRESAFING	1 day	Wed 2/16/22	Wed 2/16/22	3477SS
3479	7582	NA	0%	INSPEC. FIRE MUD ON TOP OF FIRE SAFE SLAB EDGE L3	1 day	Thu 2/17/22	Thu 2/17/22	3478
3480	<b>7585</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 4</b>	<b>13.88 days</b>	<b>Tue 2/15/22</b>	<b>Fri 3/4/22</b>	
3481	6783	NA	0%	INSTALL L4 PANELS	10 days	Tue 2/15/22	Tue 3/1/22	3475
3482	7587	NA	0%	FIRESAFE SLAB EDGE	1 day	Wed 3/2/22	Wed 3/2/22	3481
3483	10444	NA	0%	INSPECTIONS FIRESAFE (AM INSPECTION)	1 day	Thu 3/3/22	Thu 3/3/22	3482
3484	7588	NA	0%	FIRE MUD ON TOP OF FIRESAFING	1 day	Thu 3/3/22	Thu 3/3/22	3483SS
3485	7589	NA	0%	INSPEC. FIRE MUD ON TOP OF FIRE SAFE SLAB EDGE L4	1 day	Fri 3/4/22	Fri 3/4/22	3484
3486	<b>7586</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 5</b>	<b>12.88 days</b>	<b>Wed 3/2/22</b>	<b>Fri 3/18/22</b>	
3487	6781	NA	0%	INSTALL L5 PANELS	10 days	Wed 3/2/22	Tue 3/15/22	3481
3488	7592	NA	0%	FIRESAFE SLAB EDGE	1 day	Wed 3/16/22	Wed 3/16/22	3487
3489	10445	NA	0%	INSPECTIONS FIRESAFE (AM INSPECTION)	1 day	Thu 3/17/22	Thu 3/17/22	3488
3490	7593	NA	0%	FIRE MUD ON TOP OF FIRESAFING	1 day	Thu 3/17/22	Thu 3/17/22	3489SS
3491	7594	NA	0%	INSPEC. FIRE MUD ON TOP OF FIRE SAFE SLAB EDGE L5	1 day	Fri 3/18/22	Fri 3/18/22	3490
3492	<b>7591</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 6</b>	<b>12.88 days</b>	<b>Wed 3/16/22</b>	<b>Fri 4/1/22</b>	
3493	6780	NA	0%	INSTALL L6 PANELS	10 days	Wed 3/16/22	Tue 3/29/22	3487
3494	7600	NA	0%	FIRESAFE SLAB EDGE	1 day	Wed 3/30/22	Wed 3/30/22	3493
3495	10446	NA	0%	INSPECTIONS FIRESAFE (AM INSPECTION)	1 day	Thu 3/31/22	Thu 3/31/22	3494
3496	7601	NA	0%	FIRE MUD ON TOP OF FIRESAFING	1 day	Thu 3/31/22	Thu 3/31/22	3495SS
3497	7602	NA	0%	INSPEC. FIRE MUD ON TOP OF FIRE SAFE SLAB EDGE L6	1 day	Fri 4/1/22	Fri 4/1/22	3496

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
3498	<b>7599</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 7</b>	<b>12.88 days</b>	<b>Wed 3/30/22</b>	<b>Fri 4/15/22</b>	
3499	6793	NA	0%	INSTALL L7 PANELS	10 days	Wed 3/30/22	Tue 4/12/22	3493
3500	7604	NA	0%	FIRESAFE SLAB EDGE	1 day	Wed 4/13/22	Wed 4/13/22	3499
3501	10447	NA	0%	INSPECTIONS FIRESAFE (AM INSPECTION)	1 day	Thu 4/14/22	Thu 4/14/22	3500
3502	7605	NA	0%	FIRE MUD ON TOP OF FIRESAFING	1 day	Thu 4/14/22	Thu 4/14/22	3501SS
3503	7606	NA	0%	INSPEC. FIRE MUD ON TOP OF FIRE SAFE SLAB EDGE L7	1 day	Fri 4/15/22	Fri 4/15/22	3502
3504	<b>7603</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 8</b>	<b>12.88 days</b>	<b>Wed 4/13/22</b>	<b>Fri 4/29/22</b>	
3505	6794	NA	0%	INSTALL L8 PANELS	10 days	Wed 4/13/22	Tue 4/26/22	3499
3506	7608	NA	0%	FIRESAFE SLAB EDGE	1 day	Wed 4/27/22	Wed 4/27/22	3505
3507	10448	NA	0%	INSPECTIONS FIRESAFE (AM INSPECTION)	1 day	Thu 4/28/22	Thu 4/28/22	3506
3508	7609	NA	0%	FIRE MUD ON TOP OF FIRESAFING	1 day	Thu 4/28/22	Thu 4/28/22	3507SS
3509	7610	NA	0%	INSPEC. FIRE MUD ON TOP OF FIRE SAFE SLAB EDGE L8	1 day	Fri 4/29/22	Fri 4/29/22	3508
3510	<b>7607</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 9</b>	<b>12.88 days</b>	<b>Wed 4/27/22</b>	<b>Fri 5/13/22</b>	
3511	6795	NA	0%	INSTALL L9 PANELS	10 days	Wed 4/27/22	Tue 5/10/22	3505
3512	7612	NA	0%	FIRESAFE SLAB EDGE	1 day	Wed 5/11/22	Wed 5/11/22	3511
3513	10449	NA	0%	INSPECTIONS FIRESAFE (AM INSPECTION)	1 day	Thu 5/12/22	Thu 5/12/22	3512
3514	7613	NA	0%	FIRE MUD ON TOP OF FIRESAFING	1 day	Thu 5/12/22	Thu 5/12/22	3513SS
3515	7614	NA	0%	INSPEC. FIRE MUD ON TOP OF FIRE SAFE SLAB EDGE L9	1 day	Fri 5/13/22	Fri 5/13/22	3514
3516	<b>7611</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 10</b>	<b>12.88 days</b>	<b>Wed 5/11/22</b>	<b>Fri 5/27/22</b>	
3517	6796	NA	0%	INSTALL L10 PANELS	10 days	Wed 5/11/22	Tue 5/24/22	3511
3518	7616	NA	0%	FIRESAFE SLAB EDGE	1 day	Wed 5/25/22	Wed 5/25/22	3517
3519	10450	NA	0%	INSPECTIONS FIRESAFE (AM INSPECTION)	1 day	Thu 5/26/22	Thu 5/26/22	3518
3520	7617	NA	0%	FIRE MUD ON TOP OF FIRESAFING	1 day	Thu 5/26/22	Thu 5/26/22	3519SS
3521	7618	NA	0%	INSPEC. FIRE MUD ON TOP OF FIRE SAFE SLAB EDGE L10	1 day	Fri 5/27/22	Fri 5/27/22	3520
3522	<b>7615</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 11</b>	<b>13.88 days</b>	<b>Wed 5/25/22</b>	<b>Mon 6/13/22</b>	
3523	6797	NA	0%	INSTALL L11 PANELS	10 days	Wed 5/25/22	Wed 6/8/22	3517
3524	7620	NA	0%	FIRESAFE SLAB EDGE	1 day	Thu 6/9/22	Thu 6/9/22	3523
3525	10451	NA	0%	INSPECTIONS FIRESAFE (AM INSPECTION)	1 day	Fri 6/10/22	Fri 6/10/22	3524
3526	7621	NA	0%	FIRE MUD ON TOP OF FIRESAFING	1 day	Fri 6/10/22	Fri 6/10/22	3525SS
3527	7622	NA	0%	INSPEC. FIRE MUD ON TOP OF FIRE SAFE SLAB EDGE L11	1 day	Mon 6/13/22	Mon 6/13/22	3526
3528	<b>7619</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 12</b>	<b>12.88 days</b>	<b>Thu 6/9/22</b>	<b>Mon 6/27/22</b>	
3529	6798	NA	0%	INSTALL L12 PANELS	10 days	Thu 6/9/22	Wed 6/22/22	3523
3530	7625	NA	0%	FIRESAFE SLAB EDGE	1 day	Thu 6/23/22	Thu 6/23/22	3529
3531	10452	NA	0%	INSPECTIONS FIRESAFE (AM INSPECTION)	1 day	Fri 6/24/22	Fri 6/24/22	3530
3532	7626	NA	0%	FIRE MUD ON TOP OF FIRESAFING	1 day	Fri 6/24/22	Fri 6/24/22	3531SS
3533	7627	NA	0%	INSPEC. FIRE MUD ON TOP OF FIRE SAFE SLAB EDGE L12	1 day	Mon 6/27/22	Mon 6/27/22	3532
3534	<b>7624</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 13</b>	<b>13.88 days</b>	<b>Thu 6/23/22</b>	<b>Tue 7/12/22</b>	
3535	6799	NA	0%	INSTALL L13 PANELS	10 days	Thu 6/23/22	Thu 7/7/22	3529
3536	7629	NA	0%	FIRESAFE SLAB EDGE	1 day	Fri 7/8/22	Fri 7/8/22	3535
3537	10453	NA	0%	INSPECTIONS FIRESAFE (AM INSPECTION)	1 day	Mon 7/11/22	Mon 7/11/22	3536
3538	7630	NA	0%	FIRE MUD ON TOP OF FIRESAFING	1 day	Mon 7/11/22	Mon 7/11/22	3537SS
3539	7631	NA	0%	INSPEC. FIRE MUD ON TOP OF FIRE SAFE SLAB EDGE L13	1 day	Tue 7/12/22	Tue 7/12/22	3538
3540	<b>7628</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 14</b>	<b>12.88 days</b>	<b>Fri 7/8/22</b>	<b>Tue 7/26/22</b>	
3541	6800	NA	0%	INSTALL L14 PANELS	10 days	Fri 7/8/22	Thu 7/21/22	3535
3542	7633	NA	0%	FIRESAFE SLAB EDGE	1 day	Fri 7/22/22	Fri 7/22/22	3541
3543	10454	NA	0%	INSPECTIONS FIRESAFE (AM INSPECTION)	1 day	Mon 7/25/22	Mon 7/25/22	3542
3544	7634	NA	0%	FIRE MUD ON TOP OF FIRESAFING	1 day	Mon 7/25/22	Mon 7/25/22	3543SS



University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
3545	7635	NA	0%	INSPEC. FIRE MUD ON TOP OF FIRE SAFE SLAB EDGE L14	1 day	Tue 7/26/22	Tue 7/26/22	3544
3546	<b>7632</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 15</b>	<b>12.88 days</b>	<b>Fri 7/22/22</b>	<b>Tue 8/9/22</b>	
3547	6801	NA	0%	INSTALL L15 PANELS	10 days	Fri 7/22/22	Thu 8/4/22	3541
3548	7637	NA	0%	FIRESAFE SLAB EDGE	1 day	Fri 8/5/22	Fri 8/5/22	3547
3549	10455	NA	0%	INSPECTIONS FIRESAFE (AM INSPECTION)	1 day	Mon 8/8/22	Mon 8/8/22	3548
3550	7638	NA	0%	FIRE MUD ON TOP OF FIRESAFING	1 day	Mon 8/8/22	Mon 8/8/22	3549SS
3551	7639	NA	0%	INSPEC. FIRE MUD ON TOP OF FIRE SAFE SLAB EDGE L15 (? PARAPET FRAM	1 day	Tue 8/9/22	Tue 8/9/22	3550
3552	<b>1955</b>	<b>NA</b>	<b>0%</b>	<b>SEAL EXTERIOR</b>	<b>154.88 days</b>	<b>Tue 1/18/22</b>	<b>Mon 8/22/22</b>	
3553	1956	NA	0%	CAULK/SEAL PANELS - LEVEL 13 TO ROOF	12 days	Fri 8/5/22	Mon 8/22/22	3547
3554	1957	NA	0%	CAULK/SEAL PANELS - LEVEL 3 TO LEVEL 7	40 days	Wed 4/13/22	Wed 6/8/22	3499
3555	1958	NA	0%	CAULK/SEAL PANELS - LEVEL 7 TO LEVEL 11	32 days	Thu 6/9/22	Mon 7/25/22	3554
3556	1959	NA	0%	CAULK/SEAL PANELS - LEVEL 11 TO LEVEL 13	14 days	Tue 7/26/22	Fri 8/12/22	3555
3557	1917	NA	0%	CAULK/SEAL PANELS - LEVEL 15 STRUCTURES	5 days	Fri 8/5/22	Thu 8/11/22	3547
3558	1290	NA	0%	CAULK/SEAL PANELS L1 TO L3 (10 DAYS/LEVEL)	20 days	Tue 1/18/22	Mon 2/14/22	3463
3559	<b>1960</b>	<b>NA</b>	<b>0%</b>	<b>MANLIFT BAY</b>	<b>15 days</b>	<b>Fri 9/9/22</b>	<b>Fri 9/30/22</b>	
3560	155	NA	0%	INFILL BAY MANLIFT 2 MCALLISTER ST	10 days	Fri 9/9/22	Fri 9/23/22	286
3561	150	NA	0%	INFILL BAY MANLIFT 1 HYDE ST	10 days	Fri 9/16/22	Fri 9/30/22	308
3562	<b>1966</b>	<b>NA</b>	<b>0%</b>	<b>STOREFRONTS &amp; ENTRIES</b>	<b>171.13 days</b>	<b>Wed 4/13/22</b>	<b>Thu 12/8/22</b>	
3563	1967	NA	0%	STOREFRONT - MCALLISTER	20 days	Wed 4/13/22	Tue 5/10/22	3499
3564	1968	NA	0%	STOREFRONT - HYDE	20 days	Wed 4/20/22	Tue 5/17/22	1644,3563SS+40 hrs
3565	8390	NA	0%	GAS ALCOVE PERFORATED PANELS/DOOR/HARDWARE	5 days	Tue 5/17/22	Tue 5/24/22	3564
3566	1969	NA	0%	INSTALL ENTRY DOORS - MCALLISTER	5 days	Thu 12/1/22	Thu 12/8/22	2025,3805
3567	1971	NA	0%	INSTALL ENTRY DOORS - GOLDEN GATE	5 days	Mon 10/31/22	Mon 11/7/22	3568,3833
3568	1972	NA	0%	INSTALL STOREFRONT - GOLDEN GATE	5 days	Fri 9/16/22	Fri 9/23/22	308,286
3569	<b>1974</b>	<b>NA</b>	<b>0%</b>	<b>MISCELLANEOUS SHELL</b>	<b>102.13 days</b>	<b>Fri 12/17/21</b>	<b>Tue 5/10/22</b>	
3570	1914	NA	0%	GUARDRAILS- LEVEL 3	20 days	Fri 12/17/21	Tue 1/18/22	949
3571	1643	NA	0%	INSTALL COURTYARD SKYLIGHT	20 days	Fri 12/17/21	Tue 1/18/22	3433
3572	1975	NA	0%	INSTALL LOADING DOCK DOOR	5 days	Tue 1/18/22	Mon 1/24/22	3463
3573	1976	NA	0%	LEVEL 7 TERRACE GLASS RAIL SHOE	5 days	Fri 4/15/22	Fri 4/22/22	1361,1340
3574	1964	NA	0%	GUARDRAILS - LEVEL 13	5 days	Fri 4/29/22	Thu 5/5/22	1406
3575	1932	NA	0%	LEVEL 7 HANDRAIL	10 days	Fri 4/22/22	Fri 5/6/22	3573
3576	1962	NA	0%	GUARDRAILS - LEVEL 15	5 days	Tue 5/3/22	Tue 5/10/22	1448
3577	<b>1961</b>	<b>NA</b>	<b>0%</b>	<b>ROOFING</b>	<b>81.13 days</b>	<b>Wed 4/13/22</b>	<b>Thu 8/4/22</b>	
3578	1963	NA	0%	LEVEL 13 ROOF	20 days	Fri 5/6/22	Fri 6/3/22	3574
3579	1965	NA	0%	LEVEL 3 ROOF	10 days	Wed 4/13/22	Tue 4/26/22	3423
3580	8388	NA	0%	LEVEL 15 ROOF COMPLETE	0 days	Thu 8/4/22	Thu 8/4/22	3631
3581	<b>8389</b>	<b>NA</b>	<b>0%</b>	<b>L15 ROOF LOGISTICS</b>	<b>101 days</b>	<b>Tue 5/10/22</b>	<b>Mon 10/3/22</b>	
3582	<b>8287</b>	<b>NA</b>	<b>0%</b>	<b>Roof Top Equipment</b>	<b>17 days</b>	<b>Fri 5/13/22</b>	<b>Tue 6/7/22</b>	
3583	<b>8288</b>	<b>NA</b>	<b>0%</b>	<b>Install Supports/Framing Prior To Roofing</b>	<b>17 days</b>	<b>Fri 5/13/22</b>	<b>Tue 6/7/22</b>	
3584	8387	NA	0%	INSTALL PARAPET FRAMING/DENSGLOSS	15 days	Tue 5/17/22	Tue 6/7/22	3622
3585	<b>8295</b>	<b>NA</b>	<b>0%</b>	<b>MECHANICAL Support Frame</b>	<b>5 days</b>	<b>Tue 5/17/22</b>	<b>Tue 5/24/22</b>	
3586	8296	NA	0%	Install Support frame/Welding	5 days	Tue 5/17/22	Tue 5/24/22	3622
3587	<b>8306</b>	<b>NA</b>	<b>0%</b>	<b>Roofer</b>	<b>1 day</b>	<b>Fri 5/13/22</b>	<b>Mon 5/16/22</b>	
3588	8307	NA	0%	Roofer Provide All Roof Jacks for MEPS Contractors To Use One Piece Roof	1 day	Fri 5/13/22	Mon 5/16/22	3586SF-1 day
3589	<b>8308</b>	<b>NA</b>	<b>0%</b>	<b>MEPS Set Supports/Posts</b>	<b>5 days</b>	<b>Tue 5/24/22</b>	<b>Tue 5/31/22</b>	
3590	8311	NA	0%	Install Prefabricated MEPS Utility Curbs/Pads	2 days	Tue 5/24/22	Thu 5/26/22	3591SF-1 day
3591	8309	NA	0%	All Concrete Utility Pads/Curbs WP & FLASHED Complete	0 days	Fri 5/27/22	Fri 5/27/22	3625

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
3592	8310	NA	0%	MEPS Set Supports/Posts	2 days	Fri 5/27/22	Tue 5/31/22	3591
3593	<b>8312</b>	<b>NA</b>	<b>0%</b>	<b>Hoisting Prior To Roofing</b>	<b>36 days</b>	<b>Tue 5/10/22</b>	<b>Wed 6/29/22</b>	
3594	<b>8313</b>	<b>NA</b>	<b>0%</b>	<b>KONE</b>	<b>1 day</b>	<b>Tue 5/10/22</b>	<b>Wed 5/11/22</b>	
3595	8314	NA	0%	Hoist KONE Equipment /Tarp & Protection	1 day	Tue 5/10/22	Wed 5/11/22	3646SF-1 day
3596	<b>8317</b>	<b>NA</b>	<b>0%</b>	<b>Cupertino</b>	<b>1 day</b>	<b>Tue 5/10/22</b>	<b>Wed 5/11/22</b>	
3597	8318	NA	0%	Hoist EQUIPMENT	1 day	Tue 5/10/22	Wed 5/11/22	3646SF-1 day
3598	<b>8319</b>	<b>NA</b>	<b>0%</b>	<b>OLSEN</b>	<b>1 day</b>	<b>Thu 5/12/22</b>	<b>Fri 5/13/22</b>	
3599	8323	NA	0%	STEEL STRUCTURE/ Pan Deck	1 day	Thu 5/12/22	Fri 5/13/22	3646SS
3600	<b>8325</b>	<b>NA</b>	<b>0%</b>	<b>BOOTH</b>	<b>13 days</b>	<b>Tue 5/31/22</b>	<b>Fri 6/17/22</b>	
3601	8326	NA	0%	Hoist Piping (Above 6'-0" Off Finish Roof Only Allowed)	1 day	Tue 5/31/22	Wed 6/1/22	3592
3602	8327	NA	0%	Install Piping (Above 6'-0" Off Finish Roof Only Allowed)	10 days	Wed 6/1/22	Wed 6/15/22	3601
3603	8328	NA	0%	Hoist/Set Cooling Towers	1 day	Thu 6/2/22	Fri 6/3/22	3625FS+3 days,3626
3604	8329	NA	0%	Hoist Boliers	1 day	Thu 6/2/22	Fri 6/3/22	3603SS,3625
3605	8330	NA	0%	Install Piping (Above 6'-0" Off Finish Roof Only Allowed)	10 days	Fri 6/3/22	Fri 6/17/22	3604
3606	8331	NA	0%	Inertia Pads	1 day	Thu 6/2/22	Fri 6/3/22	3603SS,3625
3607	8332	NA	0%	Exchanger	1 day	Thu 6/2/22	Fri 6/3/22	3603SS,3625
3608	8333	NA	0%	Air Seperator	1 day	Thu 6/2/22	Fri 6/3/22	3603SS,3625
3609	8334	NA	0%	Expansion Tank	1 day	Thu 6/2/22	Fri 6/3/22	3603SS,3625
3610	<b>8335</b>	<b>NA</b>	<b>0%</b>	<b>JWM</b>	<b>11 days</b>	<b>Mon 5/30/22</b>	<b>Tue 6/14/22</b>	
3611	8336	NA	0%	Hoist Boilers	2 days	Mon 5/30/22	Wed 6/1/22	3603SF-1 day,3625
3612	8337	NA	0%	Hoist Piping (Above 6'-0" Off Finish Roof Only Allowed)	1 day	Mon 5/30/22	Tue 5/31/22	3611SS
3613	8338	NA	0%	Install Piping (Above 6'-0" Off Finish Roof Only Allowed)	10 days	Tue 5/31/22	Tue 6/14/22	3612
3614	<b>8339</b>	<b>NA</b>	<b>0%</b>	<b>HVAC</b>	<b>1 day</b>	<b>Wed 6/1/22</b>	<b>Thu 6/2/22</b>	
3615	8340	NA	0%	Hoist EFUs & MAU	1 day	Wed 6/1/22	Thu 6/2/22	3611
3616	<b>8341</b>	<b>NA</b>	<b>0%</b>	<b>Window Washing Davit Bases</b>	<b>2 days</b>	<b>Tue 5/17/22</b>	<b>Thu 5/19/22</b>	
3617	8342	NA	0%	Set/Grout BMU Bases	2 days	Tue 5/17/22	Thu 5/19/22	3622
3618	<b>8345</b>	<b>NA</b>	<b>0%</b>	<b>WESTEC Roofing</b>	<b>1 day</b>	<b>Tue 6/28/22</b>	<b>Wed 6/29/22</b>	
3619	8346	NA	0%	Hoist Built-up Insulation	1 day	Tue 6/28/22	Wed 6/29/22	3630SS
3620	8347	NA	0%	Hoist Roofing Sheet Membrane	1 day	Tue 6/28/22	Wed 6/29/22	3630SS
3621	<b>8348</b>	<b>NA</b>	<b>0%</b>	<b>Roofing L15</b>	<b>65 days</b>	<b>Thu 5/12/22</b>	<b>Thu 8/11/22</b>	
3622	8349	NA	0%	Concrete Cure Time CURBS & PADS	5 edays	Thu 5/12/22	Tue 5/17/22	1448,1426,1435,1457
3623	8350	NA	0%	Waterproof Strip In Equipment Pads	3 days	Tue 5/17/22	Fri 5/20/22	3622
3624	8351	NA	0%	Prep For Flashing Sheetmetal Pans	2 days	Wed 5/18/22	Fri 5/20/22	3623FF
3625	8352	NA	0%	Flashing/Sheetmetal Pans at Equipment Pads/Counterflashing's at buildings	5 days	Fri 5/20/22	Fri 5/27/22	3623,3624SS
3626	8353	NA	0%	Waterproof Strip In at Cooling Tower Pads	5 days	Fri 5/20/22	Fri 5/27/22	3623
3627	8355	NA	0%	MEPS Hang/Install/Secure Vertical/Drains at Roof for Roofing Jacks	5 days	Thu 6/9/22	Thu 6/16/22	3629SF-3 days
3628	8356	NA	0%	REMOVE WELDERS/JOB BOXES/EQUIPMENT/CLEAN ROOF 100%	2 days	Fri 6/17/22	Tue 6/21/22	3615,3611,3612,3613,3601,36
3629	8357	NA	0%	Built-up Insulation & Jack All Penetrations	5 days	Tue 6/21/22	Tue 6/28/22	3585,3587,3589,3628,3055,30
3630	8358	NA	0%	Hoist Roofing Product Insulation/Membrane	1 day	Tue 6/28/22	Wed 6/29/22	3629
3631	8360	NA	0%	Roofing Sheet Membrane / Boot Penetrations/Flood Test	27 days	Mon 6/27/22	Thu 8/4/22	3629FS-1 day,3584
3632	8361	NA	0%	Perimeter Roof Edge Flashings	5 days	Thu 8/4/22	Thu 8/11/22	3631
3633	8362	NA	0%	Install Roof Walk Pads	2 days	Thu 8/4/22	Mon 8/8/22	3631
3634	<b>8363</b>	<b>NA</b>	<b>0%</b>	<b>MEPS After Roofing</b>	<b>20 days</b>	<b>Thu 8/4/22</b>	<b>Thu 9/1/22</b>	
3635	<b>8364</b>	<b>NA</b>	<b>0%</b>	<b>Contractors To Provide Required Roofing Protection Board/Fire Blankets</b>	<b>20 days</b>	<b>Thu 8/4/22</b>	<b>Thu 9/1/22</b>	
3636	8365	NA	0%	Boiler Low Horizontal Piping (Under 6'-0" Off top of Roof )	20 days	Thu 8/4/22	Thu 9/1/22	3631,3626
3637	8366	NA	0%	Cooling Tower Low Horizontal Piping (Under 6'-0" Off top of Roof )	20 days	Thu 8/4/22	Thu 9/1/22	3631
3638	8367	NA	0%	HVAC Install Unistrut Support Frames	20 days	Thu 8/4/22	Thu 9/1/22	3631

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
3639	<b>8372</b>	<b>NA</b>	<b>0%</b>	<b>Roof Equipment Connect/ Hook-ups</b>	<b>22 days</b>	<b>Thu 9/1/22</b>	<b>Mon 10/3/22</b>	
3640	<b>8373</b>	<b>NA</b>	<b>0%</b>	<b>Contractors To Provide Required Roofing Protection Board/Fire Blankets</b>	<b>22 days</b>	<b>Thu 9/1/22</b>	<b>Mon 10/3/22</b>	
3641	8374	NA	0%	Install Connections at Boiler Area/Permit To Operate	20 days	Thu 9/1/22	Fri 9/30/22	3636
3642	8375	NA	0%	Install Connections at Cooling Tower Area	20 days	Thu 9/1/22	Thu 9/29/22	3637
3643	8376	NA	0%	Install HVAC Prefabbed to EF's, MAU	20 days	Thu 9/1/22	Thu 9/29/22	3631,3638
3644	8377	NA	0%	Roof Level 15 Equipment Hook-ups & Documentation Completed	1 day	Fri 9/30/22	Mon 10/3/22	3641,3642,3643
3645	<b>6813</b>	<b>NA</b>	<b>0%</b>	<b>ELEVATOR MACHINE ROOM/ELECTRICAL ROOM PENTHOUSE</b>	<b>29 days</b>	<b>Thu 5/12/22</b>	<b>Thu 6/23/22</b>	
3646	6814	NA	0%	Erect Structural Steel at Mechanical Room Penthouse	3 days	Thu 5/12/22	Tue 5/17/22	1451
3647	6815	NA	0%	Bolt-up and Weld	1 day	Mon 5/16/22	Tue 5/17/22	3646FS-1 day
3648	6816	NA	0%	Weld extended Clips for wall Framing/Joists Prior To Fireproofing	2 days	Wed 5/18/22	Fri 5/20/22	3647FS+1 day
3649	9926	NA	0%	Hoist KONE Equipment To Roof (HOIST AM)	0 days	Fri 5/20/22	Fri 5/20/22	3648
3650	6817	NA	0%	Install Joists	1 day	Fri 5/20/22	Mon 5/23/22	3648
3651	6818	NA	0%	Install PanDeck	1 day	Mon 5/23/22	Tue 5/24/22	3646,3650
3652	6819	NA	0%	Fire Proof Struc Steel & Joists	3 days	Tue 5/24/22	Fri 5/27/22	3650,3651
3653	6820	NA	0%	Frame Walls/Densglass Elevator Machine Room/Electrical Room Penthouse	3 days	Fri 5/27/22	Thu 6/2/22	3648,3651,3652
3654	6822	NA	0%	Sill Flashings/Counterflashings	2 days	Fri 5/27/22	Wed 6/1/22	3653FF-1 day
3655	6823	NA	0%	Door Frames	1 day	Wed 6/1/22	Thu 6/2/22	3653FF
3656	6825	NA	0%	Water Proofing on Densglass	3 days	Thu 6/2/22	Tue 6/7/22	3653
3657	6827	NA	0%	Install Parapet Densglass	1 day	Thu 6/2/22	Fri 6/3/22	3651,3653
3658	6840	NA	0%	WATER Proofing ON ROOF	2 days	Fri 6/3/22	Tue 6/7/22	3657
3659	6831	NA	0%	MEPS Rough In Walls/Ceilings	2 days	Thu 6/2/22	Mon 6/6/22	3653
3660	6832	NA	0%	Inspections	1 day	Mon 6/6/22	Tue 6/7/22	3659
3661	6833	NA	0%	Insulate	1 day	Tue 6/7/22	Wed 6/8/22	3660
3662	6834	NA	0%	Hang Drywall	1 day	Wed 6/8/22	Thu 6/9/22	3661
3663	6835	NA	0%	Tape	2 days	Thu 6/9/22	Mon 6/13/22	3662
3664	7192	NA	0%	MEPS FINISH EQUIPMENT INSTALLATION COMPLETE	5 days	Mon 6/13/22	Mon 6/20/22	3663
3665	6836	NA	0%	Install Electrical Panels/Disconnects	5 days	Mon 6/13/22	Mon 6/20/22	3663
3666	6838	NA	0%	Pull Feeders & Terminate Electrical Room	3 days	Mon 6/20/22	Thu 6/23/22	3665
3667	6844	NA	0%	Install doors and lockable hardware	1 day	Wed 6/22/22	Thu 6/23/22	3666FF
3668	6839	NA	0%	ELEVATOR MACHINE ROOM WATER TIGHT/POWERED/LOCKED DOORS ALL MEPS	0 days	Thu 6/23/22	Thu 6/23/22	3666FF,3658,3667FF,3664
3669	<b>6843</b>	<b>NA</b>	<b>0%</b>	<b>ELEVATORS</b>	<b>221 days</b>	<b>Thu 10/14/21</b>	<b>Thu 9/1/22</b>	
3670	<b>7207</b>	<b>NA</b>	<b>0%</b>	<b>ELEVATORS 2,3,4,5</b>	<b>230 days</b>	<b>Thu 10/14/21</b>	<b>Thu 9/1/22</b>	
3671	7247	NA	0%	ELEVATOR MANUFACTURING	18 wks	Thu 10/14/21	Thu 2/17/22	3672SF
3672	9928	NA	0%	KONE Deliver Material onsite	20 days	Thu 2/17/22	Thu 3/17/22	3673SF
3673	7205	NA	0%	MOBILIZE ELEVATORS 2,3,4,5 (INSTALL PIT TO L9)	0 days	Thu 3/17/22	Thu 3/17/22	3674,3675
3674	7201	NA	0%	INSTALL ELEVATORS 2,3,4,5 CRASH DECK L10 (WORKING DECK NOT REQUIRED)	0 days	Thu 3/3/22	Thu 3/3/22	1238
3675	7202	NA	0%	INSTALL ELEVATORS 2,3,4,5 CRASH DECK WITH TEMPORARY ROOF AND DRAIN	0 days	Thu 3/17/22	Thu 3/17/22	1282
3676	7204	NA	0%	ELEVATOR MACHINE ROOM WATER TIGHT/POWERED/LOCKED DOORS ALL MEPS	0 days	Thu 6/23/22	Thu 6/23/22	3668FF
3677	6841	NA	0%	INSTALL ELEVATORS 2,3,4,5	8 wks	Thu 6/23/22	Thu 8/18/22	3676
3678	<b>6858</b>	<b>NA</b>	<b>0%</b>	<b>START INSTALL ELEVATOR JAMBS/LOCKED DOORS (2 WKS AFTER ELEVATOR MACHINE ROOM ACCEPTANCE)</b>	<b>16 days</b>	<b>Thu 7/7/22</b>	<b>Fri 7/29/22</b>	
3679	10205	NA	0%	L2 & L3	2 days	Thu 7/7/22	Mon 7/11/22	3676FS+10 days
3680	10206	NA	0%	L4 & L5	2 days	Mon 7/11/22	Wed 7/13/22	3679
3681	10207	NA	0%	L6 & L7	2 days	Wed 7/13/22	Fri 7/15/22	3680
3682	10202	NA	0%	L8 & L9	2 days	Fri 7/15/22	Tue 7/19/22	3681
3683	10203	NA	0%	L10 & L11	2 days	Tue 7/19/22	Thu 7/21/22	3682
3684	10204	NA	0%	L12 & L13	2 days	Thu 7/21/22	Mon 7/25/22	3683

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
3685	10201	NA	0%	L14	2 days	Mon 7/25/22	Wed 7/27/22	3684
3686	10199	NA	0%	LOWER LEVEL	1 day	Wed 7/27/22	Thu 7/28/22	3685
3687	10200	NA	0%	L1	1 day	Thu 7/28/22	Fri 7/29/22	3686
3688	6845	NA	0%	ELEVATORS COMPLETE FOR CONSTRUCTION USE 4 & 5	0 days	Thu 8/18/22	Thu 8/18/22	3677
3689	10404	NA	0%	ELEVATOR LOBBIES (LOWER LEVEL THRU LEVEL 14) READY FOR STATE INSPECTI	0 days	Mon 8/15/22	Mon 8/15/22	3755FF
3690	6847	NA	0%	STATE INSPECT, CERTIFY CONSTRUCTION ELEVATORS 4 & 5	10 days	Thu 8/18/22	Thu 9/1/22	3677,3688,3689FF
3691	10272	NA	0%	ELEVATOR SHAFT WALLS (AFTER HOURS)	16 days	Mon 7/11/22	Tue 8/2/22	
3692	10273	NA	0%	L2 & L3	1 day	Mon 7/11/22	Tue 7/12/22	3676FS+10 days
3693	10274	NA	0%	INSTALL FRAMING/COREBOARD/FIRECAULKING	1 day	Mon 7/11/22	Tue 7/12/22	3679
3694	10275	NA	0%	L4 & L5	1 day	Wed 7/13/22	Thu 7/14/22	3692
3695	10276	NA	0%	INSTALL FRAMING/COREBOARD/FIRECAULKING	1 day	Wed 7/13/22	Thu 7/14/22	3680
3696	10277	NA	0%	L6 & L7	1 day	Fri 7/15/22	Mon 7/18/22	3694
3697	10278	NA	0%	INSTALL FRAMING/COREBOARD/FIRECAULKING	1 day	Fri 7/15/22	Mon 7/18/22	3681
3698	10279	NA	0%	L8 & L9	1 day	Tue 7/19/22	Wed 7/20/22	3696
3699	10280	NA	0%	INSTALL FRAMING/COREBOARD/FIRECAULKING	1 day	Tue 7/19/22	Wed 7/20/22	3682
3700	10281	NA	0%	L10 & L11	1 day	Thu 7/21/22	Fri 7/22/22	3698
3701	10282	NA	0%	INSTALL FRAMING/COREBOARD/FIRECAULKING	1 day	Thu 7/21/22	Fri 7/22/22	3683
3702	10283	NA	0%	L12 & L13	1 day	Mon 7/25/22	Tue 7/26/22	3700
3703	10284	NA	0%	INSTALL FRAMING/COREBOARD/FIRECAULKING	1 day	Mon 7/25/22	Tue 7/26/22	3684
3704	10285	NA	0%	L14	1 day	Wed 7/27/22	Thu 7/28/22	3702
3705	10286	NA	0%	INSTALL FRAMING/COREBOARD/FIRECAULKING	1 day	Wed 7/27/22	Thu 7/28/22	3685
3706	10287	NA	0%	LOWER LEVEL	1 day	Thu 7/28/22	Fri 7/29/22	3702
3707	10288	NA	0%	INSTALL FRAMING/COREBOARD/FIRECAULKING	1 day	Thu 7/28/22	Fri 7/29/22	3686
3708	10289	NA	0%	L1	2 days	Fri 7/29/22	Tue 8/2/22	3704,3706
3709	10290	NA	0%	INSTALL FRAMING/COREBOARD/FIRECAULKING	2 days	Fri 7/29/22	Tue 8/2/22	3687
3710	10291	NA	0%	ELEVATOR LOBBY	26 days	Tue 7/12/22	Wed 8/17/22	
3711	10292	NA	0%	LEVEL 2 - LEVELS 3	11 days	Tue 7/12/22	Wed 7/27/22	
3712	10293	NA	0%	Inspection Coreboard Prior to Drywall Install	1 day	Tue 7/12/22	Wed 7/13/22	3693
3713	10294	NA	0%	Install Drywall Full Height/Fire Caulk Fire Tape/Total Doors framing 100%	1 day	Wed 7/13/22	Thu 7/14/22	3712
3714	10295	NA	0%	Tape	7 days	Thu 7/14/22	Mon 7/25/22	3713
3715	10296	NA	0%	MEPS/DAS Rough-ins Exposed Concrete Ceilings	2 days	Mon 7/25/22	Wed 7/27/22	3714
3716	10297	NA	0%	LEVEL 4 - LEVEL 5	11 days	Thu 7/14/22	Fri 7/29/22	
3717	10298	NA	0%	Inspection Coreboard Prior to Drywall Install	1 day	Thu 7/14/22	Fri 7/15/22	3695
3718	10299	NA	0%	Install Drywall Full Height/Fire Caulk Fire Tape/Total Doors framing 100%	1 day	Fri 7/15/22	Mon 7/18/22	3713,3717
3719	10300	NA	0%	Tape	7 days	Mon 7/18/22	Wed 7/27/22	3718
3720	10301	NA	0%	MEPS/DAS Rough-ins Exposed Concrete Ceilings	2 days	Wed 7/27/22	Fri 7/29/22	3718,3719
3721	10302	NA	0%	LEVEL 6 - LEVEL 7	11 days	Mon 7/18/22	Tue 8/2/22	
3722	10303	NA	0%	Inspection Coreboard Prior to Drywall Install	1 day	Mon 7/18/22	Tue 7/19/22	3697
3723	10304	NA	0%	Install Drywall Full Height/Fire Caulk Fire Tape/Total Doors framing 100%	1 day	Tue 7/19/22	Wed 7/20/22	3718,3722
3724	10305	NA	0%	Tape	7 days	Wed 7/20/22	Fri 7/29/22	3723
3725	10306	NA	0%	MEPS/DAS Rough-ins Exposed Concrete Ceilings	2 days	Fri 7/29/22	Tue 8/2/22	3723,3724
3726	10307	NA	0%	LEVEL 8 - LEVEL 9	11 days	Wed 7/20/22	Thu 8/4/22	
3727	10308	NA	0%	Inspection Coreboard Prior to Drywall Install	1 day	Wed 7/20/22	Thu 7/21/22	3699
3728	10309	NA	0%	Install Drywall Full Height/Fire Caulk Fire Tape/Total Doors framing 100%	1 day	Thu 7/21/22	Fri 7/22/22	3723,3727
3729	10310	NA	0%	Tape	7 days	Fri 7/22/22	Tue 8/2/22	3728
3730	10311	NA	0%	MEPS/DAS Rough-ins Exposed Concrete Ceilings	2 days	Tue 8/2/22	Thu 8/4/22	3728,3729
3731	10312	NA	0%	LEVEL 10 - LEVEL 11	11 days	Fri 7/22/22	Mon 8/8/22	

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
3732	10313	NA	0%	Inspection Coreboard Prior to Drywall Install	1 day	Fri 7/22/22	Mon 7/25/22	3701
3733	10314	NA	0%	Install Drywall Full Height/Fire Caulk Fire Tape/Total Doors framing 100%	1 day	Mon 7/25/22	Tue 7/26/22	3728,3732
3734	10315	NA	0%	Tape	7 days	Tue 7/26/22	Thu 8/4/22	3733
3735	10316	NA	0%	MEPS/DAS Rough-ins Exposed Concrete Ceilings	2 days	Thu 8/4/22	Mon 8/8/22	3733,3734
3736	10317	NA	0%	<b>LEVEL 12 - LEVEL 13</b>	<b>11 days</b>	<b>Tue 7/26/22</b>	<b>Wed 8/10/22</b>	
3737	10318	NA	0%	Inspection Coreboard Prior to Drywall Install	1 day	Tue 7/26/22	Wed 7/27/22	3703
3738	10319	NA	0%	Install Drywall Full Height/Fire Caulk Fire Tape/Total Doors framing 100%	1 day	Wed 7/27/22	Thu 7/28/22	3733,3737
3739	10320	NA	0%	Tape	7 days	Thu 7/28/22	Mon 8/8/22	3738
3740	10321	NA	0%	MEPS/DAS Rough-ins Exposed Concrete Ceilings	2 days	Mon 8/8/22	Wed 8/10/22	3738,3739
3741	10322	NA	0%	<b>LEVEL 14</b>	<b>11 days</b>	<b>Thu 7/28/22</b>	<b>Fri 8/12/22</b>	
3742	10323	NA	0%	Inspection Coreboard Prior to Drywall Install	1 day	Thu 7/28/22	Fri 7/29/22	3705
3743	10324	NA	0%	Install Drywall Full Height/Fire Caulk Fire Tape/Total Doors framing 100%	1 day	Fri 7/29/22	Mon 8/1/22	3738,3742
3744	10325	NA	0%	Tape	7 days	Mon 8/1/22	Wed 8/10/22	3743
3745	10326	NA	0%	MEPS/DAS Rough-ins Exposed Concrete Ceilings	2 days	Wed 8/10/22	Fri 8/12/22	3743,3744
3746	10327	NA	0%	<b>LOWER LEVEL</b>	<b>11 days</b>	<b>Fri 7/29/22</b>	<b>Mon 8/15/22</b>	
3747	10328	NA	0%	Inspection Coreboard Prior to Drywall Install	1 day	Fri 7/29/22	Mon 8/1/22	3707
3748	10329	NA	0%	Install Drywall Full Height/Fire Caulk Fire Tape/Total Doors framing 100%	1 day	Mon 8/1/22	Tue 8/2/22	3743,3747
3749	10330	NA	0%	Tape	7 days	Tue 8/2/22	Thu 8/11/22	3748
3750	10331	NA	0%	MEPS/DAS Rough-ins Exposed Concrete Ceilings	2 days	Thu 8/11/22	Mon 8/15/22	3748,3749
3751	10332	NA	0%	<b>LEVEL 1</b>	<b>11 days</b>	<b>Tue 8/2/22</b>	<b>Wed 8/17/22</b>	
3752	10333	NA	0%	Inspection Coreboard Prior to Drywall Install	1 day	Tue 8/2/22	Wed 8/3/22	3709
3753	10334	NA	0%	Install Drywall Full Height/Fire Caulk Fire Tape/Total Doors framing 100%	1 day	Wed 8/3/22	Thu 8/4/22	3748,3752
3754	10335	NA	0%	Tape	7 days	Thu 8/4/22	Mon 8/15/22	3753
3755	10337	NA	0%	ELEVATOR LOBBIES (LOWER LEVEL THRU LEVEL 14) READY FOR STATE INSPECTION	1 day	Fri 8/12/22	Mon 8/15/22	3754FF
3756	10336	NA	0%	MEPS/DAS Rough-ins Exposed Concrete Ceilings	2 days	Mon 8/15/22	Wed 8/17/22	3753,3754
3757	1981	NA	0%	<b>PODIUM ELEVATORS</b>	<b>45 days</b>	<b>Thu 1/13/22</b>	<b>Mon 3/21/22</b>	
3758	7214	NA	0%	ELEVATOR MACHINE ROOMS WATER TIGHT/POWERED/LOCKED DOORS ALL MEPS	0 days	Thu 1/13/22	Thu 1/13/22	1779
3759	1982	NA	0%	INSTALL, TEST ELEVATOR 1	20 days	Fri 1/14/22	Fri 2/11/22	3758
3760	8074	NA	0%	ELEVATOR # 1 COMPLETE FOR CONSTRUCTION USE	0 days	Fri 2/11/22	Fri 2/11/22	3759FF
3761	8073	NA	0%	STATE INSPECT, CERTIFY CONSTRUCTION ELEVATORS # 1	5 days	Fri 2/11/22	Fri 2/18/22	3760
3762	1984	NA	0%	INSTALL, TEST ELEVATOR 6	20 days	Mon 2/14/22	Mon 3/14/22	3759
3763	1986	NA	0%	INSTALL ELEVATOR 1 FINISHES	5 days	Mon 2/14/22	Fri 2/18/22	3759
3764	1987	NA	0%	INSTALL ELEVATOR 6 FINISHES	5 days	Tue 3/15/22	Mon 3/21/22	3762,3763
3765	2001	NA	0%	<b>EQUIPMENT &amp; AMENITIES</b>	<b>137 days</b>	<b>Mon 1/24/22</b>	<b>Fri 8/5/22</b>	
3766	2002	NA	0%	TELCOM & DATA	30 days	Fri 6/24/22	Fri 8/5/22	1918
3767	2003	NA	0%	AUDIO/VIDEO	30 days	Fri 6/24/22	Fri 8/5/22	1918
3768	2005	NA	0%	LOADING DOCK	5 days	Tue 1/25/22	Mon 1/31/22	3572
3769	2007	NA	0%	BUILDING MAINTENANCE EQUIPMENT	5 days	Fri 1/28/22	Thu 2/3/22	1790
3770	2008	NA	0%	FITNESS CENTER	20 days	Mon 1/24/22	Fri 2/18/22	1809
3771	2009	NA	0%	<b>SITE FINISHES</b>	<b>263.13 days</b>	<b>Fri 12/3/21</b>	<b>Thu 12/22/22</b>	
3772	2010	NA	0%	<b>BUILDING LANDSCAPING</b>	<b>274.13 days</b>	<b>Fri 12/3/21</b>	<b>Thu 12/22/22</b>	
3773	2011	NA	0%	<b>DOG RUN</b>	<b>40.88 days</b>	<b>Wed 4/13/22</b>	<b>Wed 6/8/22</b>	
3774	2012	NA	0%	DOG RUN CONCRETE & MASONRY	20 days	Wed 4/13/22	Tue 5/10/22	3439,3499
3775	2013	NA	0%	LANDSCAPE & IRRIGATION	5 days	Wed 5/25/22	Wed 6/1/22	3436,3776
3776	1930	NA	0%	INSTALL STEEL PLANTERS	5 days	Wed 5/11/22	Tue 5/17/22	3774,3439
3777	2014	NA	0%	INSTALL BENCHES	5 days	Wed 5/25/22	Wed 6/1/22	3781
3778	2016	NA	0%	INSTALL SECURITY FENCE & GATE	5 days	Wed 5/11/22	Tue 5/17/22	3774

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
3779	2017	NA	0%	INSTALL DOG WASH STATION	5 days	Wed 5/25/22	Wed 6/1/22	3781
3780	1410	NA	0%	STEP & WALL LIGHT ELECTRICAL	5 days	Wed 4/20/22	Tue 4/26/22	3774SF+80 hrs
3781	2015	NA	0%	CONCRETE PAVING	5 days	Wed 5/18/22	Tue 5/24/22	3776
3782	2018	NA	0%	INSTALL SYNTHETIC TURF	5 days	Wed 5/25/22	Wed 6/1/22	3781
3783	2019	NA	0%	PRE-PUNCH DOG RUN	5 days	Thu 6/2/22	Wed 6/8/22	3782,3779,3775,3778,3777
3784	<b>2020</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 3 COURTYARD</b>	<b>274.13 days</b>	<b>Fri 12/3/21</b>	<b>Thu 12/22/22</b>	
3785	1925	NA	0%	SKYLIGHT CURBS	5 days	Fri 12/3/21	Thu 12/9/21	879
3786	2021	NA	0%	LANDSCAPING & IRRIGATION	5 days	Tue 11/15/22	Tue 11/22/22	3434
3787	1928	NA	0%	INSTALL STEEL PLANTER SECTIONS	5 days	Mon 10/24/22	Mon 10/31/22	3440
3788	1927	NA	0%	INSTALL PRECAST BENCH/PLANTER WALL	5 days	Mon 10/31/22	Mon 11/7/22	3787
3789	1412	NA	0%	ENERGIZE MICRO STEP LIGHTS	5 days	Mon 10/31/22	Mon 11/7/22	3788SF+40 hrs
3790	2022	NA	0%	PRE-PUNCH COURTYARD	20 days	Tue 11/22/22	Thu 12/22/22	3786
3791	<b>2023</b>	<b>NA</b>	<b>0%</b>	<b>LEVEL 7 TERRACE</b>	<b>21 days</b>	<b>Fri 5/20/22</b>	<b>Mon 6/20/22</b>	
3792	2024	NA	0%	INSTALL PLANTERS	5 days	Fri 5/20/22	Fri 5/27/22	3438
3793	2025	NA	0%	LANDSCAPE & IRRIGATION	10 days	Fri 5/27/22	Mon 6/13/22	3792
3794	2026	NA	0%	PRE-PUNCH LEVEL 7 TERRACE	5 days	Mon 6/13/22	Mon 6/20/22	3793
3795	<b>2027</b>	<b>NA</b>	<b>0%</b>	<b>STREET FRONTAGE</b>	<b>254.13 days</b>	<b>Fri 12/10/21</b>	<b>Thu 12/1/22</b>	
3796	<b>2028</b>	<b>NA</b>	<b>0%</b>	<b>MCALLISTER</b>	<b>254.13 days</b>	<b>Fri 12/10/21</b>	<b>Thu 12/1/22</b>	
3797	2029	NA	0%	DEMO MCALLISTER SIDEWALK	5 days	Fri 10/7/22	Mon 10/17/22	255
3798	2030	NA	0%	INSTALL STONE CLADDING	2 days	Fri 12/10/21	Mon 12/13/21	3441
3799	2031	NA	0%	INSTALL WOOD TOP	2 days	Tue 11/22/22	Mon 11/28/22	3810,3798
3800	2033	NA	0%	FINE GRADE	1 day	Mon 10/17/22	Tue 10/18/22	3797
3801	2034	NA	0%	STAKE CURB & GUTTER	1 day	Tue 10/25/22	Wed 10/26/22	3803
3802	2036	NA	0%	FORM, POUR, STRIP CURB & GUTTER	3 days	Wed 10/26/22	Mon 10/31/22	3801
3803	2035	NA	0%	EXCAVATE, FILL STRUCTURAL SOIL	5 days	Tue 10/18/22	Tue 10/25/22	3800
3804	2037	NA	0%	FORM, POUR, STRIP SIDEWALK AND APPROACHES	5 days	Tue 11/15/22	Tue 11/22/22	242,3808
3805	1970	NA	0%	INSTALL SPECIAL PAVING AT ENTRY	5 days	Tue 11/22/22	Thu 12/1/22	3804
3806	2039	NA	0%	SAWCUT & REPAVE STREET FRONTAGE	5 days	Mon 10/31/22	Mon 11/7/22	3802
3807	2040	NA	0%	INSTALL STREET TREES	5 days	Tue 11/22/22	Thu 12/1/22	3804
3808	2038	NA	0%	INSTALL IRRIGATON UNDERGROUND	5 days	Mon 11/7/22	Tue 11/15/22	3802,3806
3809	2041	NA	0%	SIGNAGE, GRAPHICS, METERS	5 days	Tue 11/22/22	Thu 12/1/22	3806,3804
3810	2032	NA	0%	PLANTER LANDSCAPING & IRRIGATION	5 days	Tue 11/15/22	Tue 11/22/22	3808,3798
3811	2042	NA	0%	INSTALL BIKE RACKS	5 days	Tue 11/22/22	Thu 12/1/22	3804
3812	8175	NA	0%	MCALLISTER ST FRONTAGE COMPLETE	0 days	Thu 12/1/22	Thu 12/1/22	3807
3813	<b>2043</b>	<b>NA</b>	<b>0%</b>	<b>HYDE</b>	<b>44 days</b>	<b>Fri 9/30/22</b>	<b>Thu 12/1/22</b>	
3814	2044	NA	0%	DEMO HYDE SIDEWALK	5 days	Fri 9/30/22	Fri 10/7/22	262
3815	2045	NA	0%	BACKFILL COMPACT CRANE FOUNDATION	1 day	Fri 10/7/22	Tue 10/11/22	3814
3816	2046	NA	0%	FINE GRADE	1 day	Tue 10/11/22	Wed 10/12/22	3815
3817	2047	NA	0%	STAKE CURB & GUTTER	1 day	Wed 10/19/22	Thu 10/20/22	3819
3818	2049	NA	0%	FORM, POUR, STRIP CURB & GUTTER	3 days	Thu 10/20/22	Tue 10/25/22	3817
3819	2048	NA	0%	EXCAVATE, FILL STRUCTURAL SOIL	5 days	Wed 10/12/22	Wed 10/19/22	3816
3820	2050	NA	0%	FORM, POUR, STRIP SIDEWALK AND APPROACHES	5 days	Tue 11/8/22	Wed 11/16/22	3823,3798
3821	2052	NA	0%	SAWCUT & REPAVE STREET FRONTAGE	5 days	Tue 10/25/22	Tue 11/1/22	3818
3822	2053	NA	0%	INSTALL STREET TREES	5 days	Tue 11/22/22	Thu 12/1/22	3835FF,3820
3823	2051	NA	0%	INSTALL IRRIGATON UNDERGROUND	5 days	Tue 11/1/22	Tue 11/8/22	3818,3821
3824	2055	NA	0%	SIGNAGE, GRAPHICS, METERS	5 days	Tue 11/22/22	Thu 12/1/22	3837FF,3820,3821
3825	2057	NA	0%	INSTALL BIKE RACKS	5 days	Tue 11/22/22	Thu 12/1/22	3838FF,3820

University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
3826	8176	NA	0%	HYDE ST FRONTAGE COMPLETE	0 days	Thu 12/1/22	Thu 12/1/22	3822
3827	<b>2059</b>	<b>NA</b>	<b>0%</b>	<b>GOLDEN GATE</b>	<b>54 days</b>	<b>Fri 9/16/22</b>	<b>Thu 12/1/22</b>	
3828	2060	NA	0%	FINE GRADE	1 day	Fri 9/16/22	Mon 9/19/22	308,286
3829	2061	NA	0%	STAKE CURB & GUTTER	1 day	Mon 9/26/22	Tue 9/27/22	3831
3830	2063	NA	0%	FORM, POUR, STRIP CURB & GUTTER	3 days	Tue 9/27/22	Fri 9/30/22	3829
3831	2062	NA	0%	EXCAVATE, FILL STRUCTURAL SOIL	5 days	Mon 9/19/22	Mon 9/26/22	3828
3832	2064	NA	0%	FORM, POUR, STRIP SIDEWALK AND APPROACHES	5 days	Mon 10/17/22	Mon 10/24/22	3836
3833	1973	NA	0%	INSTALL SPECIAL PAVING AT ENTRY	5 days	Mon 10/24/22	Mon 10/31/22	3832
3834	2066	NA	0%	SAWCUT & REPAVE STREET FRONTAGE	5 days	Fri 9/30/22	Fri 10/7/22	3830
3835	2054	NA	0%	INSTALL STREET TREES	5 days	Tue 11/22/22	Thu 12/1/22	3807FF,3832
3836	2065	NA	0%	INSTALL IRRIGATON UNDERGROUND	5 days	Fri 10/7/22	Mon 10/17/22	3830,3834
3837	2056	NA	0%	SIGNAGE, GRAPHICS, METERS	5 days	Tue 11/22/22	Thu 12/1/22	3832,3834,3809FF
3838	2058	NA	0%	INSTALL BIKE RACKS	5 days	Tue 11/22/22	Thu 12/1/22	3811FF,3832
3839	8177	NA	0%	GOLDEN GATE ST FRONTAGE COMPLETE	0 days	Thu 12/1/22	Thu 12/1/22	3835
3840	6486	NA	0%	START UP & PRE TESTING	83 days	Fri 9/30/22	Thu 2/2/23	
3841	<b>6803</b>	<b>NA</b>	<b>0%</b>	<b>PG&amp;E UNIT METERS</b>	<b>19.13 days</b>	<b>Mon 11/28/22</b>	<b>Fri 12/23/22</b>	
3842	6805	NA	0%	L14 ENTRY DOORS INSTALLED & LABELED	1 day	Mon 11/28/22	Mon 11/28/22	3107
3843	6806	NA	0%	PG&E INSTALL UNIT METERS	5 days	Mon 11/28/22	Mon 12/5/22	3842
3844	7191	NA	0%	MAN LIFT UNITS MCALLISTER MEPS TRIM COMPLETE	0 days	Fri 12/16/22	Fri 12/16/22	3289FF,3327FF
3845	7190	NA	0%	MAN LIFT UNITS HYDE MEPS TRIM COMPLETE	0 days	Fri 12/23/22	Fri 12/23/22	3408FF,3370FF
3846	<b>6487</b>	<b>NA</b>	<b>0%</b>	<b>Permanent Power On for Building Start Up</b>	<b>0 days</b>	<b>Fri 9/30/22</b>	<b>Fri 9/30/22</b>	<b>51,3547</b>
3847	7210	NA	0%	PERMANENT POWER ENERGIZIED	0 days	Fri 9/30/22	Fri 9/30/22	1718FF,1719FF,3668,3578,357
3848	6489	NA	0%	Point to Point Pre-Testing (Line Voltage Verification)	10 days	Mon 10/3/22	Tue 10/18/22	3847,1742FF,3644
3849	6496	NA	0%	Condenser Water Clean & Flush	4 days	Tue 10/18/22	Mon 10/24/22	3848
3850	6517	NA	0%	Start Up Bldg Systems, Building Supply and Exhaust Systems	15 days	Mon 10/24/22	Tue 11/15/22	3849,1727
3851	10165	NA	0%	Fire Alarm Pre Testing Starts	0 days	Tue 11/15/22	Tue 11/15/22	1765,3850
3852	10166	NA	0%	Fire Smoke Dampers Check Manual Open/Close Functions	5 days	Wed 11/16/22	Tue 11/22/22	3851
3853	10164	NA	0%	Fire Smoke Dampers Pre Test Operations	5 days	Wed 11/23/22	Thu 12/1/22	3852
3854	6808	NA	0%	Test / Adjust / Balance	10 days	Fri 12/2/22	Thu 12/15/22	3853
3855	8392	NA	0%	L 14 MEPS Trim COMPLETE	0 days	Fri 1/27/23	Fri 1/27/23	3121FF
3856	6516	NA	0%	Crosss Contamination Testing	2 days	Fri 1/27/23	Tue 1/31/23	3855
3857	6499	NA	0%	Chlorinate System (All Fixtures Installed to L14 & Man Lift Units)	2 days	Tue 1/31/23	Thu 2/2/23	3856
3858	6639	NA	0%	Unit, Common Area, Egress & Ingress Doors Installed L14 Corridors	1 day	Wed 12/14/22	Thu 12/15/22	3107,3248
3859	6629	NA	0%	Stair& Corridor Pressurization Test EVENING (SMOKE CONTROL TESTING)	5 days	Fri 12/16/22	Thu 12/22/22	3858,3854
3860	6633	NA	0%	Fire Alarm Pre Test	2 days	Fri 12/23/22	Tue 12/27/22	3859
3861	6638	NA	0%	Fire Consultant Inspection (Cupertino Required)	1 day	Wed 12/28/22	Wed 12/28/22	3860
3862	6631	NA	0%	Unit Leakage Testing 3rd Party	2 days	Thu 12/29/22	Fri 12/30/22	3861
3863	6632	NA	0%	FSD Check 3rd Party	1 day	Tue 1/3/23	Tue 1/3/23	3862
3864	6756	NA	0%	HVAC (SMOKE CONTROL LETTER OF COMPLETION)	2 days	Wed 1/4/23	Thu 1/5/23	3863
3865	10460	NA	0%	ELEVATORS STATE INSPECTION ELEVATORS 2,3,4,5 COMPLETE	1 day	Wed 1/4/23	Thu 1/5/23	3876FF
3866	6649	NA	0%	INSPECTIONS & SIGNOFF	366 days	Wed 9/1/21	Tue 2/21/23	
3867	<b>6650</b>	<b>NA</b>	<b>0%</b>	<b>BUILDING</b>	<b>385 days</b>	<b>Wed 9/1/21</b>	<b>Tue 2/21/23</b>	
3868	6651	NA	0%	FOUNDATION	1 day	Wed 9/1/21	Thu 9/2/21	473
3869	6652	NA	0%	STRUCTURE	1 day	Tue 5/3/22	Wed 5/4/22	1448
3870	6779	NA	0%	COMPLETE PLUMBING INSPECTIONS	12 days	Thu 2/2/23	Mon 2/20/23	3857,3121
3871	10142	NA	0%	COMPLETE UNIT ELECTRICAL INSPECTIONS	17 days	Fri 1/27/23	Tue 2/21/23	3121
3872	9711	NA	0%	COMPLETE BUILDING UNIT INSPECTIONS	17 days	Fri 1/27/23	Tue 2/21/23	3121



University of Calif Hastings  
CONSTRUCTION SCHEDULE  
dated 10 22 20

ID	Unique ID	Actual Start	% Complete	Task Name	Duration	Start	Finish	Predecessors
3873	6653	NA	0%	<b>ARCHITECTURAL</b>	19 days	Wed 12/7/22	Wed 1/4/23	
3874	6654	NA	0%	EXTERIOR FINISHES	1 day	Thu 12/8/22	Fri 12/9/22	3421
3875	7216	NA	0%	ELEVATORS STATE INSPECTION PODIUM ELEVATORS 1 & 6	10 days	Wed 12/7/22	Wed 12/21/22	3763FF,3764FF,3876SF-1 day,3
3876	6656	NA	0%	ELEVATORS STATE INSPECTION ELEVATORS 2,3,4,5	10 days	Wed 12/21/22	Wed 1/4/23	3247FF,3248FF,3250
3877	6744	NA	0%	<b>PUBLIC WORKS</b>	2 days	Thu 12/1/22	Mon 12/5/22	
3878	6746	NA	0%	URBAN FORESTRY	1 day	Thu 12/1/22	Fri 12/2/22	3839,3826,3812
3879	6747	NA	0%	Paving Complete	1 day	Thu 12/1/22	Fri 12/2/22	3839,3826,3812
3880	6748	NA	0%	SidewalkS Complete	1 day	Thu 12/1/22	Fri 12/2/22	3839,3826,3812
3881	6749	NA	0%	SFMTA	1 day	Fri 12/2/22	Mon 12/5/22	3880,3826,3812
3882	6750	NA	0%	DPW	1 day	Fri 12/2/22	Mon 12/5/22	3880,3826,3812
3883	6752	NA	0%	<b>Special Inspections / Final Affidavit Letter Required Prior To TCO</b>	1 day	Mon 2/20/23	Tue 2/21/23	3869,3874
3884	6753	NA	0%	Final Affidavit Letter	1 day	Mon 2/20/23	Tue 2/21/23	3897SF-1 day
3885	6754	NA	0%	S-18 Form/Agreement Between Client & DBI Required Prior To TCO	1 day	Mon 2/20/23	Tue 2/21/23	3897SF-1 day
3886	6671	NA	0%	<b>TEMPORARY OCCUPANCY INSPECTIONS</b>	42 days	Fri 12/30/22	Tue 2/28/23	
3887	6672	NA	0%	<b>UC HASTINGS MUST (ACQUIRE UL CERTIFICATION FOR MONITORING BUILDING</b>	0 days	Thu 1/5/23	Thu 1/5/23	3889SF-1 day
3888	6673	NA	0%	2-Way Communications	0 days	Fri 12/30/22	Fri 12/30/22	3864FS-4 days
3889	6674	NA	0%	INSPECTION DAY #1 GENERATOR SHOCK TEST, FUEL OIL ALARMS, Fire Pump Testir	1 day	Fri 1/6/23	Fri 1/6/23	3864,3876FS+1 day,3865
3890	6680	NA	0%	ERRCS Emissions Reduction Currency System	1 day	Fri 1/6/23	Fri 1/6/23	
3891	6675	NA	0%	INSPECTION DAY #2 SMOKE CONTROL, GARAGE CO SYSTEM TEST	1 day	Mon 1/9/23	Mon 1/9/23	3889
3892	6676	NA	0%	INSPECTION DAY #3 SMOKE CONTROL TEST	1 day	Tue 1/10/23	Tue 1/10/23	3891
3893	6677	NA	0%	INSPECTION DAY #4, FA DEVICE INITATION, AUDIBLE/VISUAL ALARMS	1 day	Wed 1/11/23	Wed 1/11/23	3892
3894	6678	NA	0%	INSPECTION DAY #5 TAMPER FLOW SWITCHES, EVACUATION MAPS	1 day	Thu 1/12/23	Thu 1/12/23	3893
3895	6679	NA	0%	INSPECTION DAY #6 FLOW TEST, ELEVATOR RECALL	1 day	Fri 1/13/23	Fri 1/13/23	3894
3896	8726	NA	0%	WEATHER DAYS (25)	25 days	Mon 1/16/23	Mon 2/20/23	3895FS+1 day
3897	6681	NA	0%	CITY OF SAN FRANCISCO ISSUE TCO DOCUMENTATION	2 days	Wed 2/22/23	Thu 2/23/23	3887,3888,3889,3891,3892,38
3898	6682	NA	0%	BUILDING INSPECTOR SIGN'S ALL PERMIT CARDS FOR TCO	1 day	Thu 2/23/23	Thu 2/23/23	3897FF,3868,3869
3899	9688	NA	0%	TCO - ACADEMIC	0 days	Thu 2/23/23	Thu 2/23/23	3898,1886,2080FF
3900	9687	NA	0%	TCO - RESIDENTIAL	0 days	Tue 2/28/23	Tue 2/28/23	3899FS+3 days,3408,3327,312



February 19, 2020

*\*Revised September 23, 2020\**

Mr. Neil Hanlon, Development Associate  
Greystar  
450 Sansome Street, Suite 500  
San Francisco, California 94111

Via E-Mail: [neil.hanlon@greystar.com](mailto:neil.hanlon@greystar.com)

**Subject: UC Hastings Law Campus Housing, 198 McAllister, San Francisco, California 94102**  
**██████████ #10-36983**  
**Materials Testing and Construction Inspection Services**

Dear Mr. Hanlon:

██ is pleased to submit our cost proposal to provide materials testing and construction inspection services for the **UC Hastings Law Campus Housing project, located at 198 McAllister in San Francisco, California.** ██████████ would be proud to be part of your team, helping to ensure the construction quality and success of this project.

Following are our cost estimate and scope of services. We assembled this proposal based on the following sources:

- 50% DD Structural drawings prepared by Rutherford + Chekene, dated August 22, 2019;
- 50% DD Architectural drawings prepared by Perkins + Will, dated August 22, 2019;
- Milestone Construction schedule prepared by Build Group, dated August 26, 2020.

Thank you for giving ██████████ the opportunity to be a part of your project team. We are committed to providing our clients the very best service possible to fulfill their testing and inspection needs, and are eager to prove this commitment to you. Should you have any questions or require additional information, please do not hesitate to contact me.

Respectfully submitted,

---

Date

## SCOPE OF SERVICES

---

### **AUGER CAST PILES**

#### **Non-Shrink Grout Placement**

Our inspector's duties will include the following:

- Review mill test certifications of reinforcing steel;
- Inspect reinforcing steel of cages prior to placement in piles;
- Monitor the placement of the grout;
- Test the flow of each batch of grout using a flow cone;
- Cast cubes for compression tests at the required frequency.

#### **Compression Testing**

We will transport all samples to our laboratory for testing in strict accordance with the American Society for Testing and Materials (ASTM) requirements. Reports of compression tests will be distributed to the appropriate parties.

### **REINFORCED CONCRETE**

#### **Mix Design Review**

We will review the proposed concrete mixes in our laboratory for conformance with the specifications.

#### **Reinforcing Steel Placement**

Prior to the pours, our inspector will inspect the reinforcing steel placement to determine that it is according to plans and specifications. Our inspector will check:

- Size and spacing of bars;
- Location and length of splices;
- Clearances;
- Cleanliness of bars;
- Spacing tolerances;
- Proper support of steel with ties.

#### **Concrete Placement and Sampling**

During the pours, our inspector will be on-site continuously, as required by Code, to monitor the placement. Our inspector will:

- Determine that no bars are displaced during pouring;
- Observe cleanliness of steel;
- Determine adequacy of placement and vibratory equipment;
- Determine proper delivery rate of concrete and monitor batch times;
- Determine the correct mix is being utilized;
- Monitor slump of each truck;
- Record temperature of air and concrete;
- Cast five (4x8) cylinders for compression tests per 150 cubic yards;
- Perform air checks, if required by specifications, during concrete placement;
- Observe anchor bolt/dowel installation operations to determine hole depth, embedment and cleanliness, as well as materials and workmanship. We will inspect to determine all dowels are installed in accordance with contract documents and/or manufacturer's requirements.

### **Concrete Compression Testing**

We will transport all samples to our laboratory for compression testing in strict accordance with the American Society for Testing and Materials (ASTM) requirements. Compression test reports will be distributed to the appropriate parties.

### **POST-TENSIONED CONCRETE**

#### **Mix Design Review**

We will review the proposed concrete mixes in our laboratory for conformance with the specifications.

#### **Tendon and Reinforcing Placement**

The day before a scheduled pour, we will dispatch a qualified inspector to check the tendon and reinforcing placement for conformance to the drawings and good construction practices. Our inspector will determine that the path of strands is the same as on the approved plans, and that tendons are securely tied and placed.

#### **Concrete Placement and Sampling**

During the pours, our inspector will be on-site continuously, as required by Code, to monitor the placement. Our inspector will:

- Determine that no bars are displaced during pouring;
- Observe cleanliness of steel;
- Determine adequacy of placement and vibratory equipment;
- Determine proper delivery rate of concrete and monitor batch times;
- Determine the correct mix is being utilized;
- Monitor slump of each truck;
- Record temperature of air and concrete;
- Cast six cylinders for compression tests per 150 cubic yards;
- Perform air checks, if required by specifications, during concrete placement;
- Observe anchor bolt/dowel installation operations to determine hole depth, embedment and cleanliness, as well as materials and workmanship. We will inspect to determine all dowels are installed in accordance with contract documents and/or manufacturer's requirements.

#### **Stressing**

Continuous inspection will be required during the stressing operations. All elongations and jacking forces will be recorded as the work proceeds. Elongation measurements not within the five percent (5%) tolerance will be noted and immediately brought to the attention of the contractor, engineer and owner.

#### **Compression Testing**

We will transport all samples to our laboratory for compression testing in strict accordance with ASTM requirements. Reports of compression tests will be distributed to the appropriate parties.

### **STRUCTURAL AND MISCELLANEOUS STEEL**

#### **Shop Inspection**

- Review of welding procedure specifications;
- Material identification and mill certificate review;
- Observe the utilization of certified welders and approved welding procedures;
- Visual inspection of welding to determine compliance with contract documents;
- Nondestructive testing of moment welds and column splices;

  
Initials

\_\_\_\_\_  
CLIENT  
Initials



- Confirm approximate preheat temperature;
- Continuous inspection of multi-pass fillet welds, groove welds and reinforcing steel welding.

#### **Field Inspection**

- Observe the utilization of certified welders and approved procedures;
- Confirm approximate preheat temperature;
- Nondestructive testing of moment welds and column splices;
- Inspect to determine and observe proper installation and tightening of high strength bolts;
- Visual inspection of welding to determine compliance with contract documents;
- Continuous inspection of multi-pass fillet welds, groove welds and reinforcing steel welding.

#### **Metal Deck | Shear Studs**

Intermittent visual inspection will be conducted for metal deck and shear stud welding.

#### **High Strength Bolting**

Prior to installation, our inspector will confirm that fastener components are properly stored. Our inspector will perform pre-installation verification testing daily where applicable to confirm the suitability of the completed fastener assembly and confirm the procedure and proper use by the bolting crew of the pretensioning method to be used. A representative sample of not fewer than three complete fastener assemblies of each combination of diameter, length, grade and lot to be used shall be checked to confirm the proper pretension is achieved. Our inspector will then observe the pretensioning methods used are in accordance with the specifications and that joints are brought to a snug tight condition and then tightened systematically from the most rigid part of the joint. Our inspector will document the testing and observations performed and locations of accepted and rejected connections.

#### **EPOXY DOWELS AND ANCHORS**

As required, we will perform visual examination of dowel/anchor placement to determine dowel/anchor holes are clean, of the proper depth and diameter, and installed as specified by the manufacturer. In addition, we will perform proofload testing of the epoxy dowels/anchors at the percentage defined by the plans and specifications.

**NOTE:** These estimates assume that adequate access will be provided for performing the work at maximum production, i.e., scaffolding. Should any dowel/anchor fail, additional tests will be required per plans.

#### **FIREPROOFING**

California Building Code (CBC) 1704.12 requires thickness verification of twenty five percent (25%) of structural steel columns and primary beams on each story, and on 10 percent (10%) of secondary beams. Floor decking requires four readings per 1,000 square feet. In addition, the substrate will be verified prior to the application of all fireproofing material. Density will be checked on one beam, column and floor per 2,500 square feet of floor area in accordance with American Society for Testing and Materials (ASTM) E-605. If specified, Adhesion/Cohesion testing will be performed.

  
Initials

CLIENT  
Initials